

July 18, 2006

Mrs. Diana Whitney  
State of Utah  
Division of Oil Gas and Mining  
P.O. Box 145801  
Salt Lake City, Utah 84114-5801

RE: Application for Permit to Drill - Petro-Hunt, L.L.C.  
**Lamb Trust 31B-1-1** - 178' FNL & 2,590' FWL, NE/4 NW/4  
Section 31, T15S, R3E, SLB&M, Sanpete County, Utah

Dear Mrs. Whitney:

On behalf of Petro-Hunt, L.L.C.. (Petro-Hunt), Buys & Associates, Inc. respectfully submits the enclosed original and one copy of the Application for Permit to Drill (APD) for the above referenced fee surface and mineral vertical well. A request for exception to spacing (R649-3-2) is hereby requested based on topography since the well is located less than 460' of the drilling unit boundary. Petro-Hunt is not the only owner and operator within 460' of the proposed well. Approval of the exception location is pending at this time from Petro-Hunt. Included with the APD is the following supplemental information:

- Exhibit "A" - Survey plats, layouts and cut and fill drawing of the proposed well site;
- Exhibit "B" - Proposed location maps with access corridor;
- Exhibit "C" - Lamb Trust Surface Use Agreement (pending);
- Exhibit "D" - Drilling Plan and Drilling Procedure;
- Exhibit "E" - Surface Use Plan;
- Exhibit "F" - Typical BOP and Choke Manifold diagram.

Please accept this letter as Petro-Hunt's, written request for confidential treatment of all information contained in and pertaining to this application.

Thank you very much for your timely consideration of this application. Please feel free to contact myself or Mick Homiston of Petro-Hunt at 701-863-6622 if you have any questions or need additional information.

Sincerely,

*Don Hamilton*  
Don Hamilton  
Agent for Petro-Hunt

cc: Mick Homiston, Petro-Hunt  
Cary Vice, Petro-Hunt  
Lee Holmstead, Sanpete County

RECEIVED

JUL 20 2006

DIV. OF OIL, GAS & MINING

ORIGINAL

CONFIDENTIAL

**STATE OF UTAH**  
DEPARTMENT OF NATURAL RESOURCES  
DIVISION OF OIL, GAS AND MINING

FORM 3

AMENDED REPORT ☐  
(highlight changes)

<b>APPLICATION FOR PERMIT TO DRILL</b>				5. MINERAL LEASE NO: <b>Patented</b>	6. SURFACE: <b>Fee</b>
1A. TYPE OF WORK: <b>DRILL</b> <input checked="" type="checkbox"/> <b>REENTER</b> <input type="checkbox"/> <b>DEEPEN</b> <input type="checkbox"/>				7. IF INDIAN ALLOTTEE OR TRIBE NAME: <b>N/A</b>	
B. TYPE OF WELL: <b>OIL</b> <input checked="" type="checkbox"/> <b>GAS</b> <input type="checkbox"/> <b>OTHER</b> _____ <b>SINGLE ZONE</b> <input type="checkbox"/> <b>MULTIPLE ZONE</b> <input checked="" type="checkbox"/>				8. UNIT or CA AGREEMENT NAME: <b>N/A</b>	
2. NAME OF OPERATOR: <b>PETRO-HUNT, L.L.C.</b>				9. WELL NAME and NUMBER: <b>LAMB TRUST 31B-1-1</b>	
3. ADDRESS OF OPERATOR: <b>258 - 119th Ave. SW</b> CITY <b>Killdeer</b> STATE <b>ND</b> ZIP <b>58640</b>				10. FIELD AND POOL, OR WILDCAT: <b>Wildcat</b>	
4. LOCATION OF WELL (FOOTAGES) AT SURFACE: <b>178' FNL &amp; 2,590' FWL,</b> <i>445927X    39.474751</i> AT PROPOSED PRODUCING ZONE: <b>178' FNL &amp; 2,590' FWL,</b> <i>4369442Y    - 111.628658</i>				11. QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: <b>NENW 31 15S 3E S</b>	
14. DISTANCE IN MILES AND DIRECTION FROM NEAREST TOWN OR POST OFFICE: <b>1.02 miles south of Wales, Utah</b>				12. COUNTY: <b>Sanpete</b>	13. STATE: <b>UTAH</b>
15. DISTANCE TO NEAREST PROPERTY OR LEASE LINE (FEET) <b>64'</b>		16. NUMBER OF ACRES IN LEASE: <i>21</i>		17. NUMBER OF ACRES ASSIGNED TO THIS WELL: <b>40</b>	
18. DISTANCE TO NEAREST WELL (DRILLING, COMPLETED, OR APPLIED FOR) ON THIS LEASE (FEET) <b>None</b>		19. PROPOSED DEPTH: <b>14,700</b>		20. BOND DESCRIPTION: <b>Statewide Surety RLB0008181</b>	
21. ELEVATIONS (SHOW WHETHER DF, RT, GR, ETC.): <b>5,583' GR</b>		22. APPROXIMATE DATE WORK WILL START: <b>9/6/2006</b>		23. ESTIMATED DURATION: <b>90 days</b>	

24. PROPOSED CASING AND CEMENTING PROGRAM							
SIZE OF HOLE	CASING SIZE, GRADE, AND WEIGHT PER FOOT			SETTING DEPTH	CEMENT TYPE, QUANTITY, YIELD, AND SLURRY WEIGHT		
26"	20"	.25" w.t.		80	Ready mix to surface		
17-1/2"	13-3/8"	J55	54.5#	2,300	50/50 Poz & Premium	950/485 sx	1.98/1.16    12.5/15.8
12-1/4"	9-5/8"	P110	53.5#	7,850	50/50 Poz	1555 sx	1.71    13.0
8-1/2"	7-5/8"	Q125	39.0#	11,200	50/50 Poz	480 sx	1.24    14.35
6-1/2"	5-1/2"	L80	20.0#	14,700	50/50 Poz	300 sx	1.43    14.3

25. ATTACHMENTS	
VERIFY THE FOLLOWING ARE ATTACHED IN ACCORDANCE WITH THE UTAH OIL AND GAS CONSERVATION GENERAL RULES:	
<input checked="" type="checkbox"/> WELL PLAT OR MAP PREPARED BY LICENSED SURVEYOR OR ENGINEER <input type="checkbox"/> EVIDENCE OF DIVISION OF WATER RIGHTS APPROVAL FOR USE OF WATER	<input checked="" type="checkbox"/> COMPLETE DRILLING PLAN <input type="checkbox"/> FORM 5, IF OPERATOR IS PERSON OR COMPANY OTHER THAN THE LEASE OWNER

**CONFIDENTIAL**

NAME (PLEASE PRINT) Don Hamilton    TITLE Agent for Petro-Hunt, L.L.C

SIGNATURE Don Hamilton    DATE 7/18/2006


(This space for State use only)

API NUMBER ASSIGNED: 43-03930034

APPROVAL:

**ORIGINAL**  
**RECEIVED**  
**JUL 20 2006**  
DIV. OF OIL, GAS & MINING

# Section 31, T.15 S., R.3 E., S.L.B. & M.



## BASIS OF BEARINGS

BASIS OF BEARING USED WAS N89°20'01"E BETWEEN THE SOUTHWEST CORNER AND THE SOUTHEAST CORNER OF SECTION 31, T.15 S., R.3 E., S.L.B. & M.  
 LATITUDE = 39°28'28.94106" (38.474705850) NAD 83  
 LONGITUDE = -111°37'45.27788" (-111.629243856) NAD 83

## PROJECT Petro-Hunt, L.L.C.

WELL LOCATION, LOCATED AS SHOWN IN THE N.E. 1/4 OF THE N.W. 1/4 OF SECTION 31, T.15 S., R.3 E., S.L.B. & M. SANPETE COUNTY, UTAH

## LEGEND

- ✕ = SECTION CORNERS (LOCATED)
- ✕ = QUARTER SECTION CORNERS (LOCATED)
- ✕ = SECTION CORNERS (NOT LOCATED)
- ✕ = QUARTER SECTION CORNERS (NOT LOCATED)
- ⊙ = PROPOSED WELL HEAD

NOTE: THE PURPOSE OF THIS SURVEY WAS TO PLAT THE PETRO-HUNT, L.L.C. LAMB TRUST #31B-1-1 LOCATION. LOCATED IN THE N.E. 1/4 OF THE N.W. 1/4 OF SECTION 31, T.15 S., R.3 E., S.L.B. & M., SANPETE COUNTY, UTAH.


## BASIS OF ELEVATION

ELEVATION BASED ON THE SOUTHWEST CORNER OF SECTION 6, T.16 S., R.3 E., S.L.B. & M. WHICH IS A SANPETE COUNTY ALUM CAP WITH AN ELEVATION OF 5559.00'.



## CERTIFICATE

THIS IS TO CERTIFY THAT THIS PLAT WAS PREPARED FROM FIELD NOTES OF ACTUAL SURVEYS MADE BY ME OR UNDER MY SUPERVISION, AND THAT THE SAME ARE TRUE AND CORRECT TO THE BEST OF MY KNOWLEDGE AND BELIEF.



**Jones & DeMille Engineering**  
 1535 South 100 West - Richfield, Utah 84701  
 Phone (435) 896-8268  
 Fax (435) 896-8268  
 www.jonesanddemille.com

## Well Location Plat for

**Petro-Hunt, L.L.C. Lamb Trust #31B-1-1**

DESIGNED	SURVEYED	CHECKED	DRAWN	PROJECT NO.	SHEET NO.
-	T.W.G.	T.R.G.	T.R.G.	0806-130	1
DATE		DWG. NAME	SCALE		
06/22/06		WELL_LOC..	1"=1000'		

**STATE OF UTAH**  
DEPARTMENT OF NATURAL RESOURCES  
DIVISION OF OIL, GAS AND MINING

FORM 3

AMENDED REPORT ☐  
(highlight changes)

<b>APPLICATION FOR PERMIT TO DRILL</b>				5. MINERAL LEASE NO: <b>Patented</b>	6. SURFACE: <b>Fee</b>
1A. TYPE OF WORK: <b>DRILL</b> <input checked="" type="checkbox"/> <b>REENTER</b> <input type="checkbox"/> <b>DEEPEN</b> <input type="checkbox"/>				7. IF INDIAN, ALLOTTEE OR TRIBE NAME: <b>N/A</b>	
8. TYPE OF WELL: <b>OIL</b> <input checked="" type="checkbox"/> <b>GAS</b> <input type="checkbox"/> <b>OTHER</b> _____ <b>SINGLE ZONE</b> <input type="checkbox"/> <b>MULTIPLE ZONE</b> <input checked="" type="checkbox"/>				8. UNIT or CA AGREEMENT NAME: <b>N/A</b>	
2. NAME OF OPERATOR: <b>PETRO-HUNT, L.L.C.</b>				9. WELL NAME and NUMBER: <b>LAMB TRUST 31B-1-1</b>	
3. ADDRESS OF OPERATOR: <b>258 - 119th Ave. SW</b> CITY <b>Killdeer</b> STATE <b>ND</b> ZIP <b>58640</b>				10. FIELD AND POOL, OR WILDCAT: <b>Wildcat</b>	
4. LOCATION OF WELL (FOOTAGES) AT SURFACE: <b>178' FNL &amp; 2,590' FWL,</b> <i>445927X    39.474751</i> AT PROPOSED PRODUCING ZONE: <b>178' FNL &amp; 2,590' FWL,</b> <i>4369442Y    - 111.628658</i>				11. QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: <b>NENW 31 15S 3E S</b>	
14. DISTANCE IN MILES AND DIRECTION FROM NEAREST TOWN OR POST OFFICE: <b>1.02 miles south of Wales, Utah</b>				12. COUNTY: <b>Sanpete</b>	
15. DISTANCE TO NEAREST PROPERTY OR LEASE LINE (FEET) <b>64'</b>				17. NUMBER OF ACRES ASSIGNED TO THIS WELL: <b>40</b>	
16. NUMBER OF ACRES IN LEASE: <b>21</b>				20. BOND DESCRIPTION: <b>Statewide Surety RLB0008181</b>	
18. DISTANCE TO NEAREST WELL (DRILLING, COMPLETED, OR APPLIED FOR) ON THIS LEASE (FEET) <b>None</b>				22. APPROXIMATE DATE WORK WILL START: <b>9/6/2006</b>	
21. ELEVATIONS (SHOW WHETHER DF, RT, GR, ETC.): <b>5,583' GR</b>				23. ESTIMATED DURATION: <b>90 days</b>	

24. PROPOSED CASING AND CEMENTING PROGRAM							
SIZE OF HOLE	CASING SIZE, GRADE, AND WEIGHT PER FOOT			SETTING DEPTH	CEMENT TYPE, QUANTITY, YIELD, AND SLURRY WEIGHT		
26"	20" .25" w.t.			80	Ready mix to surface		
17-1/2"	13-3/8"	J55	54.5#	2,300	50/50 Poz & Premium	950/485 sx	1.98/1.16    12.5/15.8
12-1/4"	9-5/8"	P110	53.5#	7,850	50/50 Poz	1555 sx	1.71    13.0
8-1/2"	7-5/8"	Q125	39.0#	11,200	50/50 Poz	480 sx	1.24    14.35
6-1/2"	5-1/2"	L80	20.0#	14,700	50/50 Poz	300 sx	1.43    14.3

25. ATTACHMENTS	
VERIFY THE FOLLOWING ARE ATTACHED IN ACCORDANCE WITH THE UTAH OIL AND GAS CONSERVATION GENERAL RULES:  <input checked="" type="checkbox"/> WELL PLAT OR MAP PREPARED BY LICENSED SURVEYOR OR ENGINEER <input type="checkbox"/> EVIDENCE OF DIVISION OF WATER RIGHTS APPROVAL FOR USE OF WATER	<input checked="" type="checkbox"/> COMPLETE DRILLING PLAN <input type="checkbox"/> FORM 5, IF OPERATOR IS PERSON OR COMPANY OTHER THAN THE LEASE OWNER

**CONFIDENTIAL**

NAME (PLEASE PRINT) <u>Don Hamilton</u>	TITLE <u>Agent for Petro-Hunt, L.L.C</u>
SIGNATURE <u>Don Hamilton</u>	DATE <u>7/18/2006</u>

(This space for State use only)

API NUMBER ASSIGNED: 43-039 30034

APPROVAL:


**ORIGINAL**  
**RECEIVED**

**JUL 20 2006**

DIV. OF OIL, GAS & MINING



# Section 31, T.15 S., R.3 E., S.L.B. & M.



## BASIS OF BEARINGS

BASIS OF BEARING USED WAS N89°20'01"E BETWEEN THE SOUTHWEST CORNER AND THE SOUTHEAST CORNER OF SECTION 31, T.15 S., R.3 E., S.L.B. & M.  
 LATITUDE = 39°28'28.94106" (38.474705850) NAD 83  
 LONGITUDE = -111°37'45.27788" (-111.629243856) NAD 83

## PROJECT Petro-Hunt, L.L.C.

WELL LOCATION, LOCATED AS SHOWN IN THE N.E. 1/4 OF THE N.W. 1/4 OF SECTION 31, T.15 S., R.3 E., S.L.B. & M. SANPETE COUNTY, UTAH

## LEGEND

- ✕ = SECTION CORNERS (LOCATED)
- ✕ = QUARTER SECTION CORNERS (LOCATED)
- ✕ = SECTION CORNERS (NOT LOCATED)
- ✕ = QUARTER SECTION CORNERS (NOT LOCATED)
- ⊙ = PROPOSED WELL HEAD

NOTE: THE PURPOSE OF THIS SURVEY WAS TO PLAT THE PETRO-HUNT, L.L.C. LAMB TRUST #31B-1-1 LOCATION. LOCATED IN THE N.E. 1/4 OF THE N.W. 1/4 OF SECTION 31, T.15 S., R.3 E., S.L.B. & M., SANPETE COUNTY, UTAH.


## BASIS OF ELEVATION

ELEVATION BASED ON THE SOUTHWEST CORNER OF SECTION 6, T.16 S., R.3 E., S.L.B. & M. WHICH IS A SANPETE COUNTY ALUM CAP WITH AN ELEVATION OF 5559.00'.



## CERTIFICATE

THIS IS TO CERTIFY THAT THIS PLAT WAS PREPARED FROM FIELD NOTES OF ACTUAL SURVEYS MADE BY ME OR UNDER MY SUPERVISION, AND THAT THE SAME ARE TRUE AND CORRECT TO THE BEST OF MY KNOWLEDGE AND BELIEF.




**Jones & DeMille Engineering**  
 1535 South 100 West - Richfield, Utah 84701  
 Phone (435) 896-8268  
 Fax (435) 896-8268  
 www.jonesanddemille.com

## Well Location Plat for

**Petro-Hunt, L.L.C. Lamb Trust #31B-1-1**

DESIGNED	SURVEYED	CHECKED	DRAWN	PROJECT NO.	SHEET NO.
-	T.W.G.	T.R.G.	T.R.G.	0606-130	1
DATE		DWG NAME	SCALE		
06/22/06		WELL LOC.	1"=1000'		



**Petro-Hunt, L.L.C. Lamb Trust #31B-1-1**  
**Section 31, T.15 S., R.3 E., S.L.B. & M.**  
**178' FNL 2590' FWL**



**Jones & DeMille Engineering**

1535 South 100 West - Richfield, Utah 84701  
 Phone (435) 896-8266 Fax (435) 896-8268  
[www.jonesanddemille.com](http://www.jonesanddemille.com)



SCALE: 1" = 2000'

Petro-Hunt, L.L.C.

FIGURE: 1

Lamb Trust #31B-1-1

Vicinity Map

DRAWN: T.W.G. 06/22/06

PEN TBL: 1stndrd-hp2600.ctb

PROJECT: 0606-130

SHEET:


CHECK: T.R.G. 06/22/06

FILE: VICINITY

LAST UPDATE: 6/22/2006

1

Casing Schematic



Well name:

**2006-11 Petro Hunt Lamb Trust 31B-1-1**Operator: **Petro-Hunt L.L.C.**String type: **Surface**

Project ID:

43-039-30034

Location: **Sanpete County****Design parameters:****Collapse**

Mud weight: 9.000 ppg

Design is based on evacuated pipe.

**Minimum design factors:****Collapse:**

Design factor 1.125

**Burst:**

Design factor 1.00

**Environment:**

H2S considered? No

Surface temperature: 75 °F

Bottom hole temperature: 107 °F

Temperature gradient: 1.40 °F/100ft

Minimum section length: 250 ft

Cement top: 490 ft

**Burst**

Max anticipated surface

pressure: 2,024 psi

Internal gradient: 0.120 psi/ft

Calculated BHP 2,300 psi

No backup mud specified.

**Tension:**

8 Round STC: 1.80 (J)

8 Round LTC: 1.80 (J)

Buttress: 1.60 (J)

Premium: 1.50 (J)

Body yield: 1.50 (B)

Tension is based on buoyed weight.

Neutral point: 1,994 ft

**Non-directional string.****Re subsequent strings:**

Next setting depth: 7,850 ft

Next mud weight: 10.800 ppg

Next setting BHP: 4,404 psi

Fracture mud wt: 19.250 ppg

Fracture depth: 2,300 ft

Injection pressure: 2,300 psi

Run Seq	Segment Length (ft)	Size (in)	Nominal Weight (lbs/ft)	Grade	End Finish	True Vert Depth (ft)	Measured Depth (ft)	Drift Diameter (in)	Internal Capacity (ft³)
1	2300	13.375	54.50	J-55	ST&C	2300	2300	12.49	1996.3
Run Seq	Collapse Load (psi)	Collapse Strength (psi)	Collapse Design Factor	Burst Load (psi)	Burst Strength (psi)	Burst Design Factor	Tension Load (Kips)	Tension Strength (Kips)	Tension Design Factor
1	1075	1130	1.051 ✓	2300	2730	1.19 ✓	109	514	4.73 J ✓

Prepared Helen Sadik-Macdonald  
by: Div of Oil, Gas & MineralsPhone: 801-538-5357  
FAX: 801-359-3940Date: November 1, 2006  
Salt Lake City, Utah**Remarks:**

Collapse is based on a vertical depth of 2300 ft, a mud weight of 9 ppg. The casing is considered to be evacuated for collapse purposes. Collapse strength is based on the Westcott, Dunlop &amp; Kemler method of biaxial correction for tension.

Burst strength is not adjusted for tension.

*Engineering responsibility for use of this design will be that of the purchaser.*

Well name:

**2006-11 Petro Hunt Lamb Trust 31B-1-1**Operator: **Petro-Canada Resources (USA)**

String type: Intermediate

Project ID:

43-039-30034

Location: Sanpete County

**Design parameters:****Collapse**

Mud weight: 10.800 ppg

Design is based on evacuated pipe.

**Minimum design factors:****Collapse:**

Design factor 1.125

**Burst:**

Design factor 1.00

**Environment:**

H2S considered? No

Surface temperature: 75 °F

Bottom hole temperature: 185 °F

Temperature gradient: 1.40 °F/100ft

Minimum section length: 1,500 ft

Cement top: 3,243 ft

**Burst**

Max anticipated surface pressure:

3,354 psi

Internal gradient: 0.220 psi/ft

Calculated BHP 5,081 psi

No backup mud specified.

**Tension:**

8 Round STC: 1.80 (J)

8 Round LTC: 1.80 (J)

Buttress: 1.60 (J)

Premium: 1.50 (J)

Body yield: 1.50 (B)

Tension is based on buoyed weight.

Neutral point: 6,570 ft

**Non-directional string.****Re subsequent strings:**

Next setting depth: 11,200 ft

Next mud weight: 10.000 ppg

Next setting BHP: 5,818 psi

Fracture mud wt: 19.250 ppg

Fracture depth: 7,850 ft

Injection pressure: 7,850 psi

Run Seq	Segment Length (ft)	Size (in)	Nominal Weight (lbs/ft)	Grade	End Finish	True Vert Depth (ft)	Measured Depth (ft)	Drift Diameter (in)	Internal Capacity (ft³)
1	7850	9.625	53.50	P-110	LT&C	7850	7850	8.5	3118.9
Run Seq	Collapse Load (psi)	Collapse Strength (psi)	Collapse Design Factor	Burst Load (psi)	Burst Strength (psi)	Burst Design Factor	Tension Load (Kips)	Tension Strength (Kips)	Tension Design Factor
1	4404	7950	1.805 ✓	5081	10900	2.15 ✓	352	1422	4.05 J ✓

Prepared Helen Sadik-Macdonald  
by: Div of Oil, Gas & MineralsPhone: 801-538-5280  
FAX: 801-359-3940Date: November 1, 2006  
Salt Lake City, Utah**Remarks:**

Collapse is based on a vertical depth of 7850 ft, a mud weight of 10.8 ppg. The casing is considered to be evacuated for collapse purposes. Collapse strength is based on the Westcott, Dunlop &amp; Kemler method of biaxial correction for tension.

Burst strength is not adjusted for tension.

*Engineering responsibility for use of this design will be that of the purchaser.*

Well name:	<b>2006-11 Petro Hunt Lamb Trust 31B-1-1</b>	
Operator:	<b>Petro-Canada Resources (USA)</b>	
String type:	<b>Drilling Liner</b>	Project ID: 43-039-30034
Location:	<b>Sanpete County</b>	

**Design parameters:**
**Collapse**

Mud weight: 10.000 ppg  
Design is based on evacuated pipe.

**Minimum design factors:**
**Collapse:**

Design factor 1.125

**Burst:**

Design factor 1.00

**Environment:**

H2S considered? No  
Surface temperature: 75 °F  
Bottom hole temperature: 232 °F  
Temperature gradient: 1.40 °F/100ft  
Minimum section length: 1,500 ft

Cement top: 7,841 ft

Liner top: 7,350 ft

**Non-directional string.**
**Burst**

Max anticipated surface pressure: 4,402 psi  
Internal gradient: 0.220 psi/ft  
Calculated BHP 6,866 psi

No backup mud specified.

**Tension:**

8 Round STC: 1.80 (J)  
8 Round LTC: 1.80 (J)  
Buttress: 1.60 (J)  
Premium: 1.50 (J)  
Body yield: 1.50 (B)

Tension is based on buoyed weight.

Neutral point: 10,634 ft

**Re subsequent strings:**

Next setting depth: 14,700 ft  
Next mud weight: 10.000 ppg  
Next setting BHP: 7,636 psi  
Fracture mud wt: 19.250 ppg  
Fracture depth: 11,200 ft  
Injection pressure: 11,200 psi

Run Seq	Segment Length (ft)	Size (in)	Nominal Weight (lbs/ft)	Grade	End Finish	True Vert Depth (ft)	Measured Depth (ft)	Drift Diameter (in)	Internal Capacity (ft³)
1	3800	7.625	39.00	Q-125	HD-L	11200	11200	6.5	909.7
Run Seq	Collapse Load (psi)	Collapse Strength (psi)	Collapse Design Factor	Burst Load (psi)	Burst Strength (psi)	Burst Design Factor	Tension Load (Kips)	Tension Strength (Kips)	Tension Design Factor
1	5818	12060	2.073 ✓	6866	14340	2.09 ✓	126	867	6.88 J ✓

Prepared by: Helen Sadik-Macdonald  
Div of Oil, Gas & Minerals

Phone: 801-538-5280  
FAX: 801-359-3940

Date: November 1, 2006  
Salt Lake City, Utah

**Remarks:**

For this liner string, the top is rounded to the nearest 100 ft. Collapse is based on a vertical depth of 11200 ft, a mud weight of 10 ppg. The Collapse strength is based on the Westcott, Dunlop & Kemler method of biaxial correction for tension.

Burst strength is not adjusted for tension.

*Engineering responsibility for use of this design will be that of the purchaser.*

Well name:	<b>2006-11 Petro Hunt Lamb Trust 31B-1-1</b>		
Operator:	<b>Petro-Canada Resources (USA)</b>		
String type:	Production	Project ID:	43-039-30034
Location:	Sanpete County		

**Design parameters:**
**Collapse**

Mud weight: 10.000 ppg  
Design is based on evacuated pipe.

**Minimum design factors:**
**Collapse:**

Design factor 1.125

**Burst:**

Design factor 1.00

**Environment:**

H2S considered? No  
Surface temperature: 75 °F  
Bottom hole temperature: 281 °F  
Temperature gradient: 1.40 °F/100ft  
Minimum section length: 1,500 ft

Cement top: 11,242 ft

**Burst**

Max anticipated surface pressure: 4,402 psi  
Internal gradient: 0.220 psi/ft  
Calculated BHP 7,636 psi

No backup mud specified.

**Tension:**

8 Round STC: 1.80 (J)  
8 Round LTC: 1.80 (J)  
Buttress: 1.60 (J)  
Premium: 1.50 (J)  
Body yield: 1.50 (B)

**Non-directional string.**

Tension is based on buoyed weight.  
Neutral point: 12,475 ft

Run Seq	Segment Length (ft)	Size (in)	Nominal Weight (lbs/ft)	Grade	End Finish	True Vert Depth (ft)	Measured Depth (ft)	Drift Diameter (in)	Internal Capacity (ft³)
1	14700	5.5	20.00	L-80	Buttress	14700	14700	4.653	1830.4
Run Seq	Collapse Load (psi)	Collapse Strength (psi)	Collapse Design Factor	Burst Load (psi)	Burst Strength (psi)	Burst Design Factor	Tension Load (Kips)	Tension Strength (Kips)	Tension Design Factor
1	7636	8830	1.156 ✓	7636	8990	1.18 ✓	249	466	1.87 B ✓

Prepared Helen Sadik-Macdonald  
by: Div of Oil, Gas & Minerals

Phone: 801-538-5280  
FAX: 801-359-3940

Date: November 1, 2006  
Salt Lake City, Utah

**Remarks:**

Collapse is based on a vertical depth of 14700 ft, a mud weight of 10 ppg. The casing is considered to be evacuated for collapse purposes. Collapse strength is based on the Westcott, Dunlop & Kemler method of biaxial correction for tension.

Burst strength is not adjusted for tension.

*Engineering responsibility for use of this design will be that of the purchaser.*





57

T15S R2E T15S R3E

LAMB TURST 31B-1-1



LAMB TRUST 31-6



31

T16S R2E T16S R3E

DYE 1



OPERATOR: PETRO-HUNT LLC (N2815)

SEC: 31 T.15S R. 3E

FIELD: WILDCAT (001)

COUNTY: SANPETE

SPACING: R649-3-3 / EXCEPTION LOCATION

#### Field Status


- ABANDONED
- ACTIVE
- COMBINED
- INACTIVE
- PROPOSED
- STORAGE
- TERMINATED

#### Unit Status

- EXPLORATORY
- GAS STORAGE
- NF PP OIL
- NF SECONDARY
- PENDING
- PI OIL
- PP GAS
- PP GEOTHERML
- PP OIL
- SECONDARY
- TERMINATED

#### Wells Status

- GAS INJECTION
- GAS STORAGE
- LOCATION ABANDONED
- NEW LOCATION
- PLUGGED & ABANDONED
- PRODUCING GAS
- PRODUCING OIL
- SHUT-IN GAS
- SHUT-IN OIL
- TEMP. ABANDONED
- TEST WELL
- WATER INJECTION
- WATER SUPPLY
- WATER DISPOSAL
- DRILLING



Utah Oil Gas and Mining



PREPARED BY: DIANA WHITNEY  
DATE: 04-AUGUST-2006

# Application for Permit to Drill

## Statement of Basis

10/10/2006

Utah Division of Oil, Gas and Mining

Page 1

<b>APD No</b>	<b>API WellNo</b>	<b>Status</b>	<b>Well Type</b>	<b>Surf Ownr</b>	<b>CBM</b>
63	43-039-30034-00-00		OW	P	No
<b>Operator</b>	PETRO-HUNT, LLC	<b>Surface Owner-APD</b>			
<b>Well Name</b>	LAMB TURST 31B-1-1	<b>Unit</b>			
<b>Field</b>	WILDCAT	<b>Type of Work</b>			
<b>Location</b>	NENW 31 15S 3E S 0 F L 0 F L	<b>GPS Coord (UTM)</b>	445927E	4369280N	

### Geologic Statement of Basis

This location is placed just to the east of the south central portion of the Gunnison Plateau area, near the extreme western edge of the Colorado Plateau physiographic province in western central Utah. Some people have characterized this area as being in the Basin and Range - Colorado Plateau transition zone. It is otherwise characterized as being astride the Sevier Overthrust Belt. The location is on fee land just within a mile to the south of Wales, Utah, and about 1.5 miles west of the San Pitch River in Sanpete County. This location falls about a mile east of the plateau-bounding Wales-Gunnison backthrust fault. A well at this location will spud into a moderately permeable soil developed on Quaternary/Tertiary Coalesced Fan deposits. It is uncertain what strata lie beneath these deposits and no prognosticated tops, other than the Navajo Sandstone pay, are prognosticated by the Operator. Nearly a mile to the west, the nearest mapped exposures below the coalesced fan deposits are of the Jurassic Twist Gulch Formation. The area is in a secondary recharge area about 0.5 mile west of the transition to a valley fill discharge area. Considerable agricultural irrigation is occurring nearby. A significant near surface quality ground water resource exists in this valley with artesian wells within a mile of the location. Aquifers with drinking water quality [600 to 700 mg/l Total Dissolved Solids (TDS)] ground water resources are likely to be encountered. A P&A'd well, about 1.2 miles southeast, encountered two water sands within the first 50' of 24" conductor casing hole. Many underground water rights have been filed within a mile of the location, with wells drilled as deep as 365'. Division personnel have described nearby water wells as being thermal and having 400 to 600 pounds formation pressure. The hole will be drilled with a fresh water and gel mud system to 2,300' TD to set the 13 3/8" surface casing. Formation tops from some nearby P&A'd wells indicate that this may be a reasonable Surface Casing seat into the Arapien Shale if diapiric flow is encountered along the backthrust fault. The intermediate hole will be drilled with a saturated salt mud system. It is anticipated that this mud system is designed to deal with the evaporites of the Arapien Shale. Any water encountered in the Arapien Shale is likely to be of poor quality. A Division of Water Rights publication notes that aquifers in close proximity to the Arapien Shale are also likely to contain ground water with high TDS levels. It is not known where the Base of Moderately Saline Ground Water is but it is not unreasonable to expect a rapid transition from the better quality resource near the surface to ground water with considerably higher Total Dissolved Solids concentrations around Surface Casing depth. A casing, cementing and drilling fluid program as described above should be sufficient to control and isolate the poor quality ground waters expected to be encountered at that depth in a well at this location if sufficient good quality cement is placed to overlap the Surface and Intermediate Casing strings.

Chris Kierst  
APD Evaluator

10/5/2006  
Date / Time

### Surface Statement of Basis

Participating in the pre-site evaluation were; M. Jones (UDOGM), John Wunderlick, Ray Lewis (Petro-Hunt), Ron Lamb and Marie Lamb as well as Jeff Lamb (surface ownership representation). Location is staked ~1.0 mile south of Wales, Utah. The location is planned and staked to be built on 2 adjacent parcels of property. The landowners of the west parcel (where the wellbore will be located) is the Ben Glade Lamb Family Living Trust, represented by Jeff Lamb. The east parcel is owned by Ron Lamb. The fence currently separating the two parcels will be re-routed around the bottom of the location (to the east). Both landowners are in agreement and cooperation with the operator on this matter. The properties are both used for grazing cattle and other

---

# **Application for Permit to Drill**

## **Statement of Basis**

### **Utah Division of Oil, Gas and Mining**

---

10/10/2006

Page 2

agricultural activities. Based on the pit evaluation ranking and score the reserve pit will be required to be lined.

Mark Jones  
**Onsite Evaluator**

9/6/2006  
**Date / Time**

#### **Conditions of Approval / Application for Permit to Drill**

<b>Category</b>	<b>Condition</b>
Pits	A synthetic liner with a minimum thickness of 12 mils shall be properly installed and maintained in the reserve pit.
Surface	The reserve pit shall be fenced upon completion of drilling operations.
Surface	Drainages adjacent to the proposed pad shall be diverted around the location.

# **ON-SITE PREDRILL EVALUATION**

## **Utah Division of Oil, Gas and Mining**

**Operator** PETRO-HUNT, LLC  
**Well Name** LAMB TURST 31B-1-1  
**API Number** 43-039-30034-0 **APD No** 63 **Field/Unit** WILDCAT  
**Location:** 1/4,1/4 NENW **Sec** 31 **Tw** 15S **Rng** 3E 0 FL 0 FL  
**GPS Coord (UTM)** 445943 4369279 **Surface Owner**

### **Participants**

M. Jones (UDOGM), John Wunderlick, Ray Lewis (Petro-Hunt), Ron Lamb and Marie Lamb as well as Jeff Lamb (surface ownership representation).

### **Regional/Local Setting & Topography**

Location is staked ~1.0 mile south of Wales, Utah. The location is planned and staked to be built on 2 adjacent parcels of property. The landowners of the west parcel (where the wellbore will be located) is the Ben Glade Lamb Family Living Trust, represented by Jeff Lamb. The east parcel is owned by Ron Lamb. The fence currently separating the two parcels will be re-routed around the bottom of the location (to the east). Both landowners are in agreement and cooperation with the operator on this matter. The properties are both used for grazing cattle and other agricultural activities.

### **Surface Use Plan**

#### **Current Surface Use**

Agricultural  
Grazing

#### **New Road**

Miles	Well Pad		Src Const Material	Surface Formation
0	Width 300	Length 430	Onsite	

**Ancillary Facilities** N

### **Waste Management Plan Adequate?**

### **Environmental Parameters**

#### **Affected Floodplains and/or Wetland Y**

small dry wash drainages begin to develop near proposed location.

#### **Flora / Fauna**

Sagebrush / June grass community.

#### **Soil Type and Characteristics**

clay loam

**Erosion Issues** N

**Sedimentation Issues** N

**Site Stability Issues** N

#### **Drainage Diversion Required Y**

all drainages should be diverted away from wellpad.

**Berm Required?** N

**Erosion Sedimentation Control Required?** N

**Paleo Survey Run?** N

**Paleo Potential Observed?** N

**Cultural Survey Run?** N

**Cultural Resources?** N

**Reserve Pit**

**Site-Specific Factors**

**Site Ranking**

<b>Distance to Groundwater (feet)</b>	>200	0
<b>Distance to Surface Water (feet)</b>	>1000	0
<b>Dist. Nearest Municipal Well (ft)</b>	1320 to 5280	5
<b>Distance to Other Wells (feet)</b>	300 to 1320	10
<b>Native Soil Type</b>	Mod permeability	10
<b>Fluid Type</b>	TDS>10000	15
<b>Drill Cuttings</b>	Salt or Detrimental	10
<b>Annual Precipitation (inches)</b>	10 to 20	5
<b>Affected Populations</b>	>50	10
<b>Presence Nearby Utility Conduits</b>	Unknown	10

**Final Score** 75 1 **Sensitivity Level**

**Characteristics / Requirements**

dugout earthen (90' x 205' x 14'). Lined.

**Closed Loop Mud Required?** N

**Liner Required?** Y

**Liner Thickness** 12

**Pit Underlayment Required?** N

**Other Observations / Comments**

Mark Jones  
**Evaluator**

9/6/2006  
**Date / Time**



[Online Services](#)

[Agency List](#)

[Business](#)




Search Utah.gov [GO](#)

# UTAH DIVISION OF WATER RIGHTS

## WRPLAT Program Output Listing

Version: 2004.12.30.00      Rundate: 10/05/2006 05:40 PM

Radius search of 5280 feet from a point S712 E2584 from the NW corner, section 31, Township 15S, Range 3E, SL b&m Criteria:wrtypes=W,C,E  
podtypes=all status=U,A,P usetypes=all



### Water Rights


WR Number	Diversion Type/Location	Well Log	Status	Priority	Uses	CFS	ACFT	Owner Name
<u>65-1612</u>	Underground S103 W200 N4 32 15S 3E SL	<u>well info</u>	P	19690324	S	0.009	0.000	GRETA M. DAVIS P.O. BOX 4262
<u>65-1853</u>	Underground N2374 E1154 SW 30 15S 3E SL		P	19760601	IS	0.015	0.000	ROBERT R. JACKMAN P.O. BOX 647
<u>65-1890</u>	Underground N970 E1440 SW 30 15S 3E SL		P	19770325	DIS	0.015	0.000	P.S.A. AND SONS INCORPORATED C/O PAUL D. ANDERSON (MANAGER)
<u>65-202</u>	Underground S495 W66 NE 31 15S 3E SL		P	19520505	S	0.015	0.000	LOUIS U. MUMFORD WALES UT 84667
<u>65-204</u>	Underground N1073 E2393 SW 32 15S 3E SL		P	19520515	S	0.015	0.000	LAWRENCE THOMAS WALES UT 84667
<u>65-206</u>	Underground N571 E1332 SW 32 15S 3E SL		P	19520522	S	0.015	0.000	H. RICHARD THOMAS SANTA ROSA CA
<u>65-208</u>	Underground N1716 W2574 SE 31 15S 3E SL		P	19520710	S	0.015	0.000	NEWEL F. REESE WALES UT 84667
<u>65-231</u>	Underground N165 W66 SE 31 15S 3E SL		P	19530526	S	0.015	0.000	RALPH WASHBURN WALES UT 84667
<u>65-232</u>	Underground N1155 E990 SW 29 15S 3E SL		P	19530606	S	0.015	0.000	LLOYD PRICE WALES UT 84667
<u>65-236</u>	Underground N1485 0 SW 29 15S 3E SL		P	19530925	S	0.015	0.000	LLOYD PRICE WALES UT 84667
<u>65-2535</u>	Underground	<u>well info</u>	P	18580000	IMS	0.410	47.250	TOWN OF WALES



	N3332 E2559 SW 30 15S 3E SL					P.O. BOX 4262
<a href="#">65-2747</a>	Underground	<a href="#">well info</a>	A	19960821 DIS	0.015 0.000	KARL S. AND LESLIE CLAWSON
	N1450 E250 SW 30 15S 3E SL					P.O. BOX 4235
<a href="#">65-278</a>	Underground		P	19550910 S	0.015 0.000	DAVID C. REES
	N165 W660 SE 30 15S 3E SL					WALES UT 84667
<a href="#">65-318</a>	Underground		P	19580129 D	0.015 0.000	NEWEL FRANK AND EUNICE L. REES
	S3465 E2640 NW 30 15S 3E SL					94 W. 100 N.
<a href="#">65-963</a>	Underground		P	19000000 DS	0.004 0.000	MILTON BEAL
	S482 W678 N4 05 16S 3E SL					C/O JOHN S. BEAL
<a href="#">a26018</a>	Underground	<a href="#">well info</a>	A	20011004 O	0.003 0.500	KARL AND LESLIE CLAWSON
	N400 E700 SW 30 15S 3E SL					P.O. BOX 4235
<a href="#">a28852</a>	Underground	<a href="#">well info</a>	A	20040409 DI	0.002 1.000	CECIL AND LIZ CLAWSON
	N1815 W100 SE 36 15S 2E SL					P.O. BOX 4191

[Natural Resources](#) | [Contact](#) | [Disclaimer](#) | [Privacy Policy](#) | [Accessibility Policy](#)

**STATE ACTIONS**  
**Resource Development Coordinating Committee**  
**Governor's Office of Planning and Budget**  
**5110 State Office Building**  
**SLC, UT 84114**  
**Phone No. 537-9230**

<b>1. State Agency</b> Oil, Gas and Mining 1594 West North Temple, Suite 1210 Salt Lake City, UT 84114-5801	<b>2. Approximate date project will start:</b>  Upon Approval or August 18, 2006
<b>3. Title of proposed action:</b> Application for Permit to Drill	
<b>4. Description of Project:</b>  Petro-Hunt, LLC proposes to drill the Lamb Trust 31B-1-1 well (wildcat) on a Fee lease Fee, Sanpete County, Utah. This action is being presented to the RDCC for consideration of resource issues affecting state interests. The Division of Oil, Gas and Mining is the primary administrative agency in this action and must issue approval before operations commence.	
<b>5. Location and detailed map of land affected (site location map required, electronic GIS map preferred)</b> (include UTM coordinates where possible) <b>(indicate county)</b> 178' FNL 2590' FWL, NE/4 NW/4, Section 31, Township 15 South, Range 3 East, Sanpete County, Utah	
<b>6. Possible significant impacts likely to occur:</b> Surface impacts include up to five acres of surface disturbance during the drilling and completion phase (estimated for five weeks duration). If oil and gas in commercial quantities is discovered, the location will be reclaimed back to a net disturbance of between one and two acres – not including road, pipeline, or utility infrastructure. If no oil or gas is discovered, the location will be completely reclaimed.	
<b>7. Identify local government affected</b> a. Has the government been contacted? No. b. When? c. What was the response? d. If no response, how is the local government(s) likely to be impacted?	
<b>8. For acquisitions of land or interests in land by DWR or State Parks please identify state representative and state senator for the project area. Name and phone number of state representative, state senator near project site, if applicable:</b> a. Has the representative and senator been contacted? N/A	
<b>9. Areawide clearinghouse(s) receiving state action:</b> (to be sent out by agency in block 1) Six County Association of Governments	
<b>10. For further information, contact:</b>   Diana Whitney <b>Phone:</b> (801) 538-5312	<b>11. Signature and title of authorized officer</b>   for Gil Hunt, Associate Director <b>Date:</b> August 4, 2006

# SURFACE DAMAGE AGREEMENT

This Agreement is between, of THE BEN D. LAMB AND ANITA J. LAMB FAMILY REVOCABLE LIVING TRUST, hereinafter referred to a "Lessor", whose address is HC 13 Box 4205, Wales, UT 84667 and Petro-Hunt, L.L.C., hereinafter referred to as "Operator", whose address is Suite 3400; 1601 Elm Street; Dallas, Texas 75201

The above parties agree to the basic understanding as follows:

Prior to the commencement of any drilling operation by Operator on any land in Sanpete County, Utah on which Lessor owns surface rights ("Subject Lands"), Operator shall make the following payments as full and complete compensation for damage to the surface:

- \$500 per acre for each drill-site location and its associated access road

Operator's use of, and access to, the Subject Lands is at its own cost and risk. Operator agrees to bear all liabilities caused by its operations. A copy of Operator's State of Utah Blanket Bond in the amount of up to \$120,000 is attached hereto as Exhibit 'A'. Operator's proof of liability insurance will be furnished to Lessor.

(1) Operator shall obtain Lessor's consent to the location of all access roads, which consent shall not be unreasonably withheld. Access roads shall not exceed 30 feet in width. All pipelines, power lines, and telephone lines that will be permanent will be buried below plow depth and mapped unless otherwise agreed. In the event of a dry hole, the drill site and roadways will be restored as required by law to as near as original condition as possible, or to Lessor's specifications. Lessor hereby gives its consent to the approximate location of the access road for the ~~Lamb Trust 34B~~ as depicted on the plat attached hereto as Exhibit "B".it

(2) Unauthorized personnel, contractors, etc. will not have access to or be allowed on any drilling locations hereunder. Operator will make a reasonable effort to have a company representative on the location at all times during drilling/completion operations. Firearms, liquor, and drugs shall be prohibited from all well locations and access roads covered by this agreement.

(3) Operator will reimburse Lessor for loss, damage, injury or death of Lessor's livestock caused by or directly related to Operator's exploration and production of oil or gas on any lands covered by this agreement. Operator will recompense Lessor at a fair market value plus associated replacement costs, if any relative to any livestock covered by this paragraph 3.

(4) Operator will not bring permanent electric utilities onto the subject Property without first receiving written approval from the Lessor, which shall not be unreasonably withheld.

(5) Unless otherwise agreed, Operator will at all times keep all fencing and gates within the vicinity of the roads and the drilling site utilized by the Operator under this agreement in a condition suitable to contain livestock.

## PROPERTY RECLAMATION AGREEMENT

1. All topsoil will be stripped, stockpiled, and then replaced to support re-vegetation.
2. Ditches, and culverts, gates, cattle guards will be returned as nearly as possible to original condition as required by law.
3. Reclamation work will be accomplished in a timely manner. Natural causes such as unusual weather conditions or ground settling or other force majeure events may delay reclamation.

RECEIVED

AUG 04 2006

DIV. OF OIL, GAS & MINING


4. All construction and maintenance costs relating to roads, drill pads, equipment and facilities hereunder shall be born by Operator.

This agreement shall be binding upon Operator and Lessor, their respective heirs, executors, administrators, successors, and assigns and upon Operator, its executors, administrators, successors, and assigns. This agreement pertains to only to all surface areas owned by Lessor which may be disturbed in exploration and/or development by Operator, its contractors, subcontractors and/or designees.


Dated this 18th day of July, 2006.

**Lessor and Surface Owner:**

THE BEN D. LAMB AND ANITA J. LAMB FAMILY REVOCABLE TRUST

  
Ron Lamb, as Power of Attorney for Anita J. Lamb, aka Anita J. Carter

**Operator:**  
Petro-Hunt, L.L.C.

  
James F. Clarke, Vice President  
NW

**Exhibit "A"**

Attached to and made a part of that certain Surface Damage Agreement dated July 12, 2006 between The Ben D. Lamb and Anita J. Lamb Family Revocable Living Trust and Petro-Hunt, L.L.C. covering lands in Sanpete County, Utah.

**STATE OF UTAH**  
**DEPARTMENT OF NATURAL RESOURCES**  
**DIVISION OF OIL, GAS AND MINING**

FORM 4A

Bond No. RLB0008181**SURETY BOND****KNOW ALL MEN BY THESE PRESENTS:**

That we (operator name) Petro-Hunt, L.L.C. as Principal,  
 and

(surety name) RLI Insurance Company as Surety, duly authorized  
 and qualified to do business in the State of Utah, are held and firmly bound unto the State of Utah in the sum of:

One Hundred Twenty Thousand and no/100----- dollars (\$ 120,000.00----- )  
 lawful money of the United States, payable to the Director of the Division of Oil, Gas and Mining, as agent of the State of Utah, for the use and benefit of the State of Utah for the faithful payment of which we bind ourselves, our heirs, executors, administrators and successors jointly and severally by these presents.

THE CONDITION OF THIS OBLIGATION IS SUCH THAT, WHEREAS the Principal is or will be engaged in the drilling, redrilling, deepening, repairing, operating, and plugging and abandonment of a well or wells and restoring the well site or sites in the State of Utah for the purposes of oil or gas production and/or the injection and disposal of fluids in connection therewith for the following described land or well:

X Blanket Bond: To cover all wells drilled in the State of Utah

Individual Bond: Well No: \_\_\_\_\_  
 Section: \_\_\_\_\_ Township: \_\_\_\_\_ Range: \_\_\_\_\_  
 County: \_\_\_\_\_, Utah

NOW, THEREFORE, if the above bounden Principal shall comply with all the provisions of the laws of the State of Utah and the rules, orders and requirements of the Board of Oil, Gas and Mining of the State of Utah, including, but not limited to the proper plugging and abandonment of wells and well site restoration then this obligation is void; otherwise, the same shall be and remain in full force and effect.

IN TESTIMONY WHEREOF, said Principal has hereunto subscribed its name and has caused this instrument to be signed by its duly authorized officers and its corporate or notary seal to be affixed this

19th day of May, 2005

(Corporate or Notary Seal here)

Attested: \_\_\_\_\_ Date: \_\_\_\_\_

Principal (company name)  
 By \_\_\_\_\_  
 Name (print) Title  
T. Nelson  
 Signature

IN TESTIMONY WHEREOF, said Surety has caused this instrument to be signed by its duly authorized officers and its corporate or notary seal to be affixed this

19th day of May, 2005


(Corporate or Notary Seal here)

Attested: \_\_\_\_\_ Date: \_\_\_\_\_

Surety Company (Attach Power of Attorney)  
 By \_\_\_\_\_  
 Name (print) Title  
Greg E. Carlson  
 Signature  
8 Greenway Plaza, Suite 400  
 Surety Mailing Address  
Houston TX 77046  
 City State Zip

# Exhibit "B"

Attached to and made a part of that certain Surface Damage Agreement dated July 18, 2006 between The Ben D. Lamb and Anita J. Lamb Family Revocable Living Trust and Petro-Hunt, L.L.C. covering lands in Sanpete County, Utah.



**From:** Robert Clark  
**To:** Whitney, Diana  
**Date:** 8/14/2006 10:34:14 AM  
**Subject:** RDCC short turn around responses

43-039-30034

The following comments are provided in response to short turn around items **RDCC #6916** through **RDCC #6921**, and **RDCC #6943**.

**RDCC #6916, Comments begin:** The proposal of Enduring Resources, LLC to drill the **Southam Canyon 10-25-34-32** wildcat well, in Uintah County, may require a permit, known as an Approval Order, from the Executive Secretary of the Air Quality Board if any compressor or pump stations are constructed at the site. If a permit is required, a permit application, known as a Notice of Intent (NOI), should be submitted to the Executive Secretary at the Utah Division of Air Quality at 150 N. 1950 West, Salt Lake City, Utah, 84116 for review according to the Utah Air Quality Rule R307-401. Permit: Notice of Intent and Approval Order. The guidelines for preparing an NOI are available on-line at

<http://www.airquality.utah.gov/Permits/FORMS/NOIGuide8.pdf>. The proposed project is also subject to Utah Air Quality Rule R307-205-5, Fugitive Dust, due to the fugitive dust that is generated during the excavating phases of the project. These rules apply to construction activities that disturb an area greater than 1/4 acre in size. A permit, known as an Approval Order, is not required from the Executive Secretary of the Air Quality Board, but steps need to be taken to minimize fugitive dust, such as watering and/or chemical stabilization, providing vegetative or synthetic cover or windbreaks. A copy of the rules may be found at [www.rules.utah.gov/publicat/code/r307/r307.htm](http://www.rules.utah.gov/publicat/code/r307/r307.htm). **Comments end. RDCC #6917, Comments**

**begin:** The proposal of Enduring Resources, LLC to drill the **Southam Canyon 10-25-14-32** wildcat well, in Uintah County, may require a permit, known as an Approval Order, from the Executive Secretary of the Air Quality Board if any compressor or pump stations are constructed at the site. If a permit is required, a permit application, known as a Notice of Intent (NOI), should be submitted to the Executive Secretary at the Utah Division of Air Quality at 150 N. 1950 West, Salt Lake City, Utah, 84116 for review according to the Utah Air Quality Rule R307-401. Permit: Notice of Intent and Approval Order. The guidelines for preparing an NOI are available on-line at <http://www.airquality.utah.gov/Permits/FORMS/NOIGuide8.pdf>. The proposed project is also subject to Utah Air Quality Rule R307-205-5, Fugitive Dust, due to the fugitive dust that is generated during the excavating phases of the project. These rules apply to construction activities that disturb an area greater than 1/4 acre in size. A permit, known as an Approval Order, is not required from the Executive Secretary of the Air Quality Board, but steps need to be taken to minimize fugitive dust, such as watering and/or chemical stabilization, providing vegetative or synthetic cover or windbreaks. A copy of the rules may be found at

[www.rules.utah.gov/publicat/code/r307/r307.htm](http://www.rules.utah.gov/publicat/code/r307/r307.htm). **Comments end. RDCC #6918, Comments begin:** The proposal of Enduring Resources, LLC to drill the **Southam Canyon 10-25-11-32** wildcat well, in Uintah County, may require a permit, known as an Approval Order, from the Executive Secretary of the Air Quality Board if any compressor or pump stations are constructed at the site. If a permit is required, a permit application, known as a Notice of Intent (NOI), should be submitted to the Executive Secretary at the Utah Division of Air Quality at 150 N. 1950 West, Salt Lake City, Utah, 84116 for review according to the Utah Air Quality Rule R307-401. Permit: Notice of Intent and Approval Order. The guidelines for preparing an NOI are available on-line at <http://www.airquality.utah.gov/Permits/FORMS/NOIGuide8.pdf>. The proposed project is also subject to Utah Air Quality Rule R307-205-5, Fugitive Dust, due to the fugitive dust that is generated during the excavating phases of the project. These rules apply to construction activities that disturb an area greater than 1/4 acre in size. A permit, known as an Approval Order, is not required from the Executive Secretary of the Air Quality Board, but steps need to be taken to minimize fugitive dust, such as watering and/or chemical stabilization, providing vegetative or synthetic cover or windbreaks. A copy of the rules may be found at

[www.rules.utah.gov/publicat/code/r307/r307.htm](http://www.rules.utah.gov/publicat/code/r307/r307.htm). **Comments end. RDCC #6919, Comments begin:** The proposal of the Houston Exploration Company to drill the **North Horseshoe 5-16-6-22** wildcat well, in Uintah County, may require a permit, known as an Approval Order, from the Executive Secretary of the Air Quality Board if any compressor or pump stations are constructed at the site. If a permit is required, a permit application, known as a Notice of Intent (NOI), should be submitted to the Executive Secretary at the Utah Division of Air Quality at 150 N. 1950 West, Salt Lake City, Utah, 84116 for review according to the Utah Air Quality Rule R307-401. Permit: Notice of Intent and Approval Order. The guidelines for

preparing an NOI are available on-line at <http://www.airquality.utah.gov/Permits/FORMS/NOIGuide8.pdf>.

The proposed project is also subject to Utah Air Quality Rule R307-205-5, Fugitive Dust, due to the fugitive dust that is generated during the excavating phases of the project. These rules apply to construction activities that disturb an area greater than 1/4 acre in size. A permit, known as an Approval Order, is not required from the Executive Secretary of the Air Quality Board, but steps need to be taken to minimize fugitive dust, such as watering and/or chemical stabilization, providing vegetative or synthetic cover or windbreaks. A copy of the rules may be found at

[www.rules.utah.gov/publicat/code/r307/r307.htm](http://www.rules.utah.gov/publicat/code/r307/r307.htm) . **Comments end. RDCC #6920, Comments begin:** The proposal of Petro-Hunt, LLC to drill the **Vonda H. Christensen Family LP 35A-3-1** wildcat well, in Sanpete County, may require a permit, known as an Approval Order, from the Executive Secretary of the Air Quality Board if any compressor or pump stations are constructed at the site. If a permit is required, a permit application, known as a Notice of Intent (NOI), should be submitted to the Executive Secretary at the Utah Division of Air Quality at 150 N. 1950 West, Salt Lake City, Utah, 84116 for review according to the Utah Air Quality Rule R307-401. Permit: Notice of Intent and Approval Order. The guidelines for preparing an NOI are available on-line at <http://www.airquality.utah.gov/Permits/FORMS/NOIGuide8.pdf>.

The proposed project is also subject to Utah Air Quality Rule R307-205-5, Fugitive Dust, due to the fugitive dust that is generated during the excavating phases of the project. These rules apply to construction activities that disturb an area greater than 1/4 acre in size. A permit, known as an Approval Order, is not required from the Executive Secretary of the Air Quality Board, but steps need to be taken to minimize fugitive dust, such as watering and/or chemical stabilization, providing vegetative or synthetic cover or windbreaks. A copy of the rules may be found at

[www.rules.utah.gov/publicat/code/r307/r307.htm](http://www.rules.utah.gov/publicat/code/r307/r307.htm) . **Comments end. RDCC #6921, Comments begin:** The proposal of Petro-Hunt, LLC to drill the **Lamb Trust 31B-1-1** wildcat well, in Sanpete County, may require a permit, known as an Approval Order, from the Executive Secretary of the Air Quality Board if any compressor or pump stations are constructed at the site. If a permit is required, a permit application, known as a Notice of Intent (NOI), should be submitted to the Executive Secretary at the Utah Division of Air Quality at 150 N. 1950 West, Salt Lake City, Utah, 84116 for review according to the Utah Air Quality Rule R307-401. Permit: Notice of Intent and Approval Order. The guidelines for preparing an NOI are available on-line at <http://www.airquality.utah.gov/Permits/FORMS/NOIGuide8.pdf>. The proposed project is also subject to Utah Air Quality Rule R307-205-5, Fugitive Dust, due to the fugitive dust that is generated during the excavating phases of the project. These rules apply to construction activities that disturb an area greater than 1/4 acre in size. A permit, known as an Approval Order, is not required from the Executive Secretary of the Air Quality Board, but steps need to be taken to minimize fugitive dust, such as watering and/or chemical stabilization, providing vegetative or synthetic cover or windbreaks. A copy of the rules may be found at [www.rules.utah.gov/publicat/code/r307/r307.htm](http://www.rules.utah.gov/publicat/code/r307/r307.htm) . **Comments end.**

**RDCC #6943, Comments begin:** The proposal of Enduring Resources, LLC to drill the **Long Draw 12-24-31-26** wildcat well, in Uintah County, may require a permit, known as an Approval Order, from the Executive Secretary of the Air Quality Board if any compressor or pump stations are constructed at the site. If a permit is required, a permit application, known as a Notice of Intent (NOI), should be submitted to the Executive Secretary at the Utah Division of Air Quality at 150 N. 1950 West, Salt Lake City, Utah, 84116 for review according to the Utah Air Quality Rule R307-401. Permit: Notice of Intent and Approval Order. The guidelines for preparing an NOI are available on-line at

<http://www.airquality.utah.gov/Permits/FORMS/NOIGuide8.pdf>. The proposed project is also subject to Utah Air Quality Rule R307-205-5, Fugitive Dust, due to the fugitive dust that is generated during the excavating phases of the project. These rules apply to construction activities that disturb an area greater than 1/4 acre in size. A permit, known as an Approval Order, is not required from the Executive Secretary of the Air Quality Board, but steps need to be taken to minimize fugitive dust, such as watering and/or chemical stabilization, providing vegetative or synthetic cover or windbreaks. A copy of the rules may be found at [www.rules.utah.gov/publicat/code/r307/r307.htm](http://www.rules.utah.gov/publicat/code/r307/r307.htm) . **Comments end.** Robert Clark Division of Air Quality 536-4435

**CC:** McNeill, Dave; Wright, Carolyn



## MEMORANDUM

*Deftro Hunt*  
*43-034-30034*

DATE: August 15, 2006

TO: Utah Division of Oil, Gas and Mining, Forestry, Fire, and State Lands, and Resource Development Coordinating Committee

FROM: Utah Geological Survey, Ground Water and Paleontology Program

SUBJECT: UGS comments on RDCC items 6916, 6917, 6918, 6919, 6920, 6921, 6922, and 6943.

6916. Division of Oil, Gas and Mining # ML-47065  
Short Turn Around; Sec. 32, T10S, R25E  
Uintah Co.

Application for Permit to Drill - proposal to drill a wildcat well the Southam Canyon 10-25-34-32 on a State lease ML-47065

Although there are no paleontological localities recorded in our files in this project area, it is mapped as T3 (Eocene Uinta and Duchesne River Formations) on the Utah State Geological Map. The Uinta and Duchesne River Formations are among the most paleontological sensitive rock units in Utah and have a strong potential for yielding significant vertebrate fossil localities. The office of the State paleontologist therefore recommends that a paleontological survey be conducted for this project and its easements.

6917. Division of Oil, Gas and Mining  
Short Turn Around;; Sec. 32, T10S, R25E  
Uintah Co.

Application for Permit to Drill - proposal to drill a wildcat well the Southam Canyon 10-25-14-32 on a State lease ML-47065

Although there are no paleontological localities recorded in our files in this project area, it is mapped as T3 (Eocene Uinta and Duchesne River Formations) on the Utah State Geological Map. The Uinta and Duchesne River Formations are among the most paleontological sensitive rock units in Utah and have a strong potential for yielding significant vertebrate fossil localities. The office of the State paleontologist therefore recommends that a paleontological survey be conducted for this project and its easements.

6918. Division of Oil, Gas and Mining  
Short Turn Around; Sec. 32, T10S, R25E  
Uintah Co.

Application for Permit to Drill - proposal to drill the Southam Canyon 10-25-11-32 on a State lease ML-47065

Although there are no paleontological localities recorded in our files in this project area, it is mapped as T3 (Eocene Uinta and Duchesne River Formations) on the Utah State Geological Map. The Uinta and Duchesne River Formations are among the most paleontological sensitive rock units in Utah and have a strong potential for yielding significant vertebrate fossil localities. The office of the State paleontologist therefore recommends that a paleontological survey be conducted for this project and its easements.

6919. Division of Oil, Gas and Mining  
Short Turn Around; Sec. 16, T6S, R22E  
Uintah Co.

Application for Permit to Drill - proposal to drill a wildcat well the North Horseshoe 5-16-6-22 on a State lease ML-47969

Although there are no paleontological localities recorded in our files in this project area, it is mapped as T3 (Eocene Uinta and Duchesne River Formations) on the Utah State Geological Map. The Uinta and Duchesne River Formations are among the most paleontological sensitive rock units in Utah and have a strong potential for yielding significant vertebrate fossil localities. The office of the State paleontologist therefore recommends that a paleontological survey be conducted for this project and its easements.

6920. Division of Oil, Gas and Mining  
Short Turn Around; Sec. 35, T16S, R2E  
Sanpete Co.

Application for Permit to Drill - proposal to drill a wildcat well the Vonda H. Christ. Fam. 35A-3-1 on a Fee lease

Although there are no paleontological localities recorded in our files in this project area, it is mapped as T3 (Eocene Uinta and Duchesne River Formations) on the Utah State Geological Map. The Uinta and Duchesne River Formations are among the most paleontological sensitive rock units in Utah and have a strong potential for yielding significant vertebrate fossil localities. The office of the State paleontologist therefore recommends that a paleontological survey be conducted for this project and its easements.

6921. Division of Oil, Gas and Mining  
Short Turn Around; Sec. 31, T15S, R3E  
Sanpete Co.

Application for Permit to Drill - proposal to drill a wildcat well the Lamb Trust 31B-1-1 on a Fee lease Fee

Although there are no paleontological localities recorded in our files in this project area, it is mapped as T3 (Eocene Uinta and Duchesne River Formations) on the Utah State Geological Map. The Uinta and Duchesne River Formations are among the most paleontological sensitive rock units in Utah and have a strong potential for yielding significant vertebrate fossil localities. The office of the State paleontologist therefore recommends that a paleontological survey be conducted for this project and its

easements..

6922. Trust Lands Administration  
Other Proposed Actions; State Land Proposals  
Sec. 16, T10S, R18E; Uintah Co; Easement #1124

Two paleontological localities with vertebrate fossils, Utah Paleontological Localities Un 1699 and Un 1700, are recorded in our files in this project area. The project is mapped as T3 (Eocene Uinta and Duchesne River Formations) on the Utah State Geological Map. The Uinta and Duchesne River Formations are among the most paleontological sensitive rock units in Utah and have a strong potential for yielding significant vertebrate fossil localities. The office of the State paleontologist therefore recommends that a paleontological survey be conducted for this project and its easements and, if these known critical fossil localities are to be impacted, they should be mitigated by a permitted paleontologist.

6943. Division of Forestry, Fire and State Lands  
Short Turn Around; Drilling Permits; Sec. 26, T12S, R24E  
Uintah Co.  
Application for Permit to Drill - proposal to drill a wildcat well the Long Draw 12-24-31-26 on a State lease ML-47090

Although there are no paleontological localities recorded in our files in this project area, it is mapped as T3 (Eocene Uinta and Duchesne River Formations) on the Utah State Geological Map. The Uinta and Duchesne River Formations are among the most paleontological sensitive rock units in Utah and have a strong potential for yielding significant vertebrate fossil localities. The office of the State paleontologist therefore recommends that a paleontological survey be conducted for this project and its easements.

**From:** Carolyn Wright  
**To:** Whitney, Diana  
**Date:** 8/21/2006 9:19:50 AM  
**Subject:** Fwd: RDCC short turn around responses

43-034-30034

FYI

>>> Robert Clark 8/14/2006 10:33 AM >>>

The following comments are provided in response to short turn around items **RDCC #6916** through **RDCC #6921**, and **RDCC #6943**.

**RDCC #6916, Comments begin:** The proposal of Enduring Resources, LLC to drill the **Southam Canyon 10-25-34-32** wildcat well, in Uintah County, may require a permit, known as an Approval Order, from the Executive Secretary of the Air Quality Board if any compressor or pump stations are constructed at the site. If a permit is required, a permit application, known as a Notice of Intent (NOI), should be submitted to the Executive Secretary at the Utah Division of Air Quality at 150 N. 1950 West, Salt Lake City, Utah, 84116 for review according to the Utah Air Quality Rule R307-401. Permit: Notice of Intent and Approval Order. The guidelines for preparing an NOI are available on-line at <http://www.airquality.utah.gov/Permits/FORMS/NOIGuide8.pdf>.

The proposed project is also subject to Utah Air Quality Rule R307-205-5, Fugitive Dust, due to the fugitive dust that is generated during the excavating phases of the project. These rules apply to construction activities that disturb an area greater than 1/4 acre in size. A permit, known as an Approval Order, is not required from the Executive Secretary of the Air Quality Board, but steps need to be taken to minimize fugitive dust, such as watering and/or chemical stabilization, providing vegetative or synthetic cover or windbreaks. A copy of the rules may be found at [www.rules.utah.gov/publicat/code/r307/r307.htm](http://www.rules.utah.gov/publicat/code/r307/r307.htm).

**Comments end. RDCC #6917, Comments begin:** The proposal of Enduring Resources, LLC to drill the **Southam Canyon 10-25-14-32** wildcat well, in Uintah County, may require a permit, known as an Approval Order, from the Executive Secretary of the Air Quality Board if any compressor or pump stations are constructed at the site. If a permit is required, a permit application, known as a Notice of Intent (NOI), should be submitted to the Executive Secretary at the Utah Division of Air Quality at 150 N. 1950 West, Salt Lake City, Utah, 84116 for review according to the Utah Air Quality Rule R307-401. Permit: Notice of Intent and Approval Order. The guidelines for preparing an NOI are available on-line at <http://www.airquality.utah.gov/Permits/FORMS/NOIGuide8.pdf>. The proposed project is also subject to Utah Air Quality Rule R307-205-5, Fugitive Dust, due to the fugitive dust that is generated during the excavating phases of the project. These rules apply to construction activities that disturb an area greater than 1/4 acre in size. A permit, known as an Approval Order, is not required from the Executive Secretary of the Air Quality Board, but steps need to be taken to minimize fugitive dust, such as watering and/or chemical stabilization, providing vegetative or synthetic cover or windbreaks. A copy of the rules may be found at [www.rules.utah.gov/publicat/code/r307/r307.htm](http://www.rules.utah.gov/publicat/code/r307/r307.htm).

**Comments end. RDCC #6918, Comments begin:** The proposal of Enduring Resources, LLC to drill the **Southam Canyon 10-25-11-32** wildcat well, in Uintah County, may require a permit, known as an Approval Order, from the Executive Secretary of the Air Quality Board if any compressor or pump stations are constructed at the site. If a permit is required, a permit application, known as a Notice of Intent (NOI), should be submitted to the Executive Secretary at the Utah Division of Air Quality at 150 N. 1950 West, Salt Lake City, Utah, 84116 for review according to the Utah Air Quality Rule R307-401. Permit: Notice of Intent and Approval Order. The guidelines for preparing an NOI are available on-line at <http://www.airquality.utah.gov/Permits/FORMS/NOIGuide8.pdf>. The proposed project is also subject to Utah Air Quality Rule R307-205-5, Fugitive Dust, due to the fugitive dust that is generated during the excavating phases of the project. These rules apply to construction activities that disturb an area greater than 1/4 acre in size. A permit, known as an Approval Order, is not required from the Executive Secretary of the Air Quality Board, but steps need to be taken to minimize fugitive dust, such as watering and/or chemical stabilization, providing vegetative or synthetic cover or windbreaks. A copy of the rules may be found at [www.rules.utah.gov/publicat/code/r307/r307.htm](http://www.rules.utah.gov/publicat/code/r307/r307.htm).

**Comments end. RDCC #6919, Comments begin:** The proposal of the Houston Exploration Company to drill the **North Horseshoe 5-16-6-22** wildcat well, in Uintah County, may require a permit, known as an Approval Order, from the Executive Secretary of the Air Quality Board if any compressor or pump stations are constructed at the site. If a permit is required, a

permit application, known as a Notice of Intent (NOI), should be submitted to the Executive Secretary at the Utah Division of Air Quality at 150 N. 1950 West, Salt Lake City, Utah, 84116 for review according to the Utah Air Quality Rule R307-401. Permit: Notice of Intent and Approval Order. The guidelines for preparing an NOI are available on-line at <http://www.airquality.utah.gov/Permits/FORMS/NOIGuide8.pdf>. The proposed project is also subject to Utah Air Quality Rule R307-205-5, Fugitive Dust, due to the fugitive dust that is generated during the excavating phases of the project. These rules apply to construction activities that disturb an area greater than 1/4 acre in size. A permit, known as an Approval Order, is not required from the Executive Secretary of the Air Quality Board, but steps need to be taken to minimize fugitive dust, such as watering and/or chemical stabilization, providing vegetative or synthetic cover or windbreaks. A copy of the rules may be found at [www.rules.utah.gov/publicat/code/r307/r307.htm](http://www.rules.utah.gov/publicat/code/r307/r307.htm). **Comments end. RDCC #6920, Comments begin:** The proposal of Petro-Hunt, LLC to drill the **Vonda H. Christensen Family LP 35A-3-1** wildcat well, in Sanpete County, may require a permit, known as an Approval Order, from the Executive Secretary of the Air Quality Board if any compressor or pump stations are constructed at the site. If a permit is required, a permit application, known as a Notice of Intent (NOI), should be submitted to the Executive Secretary at the Utah Division of Air Quality at 150 N. 1950 West, Salt Lake City, Utah, 84116 for review according to the Utah Air Quality Rule R307-401. Permit: Notice of Intent and Approval Order. The guidelines for preparing an NOI are available on-line at <http://www.airquality.utah.gov/Permits/FORMS/NOIGuide8.pdf>. The proposed project is also subject to Utah Air Quality Rule R307-205-5, Fugitive Dust, due to the fugitive dust that is generated during the excavating phases of the project. These rules apply to construction activities that disturb an area greater than 1/4 acre in size. A permit, known as an Approval Order, is not required from the Executive Secretary of the Air Quality Board, but steps need to be taken to minimize fugitive dust, such as watering and/or chemical stabilization, providing vegetative or synthetic cover or windbreaks. A copy of the rules may be found at [www.rules.utah.gov/publicat/code/r307/r307.htm](http://www.rules.utah.gov/publicat/code/r307/r307.htm). **Comments end. RDCC #6921, Comments begin:** The proposal of Petro-Hunt, LLC to drill the **Lamb Trust 31B-1-1** wildcat well, in Sanpete County, may require a permit, known as an Approval Order, from the Executive Secretary of the Air Quality Board if any compressor or pump stations are constructed at the site. If a permit is required, a permit application, known as a Notice of Intent (NOI), should be submitted to the Executive Secretary at the Utah Division of Air Quality at 150 N. 1950 West, Salt Lake City, Utah, 84116 for review according to the Utah Air Quality Rule R307-401. Permit: Notice of Intent and Approval Order. The guidelines for preparing an NOI are available on-line at <http://www.airquality.utah.gov/Permits/FORMS/NOIGuide8.pdf>. The proposed project is also subject to Utah Air Quality Rule R307-205-5, Fugitive Dust, due to the fugitive dust that is generated during the excavating phases of the project. These rules apply to construction activities that disturb an area greater than 1/4 acre in size. A permit, known as an Approval Order, is not required from the Executive Secretary of the Air Quality Board, but steps need to be taken to minimize fugitive dust, such as watering and/or chemical stabilization, providing vegetative or synthetic cover or windbreaks. A copy of the rules may be found at [www.rules.utah.gov/publicat/code/r307/r307.htm](http://www.rules.utah.gov/publicat/code/r307/r307.htm). **Comments end. RDCC #6943, Comments begin:** The proposal of Enduring Resources, LLC to drill the **Long Draw 12-24-31-26** wildcat well, in Uintah County, may require a permit, known as an Approval Order, from the Executive Secretary of the Air Quality Board if any compressor or pump stations are constructed at the site. If a permit is required, a permit application, known as a Notice of Intent (NOI), should be submitted to the Executive Secretary at the Utah Division of Air Quality at 150 N. 1950 West, Salt Lake City, Utah, 84116 for review according to the Utah Air Quality Rule R307-401. Permit: Notice of Intent and Approval Order. The guidelines for preparing an NOI are available on-line at <http://www.airquality.utah.gov/Permits/FORMS/NOIGuide8.pdf>. The proposed project is also subject to Utah Air Quality Rule R307-205-5, Fugitive Dust, due to the fugitive dust that is generated during the excavating phases of the project. These rules apply to construction activities that disturb an area greater than 1/4 acre in size. A permit, known as an Approval Order, is not required from the Executive Secretary of the Air Quality Board, but steps need to be taken to minimize fugitive dust, such as watering and/or chemical stabilization, providing vegetative or synthetic cover or windbreaks. A copy of the rules may be found at [www.rules.utah.gov/publicat/code/r307/r307.htm](http://www.rules.utah.gov/publicat/code/r307/r307.htm). **Comments end.** Robert Clark Division of Air Quality 536-4435

**STATE OF UTAH**  
DEPARTMENT OF NATURAL RESOURCES  
DIVISION OF OIL, GAS AND MINING

FORM 9

**SUNDRY NOTICES AND REPORTS ON WELLS**

Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.

1. TYPE OF WELL OIL WELL <input type="checkbox"/> GAS WELL <input checked="" type="checkbox"/> OTHER _____		5. LEASE DESIGNATION AND SERIAL NUMBER: <b>Patented</b>
2. NAME OF OPERATOR: <b>Petro-Hunt, L.L.C.</b>		6. IF INDIAN, ALLOTTEE OR TRIBE NAME: <b>N/A</b>
3. ADDRESS OF OPERATOR: <b>258 - 119th Ave. SW</b> CITY: <b>Killdeer</b> STATE: <b>ND</b> ZIP: <b>58640</b>		7. UNIT or CA AGREEMENT NAME: <b>N/A</b>
4. LOCATION OF WELL FOOTAGES AT SURFACE: <b>178' FNL &amp; 2,590' FWL,</b>		8. WELL NAME and NUMBER: <b>Lamb Trust 31B-1-1</b>
PHONE NUMBER: <b>(701) 863-6622</b>		9. API NUMBER: <b>4303930034</b>
10. FIELD AND POOL, OR WILDCAT: <b>Wildcat</b>		

QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: **NENW 31 15S 3E S** COUNTY: **Sanpete**

STATE: **UTAH**

11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION		
<input checked="" type="checkbox"/> NOTICE OF INTENT (Submit in Duplicate) Approximate date work will start: <b>10/6/2006</b>	<input type="checkbox"/> ACIDIZE	<input type="checkbox"/> DEEPEN	<input type="checkbox"/> REPERFORATE CURRENT FORMATION
<input type="checkbox"/> SUBSEQUENT REPORT (Submit Original Form Only) Date of work completion:	<input type="checkbox"/> ALTER CASING	<input type="checkbox"/> FRACTURE TREAT	<input type="checkbox"/> SIDETRACK TO REPAIR WELL
	<input type="checkbox"/> CASING REPAIR	<input type="checkbox"/> NEW CONSTRUCTION	<input type="checkbox"/> TEMPORARILY ABANDON
	<input type="checkbox"/> CHANGE TO PREVIOUS PLANS	<input type="checkbox"/> OPERATOR CHANGE	<input type="checkbox"/> TUBING REPAIR
	<input type="checkbox"/> CHANGE TUBING	<input type="checkbox"/> PLUG AND ABANDON	<input type="checkbox"/> VENT OR FLARE
	<input type="checkbox"/> CHANGE WELL NAME	<input type="checkbox"/> PLUG BACK	<input type="checkbox"/> WATER DISPOSAL
	<input type="checkbox"/> CHANGE WELL STATUS	<input type="checkbox"/> PRODUCTION (START/RESUME)	<input type="checkbox"/> WATER SHUT-OFF
	<input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS	<input type="checkbox"/> RECLAMATION OF WELL SITE	<input type="checkbox"/> OTHER: <b>534' relocation</b>
	<input type="checkbox"/> CONVERT WELL TYPE	<input type="checkbox"/> RECOMPLETE - DIFFERENT FORMATION	

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.

Petro-Hunt, L.L.C. requests permission to relocate the surface and bottomhole location for the referenced well 534' south prior to approval of the previously submitted APD. The new location avoids an exception to spacing issue on an offset tract. Following is the updated location information for the Lamb Trust 31B-1-1:

Surface & Target Location: 712' FNL & 2,584' FWL, NE/4 NW/4, Section 31, T15S, R3E, SLB&M

Attached please find an updated Form 3 and plat package to replace those previously submitted within the APD package.

A request for exception to spacing (R649-3-2) is hereby requested based on topography since the well is located within 460' of the drilling unit boundary. Petro-Hunt, L.L.C. is the only owner and operator within 460' of the proposed well and all points along the intended well bore path.

**ORIGINAL** **CONFIDENTIAL**

NAME (PLEASE PRINT) <u>Don Hamilton</u>	TITLE <u>Agent for Petro-Hunt, L.L.C.</u>
SIGNATURE <u>Don Hamilton</u>	DATE <u>9/12/2006</u>

(This space for State use only)

**RECEIVED**


**SEP 18 2006**

DIV. OF OIL, GAS & MINING


Cut = 14,337 c.y. (INCLUDES PIT AND RIG FOUNDATION EXCAVATION)  
Fill = 8,110 c.y. (NO SHRINK APPLIED)


PIT CAPACITY: 29,892 bbls  
PIT EXCAVATION: 7000 c.y.

EXISTING GROUND ELEV. AT LAMB TRUST 31B-1-1 = 5578.83  
GRADED GROUND ELEV. AT LAMB TRUST 31B-1-1 = 5579.50



PETRO HUNT  
LOCATION LAYOUT FOR  
LAMB TRUST 31B-1-1 WELL  
SECTION 31, T.15S., R.3E., S.L.B. & M.

[illegible]




PETRO HUNT  
LOCATION CROSS SECTIONS FOR  
LAMB TRUST 31B-1-1 WELL  
SECTION 31, T.15S., R.3E., S.L.B. & M.

NO.	DATE	REVISIONS	DWG NAME	SCALE	LAST UPDATE


DESIGN	CHECK	D.R.	REVIEW

PETRO HUNT	LAMB TRUST 31B-1-1	CROSS SECTIONS	PROJECT NUMBER: 0606-130
SANPETE COUNTY			
SHEET NO. SP-02			




SECTION 13+80


50'x70'x8' THICK (MAX.) 10" MINUS IMPORTED G.B. COMPACTED FILL RIG FOUNDATION  
REQ'D (COMPACT TO 97% OF MAX. LABORATORY DENSITY. RIG FOUNDATION THICKNESS  
MAY BE REDUCED BY ENGINEER DEPENDING ON SITE SOIL CONDITIONS)




SECTION 12+30





SECTION 11+80




SECTION 11+13



SECTION 10+80







#### LEGEND

- PROPOSED LOCATION
- PROPOSED ROAD
- EXISTING ROAD

**Petro-Hunt, L.L.C. Lamb Trust #31B-1-1**  
**Section 31, T.15 S., R.3 E., S.L.B. & M.**  
**712' FNL 2584' FWL**



**Jones & DeMille Engineering**

1535 South 100 West - Richfield, Utah 84701  
 Phone (435) 896-8266 Fax (435) 896-8268  
[www.jonesanddemille.com](http://www.jonesanddemille.com)



SCALE: 1" = 2000'

Petro-Hunt, L.L.C.

FIGURE: 1

Lamb Trust #31B-1-1

Vicinity Map

DRAWN: T.R.G. 09-06

PEN TBL-1strnd-hp2600.ctb

PROJECT: 0606-130

SHEET:

CHECK: T.R.G. 09-06

FILE: VICINITY\_SOUTH

LAST UPDATE: 9/8/2006

1


PETRO-HUNT, L.L.C.  
45 West 700 South  
Ephraim, UT 84627  
Phone: (435) 283-2122

Scott Lamb  
4309 Boton De Oro NW  
Albuquerque, New Mexico 87114

Dear Scott:

It has come to our attention that we made a clerical error in the Surface Damage Agreement between The Ben Glade Lamb Family Living Trust, and Petro-Hunt L.L.C., dated July 12th, 2006. The error lies in paragraph (1) where it states that the Lessor hereby gives its consent to the approximate location of the access road for parcels S-25831 and S-25849, also known as the Lamb Trust 31B as depicted on the plat attached to Exhibit "B". In paragraph (1) it should say that the Lessor hereby gives us consent to the approximate location of the access roads for parcels S-25828x, S-25830, S-25832, S-25849, S-25851, the rest of the paragraph will remain the same as previously stated. There is a signature block at the bottom of the page, which we ask you to sign if you approve of the changes being made. I am sorry for the inconvenience, and appreciate your cooperation in resolving this issue. A revised page 1 to the agreement is attached for your records.


Thanks,



John Robert Wunderlick  
Landman

Agreed and excepted this 8 day of September, 2006

THE BEN GLADE LAMB FAMILY LIVING TRUST

  
Scott Lamb, Trustee

## **SURFACE DAMAGE AGREEMENT**

This Agreement is between, Scott Lamb, Trustee of THE BEN GLADE LAMB FAMILY LIVING TRUST, hereinafter referred to a "Lessor", whose address is 4309 Boton De Oro NW, Albuquerque, New Mexico 87114 and Petro-Hunt, L.L.C., hereinafter referred to as "Operator", whose address is Suite 3400; 1601 Elm Street; Dallas, Texas 75201

The above parties agree to the basic understanding as follows:

Prior to the commencement of any drilling operation by Operator on any land in Sanpete County, Utah on which Lessor owns surface rights ("Subject Lands"), Operator shall make the following payments as full and complete compensation for damage to the surface:

- \$500 per acre for each drill-site location and its associated access road

Operator's use of, and access to, the Subject Lands is at its own cost and risk. Operator agrees to bear all liabilities caused by its operations. A copy of Operator's State of Utah Blanket Bond in the amount of up to \$120,000 is attached hereto as Exhibit 'A'. Operator's proof of liability insurance will be furnished to Lessor.

(1) Operator shall obtain Lessor's consent to the location of all access roads, which consent shall not be unreasonably withheld. Access roads shall not exceed 30 feet in width. All pipelines, power lines, and telephone lines that will be permanent will be buried below plow depth and mapped unless otherwise agreed. In the event of a dry hole, the drill site and roadways will be restored as required by law to as near as original condition as possible, or to Lessor's specifications. Lessor hereby gives its consent to the approximate location of the access road for parcels S-25828x, S-25830, S-25832, S-25849 and S-25851, also known as the Lamb Trust 31B as depicted on the plat attached hereto as Exhibit "B".

(2) Unauthorized personnel, contractors, etc. will not have access to or be allowed on any drilling locations hereunder. Operator will make a reasonable effort to have a company representative on the location at all times during drilling/completion operations. Firearms, liquor, and drugs shall be prohibited from all well locations and access roads covered by this agreement.

(3) Operator will reimburse Lessor for loss, damage, injury or death of Lessor's livestock or Native grass, caused by or directly related to Operator's exploration and production of oil or gas on any lands covered by this agreement. Operator will recompense Lessor at a fair market value plus associated replacement costs, if any relative to any livestock or native grass covered by this paragraph 3.

(4) Operator will not bring permanent electric utilities onto the subject Property without first receiving written approval from the Lessor, which shall not be unreasonably withheld.

(5) Unless otherwise agreed, Operator will at all times keep all fencing and gates within the vicinity of the roads and the drilling site utilized by the Operator under this agreement in a condition suitable to contain livestock.

## **PROPERTY RECLAMATION AGREEMENT**

1. All topsoil will be stripped, stockpiled, and then replaced to support re-vegetation.
2. Ditches, and culverts, gates, cattle guards will be returned as nearly as possible to original condition as required by law.
3. Reclamation work will be accomplished in a timely manner. Natural causes such as unusual weather conditions or ground settling or other force majeure events may delay reclamation.

## DRILLING PLAN

### APPROVAL OF OPERATIONS

#### Attachment for Permit to Drill

Name of Operator: Petro-Hunt, L. L. C.  
Address: 1601 Elm Street, Suite 3400  
Dallas, Tx 75201-7254

Well Location: Lamb Trust 31B-1-1  
Sanpete County, UT

1 GEOLOGIC SURFACE FORMATION Tertiary Undivided

2 ESTIMATED DEPTHS OF IMPORTANT GEOLOGIC MARKERS

<u>Formation</u>	<u>Depth MD</u>
Jurassic Twist Gulch	2,120'
Wales Backthrust	2,720'
Jurassic Arapien	7,460'
Jurassic Upper Twin Creek	8,020'
Jurassic Lower Twin Creek	8,640'
Jurassic Navajo	9,140'
Thrust	10,300'
Jurassic Upper Twin Creek	10,300'
Jurassic Lower Twin Creek	10,540'
Jurassic Navajo	11,080'
Thrust	13,600'
Jurassic Lower Twin Creek	13,600'
Jurassic Navajo	13,640'

3 ESTIMATED DEPTHS OF ANTICIPATED WATER, OIL, GAS OR MINERALS

<u>Formation</u>	<u>Depth</u>	<u>Type</u>
Jurassic Lower Twin Creek	8,640'	Oil
Jurassic Navajo	9,140'	Oil
Jurassic Lower Twin Creek	10,540'	Oil
Jurassic Navajo	11,080'	Oil
Jurassic Lower Twin Creek	13,600'	Oil
Jurassic Navajo	13,640'	Oil

4 PROPOSED CASING PROGRAM

All casing used to drill this well will be new casing

<u>Type</u>	<u>Size</u>	<u>Weight</u>	<u>Grade</u>	<u>Conn.</u>	<u>Top</u>	<u>Bottom</u>	<u>Hole</u>
Surface	13-3/8"	54.5 ppf	J-55	STC	0'	2,300'	17-1/2"
Intermediate	9-5/8"	53.5 ppf	P-110	LTC	0'	7,850'	12-1/4"
Drilling Liner	7-5/8"	39.0 ppf	Q-125	HDL	7,350'	11,200'	8-1/2"
Production	5-1/2"	20.0 ppf	L-80	BTC/LTC/HDL	0'	14,700'	6-1/2"

LAMB TRUST 31B-1-1  
SANPETE COUNTY, UTAH  
DRILLING PLAN

Note: The drilled depth of the surface hole and the setting depth of the surface casing may vary from 2,000' to 2,300'. Should a lost circulation zone be encountered while drilling, casing will be set approximately 300' below the lost circulation zone. If no lost circulation zone is encountered, casing to be set at 2,300'±.

5. OPERATOR'S MINIMUM SPECIFICATIONS FOR PRESSURE CONTROL

Surface hole: No BOPE will be utilized. Air foam mist, rotating head and diverter system may be utilized.

Intermediate & Drilling Liner hole: Prior to drilling out the surface casing shoe, intermediate and drilling liner, 10,000 psi rams and 5,000 psi annular will be installed. The pipe rams will be operated at least once per day from surface to total depth if operations permit. The blind rams will be functioned once per day from surface to total depth if operations permit.

A diagram of the planned BOP equipment for normal drilling operations in this area is attached. There will be two valves and one check valve on the kill line, two valves on the choke line, and an adjustable choke on the manifold system. The BOP "stack" will consist of three BOP rams (2 pipe, 1 blind), rated to 10,000 psi working pressure and one annular type preventer, rated to a minimum of 5,000 psi working pressure.

The BOP equipment will be pressure tested prior to drilling out surface casing shoe and anytime a new casing string is set. All test pressures will be maintained for five (5) minutes without any significant pressure decrease. Clear water will be circulated into the BOP stack and lines prior to pressure testing. The following test pressures will be used as a minimum for various equipment items:

1	Annular BOP	3,500 psi
2	Ram type BOP	5,000 psi
3	Kill line valves	5,000 psi
4	Choke line valves and choke manifold valves	5,000 psi
5	Chokes	5,000 psi
6	Casing, casinghead & weld	1,500 psi
7	Upper kelly cock and safety valve	5,000 psi
8	Dart valve	5,000 psi

6. MUD SYSTEMS

- A freshwater / gel system will be used to drill the surface hole.
- A salt saturated mud system will be used to drill well thru the anticipated salt section.
- A lignosulfonate system will be used to drill the well below the salt section to total depth.
- The mud system will be monitored manually/visually.

<u>Depths</u>	<u>Mud Weight (ppg)</u>	<u>Mud System</u>
0' - 2,300'	8.4 - 9.0	Freshwater / gel system.
2,300' - 7,850'	9.0 - 10.8	Saturated salt mud system
7,850' - 11,200'	9.0 - 10.0	Lignosulfonate mud system
11,200' - 14,700'	10.0	Lignosulfonate mud system

7. AUXILIARY EQUIPMENT TO BE USED

- a. Kelly cock.
- b. Full opening valve with drill pipe connection will be kept on floor. Valve will be used when the kelly is not in string.

8. TESTING, LOGGING, AND CORING PROGRAMS TO BE FOLLOWED

- A drillstem test in the Navajo is possible.
- Four electric wireline logs will be run from total depth to surface are anticipated for this well.
- The gamma ray will be left on to record from total depth to surface.
- Other log curves (resistivity, porosity, and caliper) will record from total depth to surface.
- A dipmeter and rotary sidewall cores may be run over selected intervals.

9. ANTICIPATED ABNORMAL PRESSURES OR TEMPERATURES EXPECTED

- Expected BHP 5,000 - 5,400 psi (approximately equal to normal pressure gradient).
- No abnormal temperature or pressures are anticipated.
- The formations to be penetrated do not contain known H<sub>2</sub>S gas.

**LAMB TRUST 31B-1-1  
SANPETE COUNTY, UTAH  
DRILLING PLAN**

**10 WATER SUPPLY**

- A water pipeline may be laid for this well. Local water wells will be used. Water well permit numbers will be provided as necessary.
- A water well may be drilled for this well and will be permitted in accordance with regulatory requirements.

**11 CEMENT SYSTEMS\***

**a. Surface Cement:**

- Drill 17-1/2" hole to 2,300' ±, run and cement 13-3/8" to surface (depth to vary based on depth of lost circulation zone)
- Pump 20 bbls fresh water spacer. Displace with mud
- Casing to be run with: a) float shoe b) float collar c) twelve (12) centralizers, two on the first joint and one per joint for the next ten joints d) bottom two joints thread locked f) pump job with top and bottom plugs.
- Cement the casing annulus to surface. Top out job to be performed if needed, a 1" tubing string may or may not be utilized

Type	Sacks	Interval	Density	Yield	Hole Volume	Cement Volume
Lead	950	0'-1,800'	12.5 ppg	1.98 CFS	1250 CF	1881 CF
Tail	485	1,800'-2,300'	15.8 ppg	1.16 CFS	347 CF	562 CF
Top Out	100	0'-100'	15.8 ppg	1.17 CFS	69 CF	117 CF

Surface design volumes based on 50% excess of gauge hole. (Typical design, subject to change)

Lead Mix:	50/50 Poz Premium + 8% gel + 10% Cal-Seal + 25#/sx Flocele					
	Slurry yield:	1.98 cf/sack		Slurry weight:	12.5 #/gal	
	Water requirement:	10.50 gal/sack				
Tail Mix:	Premium + 1% CaCl + 25 #/sx Flocele					
	Slurry yield:	1.16 cf/sack		Slurry weight:	15.80 #/gal	
	Water requirement:	4.99 gal/sack				
Top Out:	Premium + 2% CaCl					
	Slurry yield:	1.17 cf/sack		Slurry weight:	15.80 #/gal	
	Water requirement:	5.02 gal/sack				

**b. Intermediate Casing Cement:**

- Drill 12-1/4" hole to 7,850' ±, run and cement 9-5/8"
- Pump 20 bbl 5% KCL water. Displace with salt saturated mud
- Casing to be run with: a) float shoe b) float collar c) twelve (12) centralizers, two on the first joint and one per joint for the next ten joints d) bottom two joints thread locked f) pump job with top and bottom plugs.

Type	Sacks	Interval	Density	Yield	Hole Volume	Cement Volume
Lead	1555	1500'-7,850'	13.0 ppg	1.71 CFS	2017 CF	2659 CF

Intermediate design volumes are estimates based on 35% excess of gauge hole. Actual volumes will be calculated from caliper log to bring cement to 800' above 13 3/8" surface casing shoe + 15% excess. (Typical design, subject to change)

Lead Mix:	50/50 Poz + 3% gel + .3% D-Air + 15% salt + .4% Halad R567 + 25 #/sx Flocele + 5 #/sx gilsonite + 2% CFR#					
	Slurry yield:	1.71 cf/sack		Slurry weight:	13.0 #/gal	
	Water requirement:	7.90 gal/sack				

**LAMB TRUST 31B-1-1**  
**SANPETE COUNTY, UTAH**  
**DRILLING PLAN**

c. Drilling Liner Cement:

- Drill 8-1/2" hole to 11,200'  $\pm$ , run and cement 7-5/8" liner
- Pump 30 bbl 10.0 ppg Tuned spacer.
- Displace with lignosulfonate mud.

<u>Type</u>	<u>Sacks</u>	<u>Interval</u>	<u>Density</u>	<u>Yield</u>	<u>Hole</u> <u>Volume</u>	<u>Cement</u> <u>Volume</u>
Lead	480	7,150'– 11,200'	14.35 ppg	1.24 CFS	281 CF	595 CF

Drilling liner design volumes are estimates based on 35% excess of gauge hole. Actual volumes will be calculated from caliper log to bring lead cement to 700' above 9 5/8" intermediate casing shoe + 15% excess. (Typical design, subject to change)

Lead Mix: 50/50 Poz + 1% HR5 + 3% Halad R344 + 4% Microbond HT  
 Slurry yield: 1.24 cf/sack      Slurry weight: 14.35 #/gal.  
 Water requirement: 5.45 gal/sack

d. Production Casing Cement:

- Drill 6-1/2" hole to 14,700'  $\pm$ , run and cement 5 1/2" production casing
- Pump 30 bbl 12.0 ppg Tuned spacer.
- Displace with 2% KC completion fluid.

<u>Type</u>	<u>Sacks</u>	<u>Interval</u>	<u>Density</u>	<u>Yield</u>	<u>Hole</u> <u>Volume</u>	<u>Cement</u> <u>Volume</u>
Lead	300	10,000'– 14,700'	14.3 ppg	1.43 CFS	318 CF	429 CF

Production design volumes are estimates based on 35% excess of gauge hole. Actual volumes will be calculated from caliper log to bring lead cement to 1200' above 7 5/8" drilling liner shoe + 15% excess. (Typical design, subject to change)

Lead Mix: 50/50 Poz + 3% CFR3 + 2% HR5 + 3% Halad R344 + 20% SSA-1  
 Slurry yield: 1.43 cf/sack      Slurry weight: 14.3 #/gal.  
 Water requirement: 6.18 gal/sack

\* Actual cement designs may vary dependent upon selected vendor, casing depths, temperatures and well conditions

12 ANTICIPATED STARTING DATE AND DURATION OF THE OPERATIONS

Starting Date: May 1, 2007  
 Duration: 90 Days



## CASING DESIGN CHART

WELL: LAMB TRUST 31B-1-1 DEEP WELL  
 FIELD: WILDCAT - SANDPETE COUNTY, UT  
 06/20/08 qv

SIZE	WT/FT	GRADE	CONV	LENGTH OF SECTION	SETTING DEPTH TVD	SETTING DEPTH MD	EST. MUD WT.	PRESS GRAD P/SFFT	EST. BHP MW-TDS	EST. FRAC. GRAD. PPG	EST. GAS GRAD	CALC HYDRO PRESS	WT IN AIR SECTION 1000 LBS	CUMM 1000 LBS	COLLAPSE RATING 100% PSI	ADJUSTED TENSILE	TENS. STRENGTH JOINT 1000 LBS	TENS. STRENGTH BODY 1000 LBS	BURST RATING
20"	.25" wall	B	P.E.	80	80	80													
13 3/8"	54.50	J55	STC	2300	2300	2300	9	0.468	0.432	12.2	0.10	1076	125	125	1130	1130	514	853	2730
9 5/8"	53.50	P110	LTC	7850	7850	7850	10.8	0.562	0.525	14.9	0.10	4409	420	420	7950	7950	1422	1710	10900
7 5/8" CDHT, LJR	39.00	Q125	HDL	3850	11200	11200	10	0.520	0.484	17.5	0.15	5824	150	150	12060	12060	867	1399	14340
5 1/2" TOP SECTION	20.00	L80	BTC	3000	3000	3000	10	0.520	0.484	N/A	0.15	1560	80	294	8830	8830	503	466	9100
5 1/2" MID. SECTION	20.00	L80	LTC	8200	11200	11200	10	0.520	0.484	N/A	0.15	5824	164	234	8830	8830	416	466	9100
5 1/2" BTM SECTION	20.00	L80	HDL	3500	14700	14700	10	0.520	0.484	N/A	0.15	7644	70	70	8830	8830	240	466	9100
2 7/8" Tbg	6.50	L80	EUE	14000	14000	14000	10	0.520	0.484	N/A	0.15	7280	91	91	11170	11170	145	145	11200

SIZE	SAFETY FACTORS									
	DRILLING		PROD.		ASP		DRIFT		CSD	
	COL	TENS	BURST	BURST	ASP	PROD	BODY	I. D.	I. D.	O. D.
13 3/8"	1.100	1.600	1.200	1.200	DRLG	PROD	BODY	I. D.	I. D.	O. D.
9 5/8"	1.335	4.101	2.22	N/A	1229	N/A	12.459	12.615	12.615	14.375
7 5/8" CDHT, LJR	2.968	3.385	17.30	1.987	630	5487	Sp Drift 8.500	8.535	8.535	10.625
5 1/2" TOP SECTION	4.435	5.774	5.27	2.613	2720	5487	6.5	6.551	6.625	7.625
5 1/2" MID SECTION	7.955	1.585	N/A	1.675	N/A	5487	4.653	4.778	4.778	6.050
5 1/2" BTM SECTION	2.131	1.778	N/A	1.675	N/A	5487	4.653	4.778	4.778	6.050
2 3/8" Tbg	1.623	3.420	N/A	1.675	N/A	5487	4.653	4.699	4.778	5.500
	2.156	1.593	N/A	2.041	N/A	5487	2.347	2.441	2.441	3.600

BHP = MUD WT @ TD - 0.7 PPG X .052 X TVD = 7109



**PETRO HUNT L. L. C.**  
**PROPOSED DRILLING PROCEDURE**  
**LAMB TRUST 31B-1-1**

WILDCAT  
SANPETE COUNTY, UT

7/7/06  
Revision #2

SURFACE LOCATION: 712' FNL AND 2584' FWL OF SEC 31, T 15 S, R 3 E

BTM HOLE LOCATION: SAME AS ABOVE

**THIS DRILLING PROCEDURE HAS BEEN PROPOSED IN CONSIDERATION OF AND WITH RESPECT GIVEN TO THE MANY VARIABLES AND POTENTIAL PROBLEMS THAT MAY BE ENCOUNTERED IN THE DRILLING OF THIS WELL IN THIS GEOGRAPHICAL AREA. THEREFORE, THIS PROCEDURE IS TO SERVE AS A GENERAL GUIDELINE FOR THE DRILLING OF THIS WELL AND WILL BE REVIEWED AND MODIFIED WHEN REQUIRED AS DETERMINED BY ACTUAL WELLBORE CONDITIONS ENCOUNTERED IN THE DRILLING OPERATIONS. SAFETY AND PRUDENT DRILLING PRACTICES WILL TAKE PRIORITY AT ALL TIMES.**

**PETRO HUNT L. L. C. WILL ISOLATE ALL FRESH WATER, OIL AND / OR GAS BEARING INTERVALS WITH OIL WELL CEMENT AND / OR CASING.**

**ON ALL TRIPS, WHEN THE DRILL PIPE IS OUT OF THE HOLE, FUNCTION TEST THE BOP'S AND RECORD SAME ON IADC TOUR REPORTS.**

1. MIRU drilling rig. Install location sign in compliance with DOGM regulations on the derrick or in a conspicuous place near the well. We will utilize a lined earthen reserve pit. Insure the rig is completely rigged up prior to accepting the rig on daywork. The 20" x .25" conductor will be set prior to moving the rig on location to a depth of 80'.
2. **Notify DOGM within 24 hours of spudding the well and 24 hr prior to testing BOP's or any casing string.** Install bell nipple and flowline.

Note: Rig up mudlogging unit prior to spud.

3. PU 17 1/2" BHA, spud well and drill 17 1/2" hole to 2,300 RKB. Take surveys every 250' while drilling. Circulate hole clean and pull out of the hole.
4. Rig up and log.
5. Trip in the hole with 17 1/2" bit. Circulate hole clean and pull out of the hole to run casing.
6. Rig up casing tools. Pick up float shoe, 2 joints 13 3/8" 54.5# J55 STC casing and float collar. Run 13 3/8" 54.5# J55 STC casing to 2,300' RKB.

Lamb Trust 31B-1-1  
Drilling Procedure

7. Rig up cementing head and circulate. Cement casing as per attached cementing procedure. Do not overdisplace cement by more than  $\frac{1}{2}$  the volume of the shoe track. Bump plug with 500 psi over late pumping pressure. Check to insure floats are holding. Wait on cement 6 hours. **Notify DOGM 24 hr prior to testing BOP's.**
8. Rig down casing tools. Cut window in 20" conductor pipe and make rough cut on 13 3/8" casing. Make final cut on 13 3/8" casing and install 13 3/8" SOW x 13 5/8" 3M starting head. Test head to 50% collapse rating of the 13 3/8" casing.
9. NU DSA and BOP stack. Install pipe rams on top & bottom and blinds in middle ram. Test BOP's - rams with 5,000 psi and annular with 3500 psi.
10. Pick up 12 1/4" BHA and trip in the hole to float collar. Test 13 3/8" casing with 1,250 psi for 30 minutes (MASP = 1229 psi). **Notify DOGM 24 hr prior to testing all casing strings.**
11. Drill float equipment, cement and 5' of new formation. Circulate bottoms up and perform formation integrity test with pump truck to 11.5 ppg EMW. Anticipated fracture gradient at this depth is 12.2 ppg. Convert mud to salt saturated mud system.
12. Drill 12 1/4" hole to intermediate casing point at +/-7,850' RKB, taking MWD surveys every 100'. This casing point is intended to be +/-200' below the base of the salt. Circulate and condition hole to run casing. Pull out of hole (SLMOH).
13. Rig up lubricator and log.
14. Trip in the hole with 12 1/4" bit. Circulate hole clean and pull out of the hole to run casing.
15. Rig up casing tools. Pick up float shoe, 2 joints 9 5/8" 53.5# P110 LTC casing and float collar. Run 9 5/8" 53.5# P110 LTC casing to 7,850' RKB.
16. Rig up cementing head and circulate. Cement casing as per attached cementing procedure. Final cement volume may be determined by hole caliper results. Do not overdisplace cement by more than  $\frac{1}{2}$  the volume of the shoe track. Bump plug with 1,000 psi over late pumping pressure. Check to insure floats are holding. **Notify DOGM 24 hr prior to testing BOP's.**
17. Pick up stack with stack-lifter and set full weight of casing on slips. Make a rough cut and final cut on 9 5/8" casing. NU casing spool and test spool to 50% collapse rating of the 9 5/8" casing. NU DSA and BOP's.
18. Test BOP's - rams with 5,000 psi and annular with 3,500 psi. The MASP at this point is 2352 psi. Utilize nipple up and test crew.
19. Trip in the hole with 8 1/2" to the float collar and test 9 5/8" casing with 3,550 psi for 30 minutes (the hydrostatic of the 10.0 ppg mud in the casing + 3,550 psi exceeds 70% of the burst rating of the 9 5/8" casing). **Notify DOGM 24 hr prior to testing all casing strings.**

20. Drill float equipment, cement and 5' of new formation. Circulate bottoms up and perform formation integrity test with pump truck to 12.0 ppg EMW. Anticipated fracture gradient at this depth is 14.9 ppg.
21. Drill 8 1/2" hole to +/- 11,200' RKB, taking surveys with MWD every 100'. Circulate and condition hole for logging. Pull out of the hole (SLMOH).
22. Rig up lubricator and log.
23. Trip in the hole with 8 1/2" bit. Circulate hole clean and pull out of the hole to run casing.
24. Rig up casing tools. Pick up float shoe, 1 joint 7 5/8" casing, float collar, 1 joint of 7 5/8" casing and landing collar. Finish making up 7 5/8" 39.0# Q125 HDL liner with 500' lap. Make up liner hanger and run liner to TD on drill pipe.
25. Rig up cementing head and circulate. Hang off liner and cement as per attached cementing procedure. Do not overdisplace cement by more than 1/2 the volume of the shoe track. Bump plug with 1,000 psi over late pumping pressure. Check to insure floats are holding. Test liner top with 1500 psi, reverse out on top of liner and pull out of hole with setting tool. **Notify DOGM 24 hr prior to testing all casing strings.**
26. Test BOP's – rams with 5,000 psi and annular with 3,500 psi.
27. Trip in the hole with 6 1/2" BHA, picking up 3 1/2" stinger. Test 7 5/8" liner and 9 5/8" casing with 1,850 psi for 30 minutes (the hydrostatic of the 10.0 ppg fluid in the casing + 1,850 psi, exceeds 70% of the burst rating of the 9 5/8" casing). **Notify DOGM 24 hr prior to testing all casing strings.**
28. Drill float equipment, cement and 5' of new formation. Circulate bottoms up and perform formation integrity test with pump truck to 13.0 ppg EMW. Anticipated fracture gradient at this depth is 17.5 ppg.
29. Drill 6 1/2" hole to +/- 14,700' RKB, taking surveys with MWD every 100'. Circulate and condition hole for logging. Pull out of the hole (SLMOH).
30. Rig up lubricator and log. Evaluate well.
31. Completion procedure or P & A procedure will follow as needed.

**EXHIBIT "E"**  
**Multipoint Surface Use Plan**

Attached to UDOGM Form 3  
Petro-Hunt, L.L.C.  
Lamb Trust 31B-1-1  
712' FNL & 2,584' FWL,, NE/4 NW/4  
Section 31, T15S, R3E, SLB&M, Sanpete County, Utah

The dirt contractor will be provided with an approved copy of this document prior to initiating construction.

A private surface use agreement is necessary prior to initiating construction.

**1. Existing Roads**

- a. Access to the well site will utilize the existing county road under Sanpete County Road Department maintenance (See Exhibit "B") in which approval to encroach is in place at this time.
- b. The existing county road will not be upgraded but the existing Liberty-Pioneer encroachment will be utilized where the proposed access to the well leaves the county surface.
- c. We do not plan to change, alter or improve upon any other existing state or county roads.
- d. All existing roads will be maintained and kept in good repair during all phases of operation.
- e. Vehicle operators will obey posted speed restrictions and observe safe speeds commensurate with road and weather conditions.
- f. Since no improvements are anticipated to any State or County access roads no topsoil striping will occur.

**2. Planned Access Roads**

- a. From the existing County Road an access is proposed trending 0.4 miles east along the existing Liberty-Pioneer access road on Lamb surface.

- b. Approximately 0.18 miles of access across Lamb surface is proposed to the well site. The 0.18 miles of access trends northeast and consists of entirely new disturbance and crosses no significant drainages.
- c. A road design plan is not anticipated at this time.
- d. The proposed access road will consist of a 24' travel surface within a 30' disturbed area across Lamb Trust surface.
- e. DOGM approval to construct and utilize the proposed access road is requested with this application.
- f. A maximum grade of 10% will be maintained throughout the project with no major cuts and fills anticipated.
- g. No turnouts are proposed since the access road is only 0.58 miles long and adequate sight distance exists in all directions.
- h. No low water crossings and one 18" culvert is anticipated where the new road leaves the county surface. Adequate drainage structures will be incorporated into the remainder of the road.
- i. No surfacing material will come from federal or State lands.
- j. A gate and cattleguard structure is anticipated as the access road crosses the state road right-of-way fence.
- k. Surface disturbance and vehicular travel will be limited to the approved location access road.
- l. The operator will be responsible for all maintenance of the access road including drainage structures.

### **3. Location of Existing Wells**

- a. There is one existing production well within a one mile radius of the proposed location.
- b. The Lamb Trust #31-6 was drilled previously and is located within the SE/4 NW/4, Section 31, T15S, R3E, SLB&M.

### **4. Location of Existing and/or Proposed Facilities**

- a. If the well is deemed productive a sundry notice reflecting the production site layout will be submitted for approval.

- b. Rehabilitation of all pad areas not used for production facilities will be made in accordance with landowner stipulations.

## **5. Location and Type of Water Supply**

- a. The location and type of water supply has been addressed as #11 within Exhibit "D". (Drilling Plan).

## **6. Source of Construction Materials**

- a. Any necessary construction materials needed will be obtained locally from a private source and hauled to the location on existing roads.

## **7. Methods for handling waste disposal**

- a. A small reserve pit will be constructed with a minimum of one-half the total depth below the original ground surface on the lowest point within the pit. The pit will be lined with a synthetic liner. Three sides of the reserve pit will be fenced within 24 hours after completion of construction and the fourth side within 24 hours after drilling operations cease with four strands of barbed wire, or woven wire topped with barbed wire to a height of not less than four feet. The fence will be kept in good repair while the pit is drying.
- b. Following drilling, the liquid waste will be evaporated from the pit and the pit backfilled and returned to natural grade. No liquid hydrocarbons will be discharged to the reserve pit or location.
- c. In the event fluids are produced, any oil will be retained in tanks until sold and any water produced will be retained until its quality can be determined. The quality and quantity of the water will determine the method of disposal.
- d. Trash will be contained in a portable metal container and will be hauled from location periodically and disposed of at an approved disposal site. Chemical toilets will be placed on location and sewage will be disposed of at an appropriate disposal site.

## **8. Ancillary Facilities**

- a. We anticipate no need for ancillary facilities with the exception of trailers to be located on the drill site.

## **9. Well-site Layout**

- a. Available topsoil will be removed from the location and stockpiled. The location of the rig, reserve and blooie pits, and drilling support equipment will be located as shown on Exhibit "A", Figure 1 (Location Layout).
- b. A blooie pit will be located 100' from the drill hole. A line will be placed on the surface from the center hole to the blooie pit. The blooie pit will not be lined, but will be fenced on four sides to protect livestock/wildlife.
- c. Access to the well pad will be as shown on the location layout.
- d. Natural runoff will be diverted around the well pad as shown on the location layout.

## **10. Plans for Restoration of Surface**

- a. All surface areas not required for producing operations will be graded to as near original condition as possible and contoured to maintain possible erosion to a minimum.
- b. Available topsoil will be stockpiled and will be evenly distributed over the disturbed areas and the area will be reseeded as prescribed by the landowner.
- c. Pits and any other area that would present a hazard to wildlife or livestock will be fenced off when the rig is released and removed.
- d. Any oil accumulation on the pit will be removed or overhead flagged as dictated by then existing conditions.
- e. Rehabilitation will commence following completion of the well. Holes will be filled immediately upon release of the drilling rig from the location. If the well-site is to be abandoned, all disturbed areas will be recontoured to the natural contour as is possible.

## **11. Surface Ownership**

- a. The well-site and access road will be constructed on lands owned by:
  - i. The Ben Glade Lamb Family Living Trust  
Contact: Scott D. Lamb, Trustee  
Cell Phone: 505-301-2436  
FAX: 505-428-3530  
Email: wannagogolfing@hotmail.com  
Address: 7521 Sunrose Drive. .NW  
Albuquerque, New Mexico 87120

- b. A surface use agreement is presently in-place and has been submitted as Exhibit 'C'.
- c. The operator shall contact the landowner and the Division of Oil, Gas and Mining 48 hours prior to beginning construction activities.

**12. Other Information:**

- a. The primary surface use is wildlife habitat and grazing. The nearest dwelling is near Wales approximately ½ mile northwest of the proposed location. The nearest live water is in Silver Creek Ditch approximately 1 mile east.
- b. If there is snow on the ground when construction begins, it will be removed before the soil is disturbed, and piled downhill from the topsoil stockpile location.
- c. The back-slope and fore-slope will be constructed no steeper than 3:1.
- d. All equipment and vehicles will be confined to the access road and well pad.
- e. A complete copy of the approved Application for Permit to Drill (APD) including conditions and stipulations and the surface use agreement shall be on the well-site during construction and drilling operations.

There will be no deviation from the proposed drilling and/or workover program without prior approval from the Division of Oil, Gas & Mining.

**13. Company Representative**

Mick Homiston  
Petro-Hunt, L.L.C.  
258 – 119<sup>th</sup> Ave. SW  
Killdeer, ND 58640  
701-863-6622

**Company Agent**

Don Hamilton  
Buys & Associates, Inc  
2580 Creekview Road, Moab, Utah 84532  
435-718-2018



#### 14. Certification

I hereby certify that I, or persons under my direct supervision have inspected the proposed drill site and access route; that I am familiar with the conditions which presently exist; that the statements made in this plan are, to the best of my knowledge, true and correct, and that the work associated with the operations proposed herein will be performed by Petro-Hunt, L.L.C. and its subcontractors in conformity with this plan and the terms and conditions under which it is approved.


9-25-06

Date


Don Hamilton

Don Hamilton

Agent for Petro-Hunt, L.L.C.



SANPETE COUNTY		PETRO HUNT		LAMB TRUST 31B-1-1		WELL LOCATION LAYOUT		APPROVAL RECOMM.		DATE		PROJECT DESIGN ENGINEER		DESIGN		B.L.		07-06		CHECK		D.R.		07-06		REVIEW	
								APPROVED		DATE				DRAWING		B.L.		07-06		CHECK		D.R.		07-06		DATE	
PROJECT NUMBER:		0606-130												QUANT.		B.L.		07-06		CHECK		D.R.		07-06			
SHEET NO.		SP-01																									
JONES & DeMille Engineering 1535 South 100 West - Richfield, Utah 84701 Phone (435) 896-8266 Fax (435) 896-8268 www.jonesanddemic.com																											
NO.		DATE		DESIGN REV. BY		WARS CORES BY		PARCELS REQUEST BY																			
REMARKS																											
ORIGINAL SUBMISSION FOR AUTHORIZATION																											
SCALE: 1:50		DWG NAME: LAMB-SITE		SHT SET: #####		DWG CREATED: 07/17/2006		LAST UPDATE: 7/17/2006																			
PEN TBL: _101rdrhpg0000.cb																											





SECTION 13+50

SECTION 11+50

SECTION 10+83

SECTION 10+50

<div><div></div><div><div>Jones &amp; DeMille Engineering</div><div>1535 South 100 West • Richfield, Utah 84701</div><div>Phone (435) 896-3286 Fax (435) 896-3288</div><div>www.jonesanddemic.com</div></div></div>																																			
PETRO HUNT		LAMB TRUST 31B-1-1		CROSS SECTIONS		0606-130		PROJECT NUMBER:		SCALE: 1:50		DWG NAME: LAME.SITE		DWG CREATED: 07/17/2006		LAST UPDATE: 7/17/2006																			
SANPETE				APPROVAL		APPROVED		DATE		DESIGN		B.L.		07-06		CHECK		D.R.		07-06		CHECK		D.R.		07-06		CHECK		D.R.		07-06		BY:	
				RECOMM:		PROJECT DESIGN ENGINEER		DATE		DRAWN		B.L.		07-06		CHECK		D.R.		07-06		DATE													



# LEGEND



PROPOSED LOCATION

**Petro-Hunt, L.L.C. Lamb Trust #31B-1-1**  
**Section 31, T.15 S., R.3 E., S.L.B. & M.**  
**178' FNL 2590' FWL**



**Jones & DeMille Engineering**

1535 South 100 West - Richfield, Utah 84701  
 Phone (435) 896-8266 Fax (435) 896-8268  
 www.jonesanddemille.com



SCALE: 1" = 2000'

Petro-Hunt, L.L.C.

FIGURE: 1

Lamb Trust #31B-1-1

Vicinity Map

DRAWN: T.W.G. 06/22/06

PEN: TBL: \_1stndrd-hp2600.ctb

PROJECT: 0606-130

SHEET:

CHECK: T.R.G. 06/22/06


FILE: VICINITY

LAST UPDATE: 6/22/2006

1

BOP STACK AND  
CHOKE MANIFOLD  
SCHEMATIC

- R - ROTATING HEAD-IF NEEDED
- A - 11" 3M ANNULAR BOP
- D - 11" 3M DOUBLE RAM BOP
- S - 11" 3M DRILLING SPOOL
- V1 - 2-1/16" 5M CHECK VALVE
- V2 - 2-1/16" 5M MANUAL GATE VALVE
- V3 - 3-1/16" 5M MANUAL GATE VALVE
- V4 - 3-1/16" 5M MANUAL GATE VALVE
- V5 - 3-1/16" 5M MANUAL GATE VALVE
- V6 - 3-1/16" 5M MANUAL GATE VALVE
- V7 - 3-1/16" 5M MANUAL GATE VALVE
- V8 - 3-1/16" 5M MANUAL GATE VALVE
- V9 - 3-1/16" 5M MANUAL GATE VALVE
- V10 - 2-1/16" 5M MANUAL GATE VALVE
- C1 - 3-1/16" 5M MANUAL CHOKE
- C2 - 3-1/16" 5M MANUAL CHOKE
- G1 - GAUGE



**STATE OF UTAH**  
DEPARTMENT OF NATURAL RESOURCES  
DIVISION OF OIL, GAS AND MINING

FORM 3

AMENDED REPORT ☒  
(highlight changes)

<b>APPLICATION FOR PERMIT TO DRILL</b>			5. MINERAL LEASE NO: <b>Patented</b>	6. SURFACE: <b>Fee</b>
1A. TYPE OF WORK: <b>DRILL</b> <input checked="" type="checkbox"/> <b>REENTER</b> <input type="checkbox"/> <b>DEEPEN</b> <input type="checkbox"/>			7. IF INDIAN, ALLOTTEE OR TRIBE NAME: <b>N/A</b>	
B. TYPE OF WELL: <b>OIL</b> <input checked="" type="checkbox"/> <b>GAS</b> <input type="checkbox"/> <b>OTHER</b> _____ <b>SINGLE ZONE</b> <input type="checkbox"/> <b>MULTIPLE ZONE</b> <input checked="" type="checkbox"/>			8. UNIT or CA AGREEMENT NAME: <b>N/A</b>	
2. NAME OF OPERATOR: <b>PETRO-HUNT, L.L.C.</b>			9. WELL NAME and NUMBER: <b>LAMB TRUST 31B-1-1</b>	
3. ADDRESS OF OPERATOR: <b>258 - 119th Ave. SW</b> <b>Killdeer</b> <b>ND</b> <b>58640</b>			10. FIELD AND POOL, OR WILDCAT: <b>Wildcat</b>	
4. LOCATION OF WELL (FOOTAGES) AT SURFACE: <b>712' FNL &amp; 2,584' FWL</b> AT PROPOSED PRODUCING ZONE: <b>712' FNL &amp; 2,584' FWL</b>			11. QTR/CTR. SECTION, TOWNSHIP, RANGE, MERIDIAN: <b>NENW 31 15S 3E S</b>	
14. DISTANCE IN MILES AND DIRECTION FROM NEAREST TOWN OR POST OFFICE: <b>1.02 miles south of Wales, Utah</b>			12. COUNTY: <b>Sanpete</b>	13. STATE: <b>UTAH</b>
15. DISTANCE TO NEAREST PROPERTY OR LEASE LINE (FEET) <b>69'</b>	16. NUMBER OF ACRES IN LEASE: <b>21</b>	17. NUMBER OF ACRES ASSIGNED TO THIS WELL: <b>40</b>		
18. DISTANCE TO NEAREST WELL (DRILLING, COMPLETED, OR APPLIED FOR) ON THIS LEASE (FEET) <b>None</b>	19. PROPOSED DEPTH: <b>14,700</b>	20. BOND DESCRIPTION: <b>Statewide Surety RLB0008181</b>		
21. ELEVATIONS (SHOW WHETHER DF, RT, GR, ETC.): <b>5,579' GR</b>	22. APPROXIMATE DATE WORK WILL START: <b>10/6/2006</b>	23. ESTIMATED DURATION: <b>90 days</b>		

24. PROPOSED CASING AND CEMENTING PROGRAM									
SIZE OF HOLE	CASING SIZE, GRADE, AND WEIGHT PER FOOT			SETTING DEPTH	CEMENT TYPE, QUANTITY, YIELD, AND SLURRY WEIGHT				
26"	20"	.25" w.t.		80	Ready mix to surface				
17-1/2"	13-3/8"	J55	54.5#	2,300	50/50 Poz & Premium	950/485 sx	1.98/1.16	12.5/15.8	
12-1/4"	9-5/8"	P110	53.5#	7,850	50/50 Poz	1555 sx	1.71	13.0	
8-1/2"	7-5/8"	Q125	39.0#	11,200	50/50 Poz	480 sx	1.24	14.35	
6-1/2"	5-1/2"	L80	20.0#	14,700	50/50 Poz	300 sx	1.43	14.3	

<b>25. ATTACHMENTS</b>	
VERIFY THE FOLLOWING ARE ATTACHED IN ACCORDANCE WITH THE UTAH OIL AND GAS CONSERVATION GENERAL RULES:	
<input checked="" type="checkbox"/> WELL PLAT OR MAP PREPARED BY LICENSED SURVEYOR OR ENGINEER <input type="checkbox"/> EVIDENCE OF DIVISION OF WATER RIGHTS APPROVAL FOR USE OF WATER	<input checked="" type="checkbox"/> COMPLETE DRILLING PLAN <input type="checkbox"/> FORM 5, IF OPERATOR IS PERSON OR COMPANY OTHER THAN THE LEASE OWNER

NAME (PLEASE PRINT) <u>Don Hamilton</u>	TITLE <u>Agent for Petro-Hunt, L.L.C</u>
SIGNATURE <u>Don Hamilton</u>	DATE <u>9/12/2006</u>

(This space for State use only)


**Approved by the  
Utah Division of  
Oil, Gas and Mining**

API NUMBER ASSIGNED: 43-039-30054

APPROVAL:

Date: 01-18-07  
By: [Signature]

# Section 31, T.15 S., R.3 E., S.L.B. & M.



## BASIS OF BEARINGS

BASIS OF BEARING USED WAS N89°20'01\"E BETWEEN THE SOUTHWEST CORNER AND THE SOUTHEAST CORNER OF SECTION 31, T.15 S., R.3 E., S.L.B. & M.  
 LATITUDE = 39°28'23.6821\" (38.473245028) NAD 83  
 LONGITUDE = -111°37'45.3008\" (-111.629250222) NAD 83

## PROJECT Petro-Hunt, L.L.C.

WELL LOCATION, LOCATED AS SHOWN IN THE N.E. 1/4 OF THE N.W. 1/4 OF SECTION 31, T.15 S., R.3 E., S.L.B. & M. SANPETE COUNTY, UTAH


## LEGEND

- = SECTION CORNERS (LOCATED)
- = QUARTER SECTION CORNERS (LOCATED)
- = SECTION CORNERS (NOT LOCATED)
- = QUARTER SECTION CORNERS (NOT LOCATED)
- = PROPOSED WELL HEAD

NOTE: THE PURPOSE OF THIS SURVEY WAS TO PLAT THE PETRO-HUNT, L.L.C. LAMB TRUST #31B-1-1 LOCATION. LOCATED IN THE N.E. 1/4 OF THE N.W. 1/4 OF SECTION 31, T.15 S., R.3 E., S.L.B. & M., SANPETE COUNTY, UTAH.

## BASIS OF ELEVATION

ELEVATION BASED ON THE SOUTHWEST CORNER OF SECTION 6, T.16 S., R.3 E., S.L.B. & M. WHICH IS A SANPETE COUNTY ALUM CAP WITH AN ELEVATION OF 5559.00'.



## CERTIFICATE

THIS IS TO CERTIFY THAT THIS PLAT WAS PREPARED FROM FIELD NOTES OF ACTUAL SURVEYS MADE BY ME OR UNDER MY SUPERVISION, AND THAT THE SAME ARE TRUE AND CORRECT TO THE BEST OF MY KNOWLEDGE AND BELIEF.

TREVOR ROY GADD, L.S. #343639  
 DATE 09/06/06



**Jones & DeMille Engineering**  
 1535 South 100 West Richfield, Utah 84701  
 Phone (435) 896-8268  
 Fax (435) 896-8268  
 www.jonesanddemille.com

## Well Location Plat for

**Petro-Hunt, L.L.C. Lamb Trust #31B-1-1**

DESIGNED	SURVEYED	CHECKED	DRAWN	PROJECT NO.	SHEET NO.
DATE	T.W.G.	T.R.G.	T.R.G.	0606-130	1
09/06/06		WELL_LOC..	SCALE 1\"=1000'		



**State of Utah**

**Department of  
Natural Resources**

MICHAEL R. STYLER  
*Executive Director*

**Division of  
Oil, Gas & Mining**

JOHN R. BAZA  
*Division Director*

JON M. HUNTSMAN, JR.  
*Governor*

GARY R. HERBERT  
*Lieutenant Governor*

January 18, 2007

Petro-Hunt, LLC  
258 - 119th Ave., SW  
Killdeer, ND 58640

Re: Lamb Trust 31B-1-1 Well, 712' FNL, 2584' FWL, NE NW, Sec. 31,  
T. 15 South, R. 3 East, Sanpete County, Utah

Gentlemen:

Pursuant to the provisions and requirements of Utah Code Ann. § 40-6-1 *et seq.*, Utah Administrative Code R649-3-1 *et seq.*, and the attached Conditions of Approval, approval to drill the referenced well is granted.

Appropriate information has been submitted to DOGM and administrative approval of the requested exception location is hereby granted.

This approval shall expire one year from the above date unless substantial and continuous operation is underway, or a request for extension is made prior to the expiration date. The API identification number assigned to this well is 43-039-30034.

Sincerely,

Gil Hunt  
Associate Director

pab  
Enclosures

cc: Sanpete County Assessor



Operator: Petro-Hunt, LLC  
Well Name & Number Lamb Trust 31B-1-1  
API Number: 43-039-30034  
Lease: Fee

Location: NE NW Sec. 31 T. 15 South R. 3 East

### Conditions of Approval

1. **General**

Compliance with the requirements of Utah Admin. R. 649-1 *et seq.*, the Oil and Gas Conservation General Rules, and the applicable terms and provisions of the approved Application for Permit to Drill.

2. **Notification Requirements**

The operator is required to notify the Division of Oil, Gas and Mining of the following actions during drilling of this well:

- 24 hours prior to cementing or testing casing
- 24 hours prior to testing blowout prevention equipment
- 24 hours prior to spudding the well
- within 24 hours of any emergency changes made to the approved drilling program
- prior to commencing operations to plug and abandon the well

The following are Division of Oil, Gas and Mining contacts and their work telephone numbers (please leave a voice mail message if the person is not available to take the call):

- Dan Jarvis at (801) 538-5338
- Carol Daniels at (801) 538-5284 (spud)

3. **Reporting Requirements**

All required reports, forms and submittals will be promptly filed with the Division, including but not limited to the Entity Action Form (Form 6), Report of Water Encountered During Drilling (Form 7), Weekly Progress Reports for drilling and completion operations, and Sundry Notices and Reports on Wells requesting approval of change of plans or other operational actions.

4. Compliance with the Conditions of Approval/Application for Permit to Drill outlined in the Statement of Basis. (Copy Attached)

5. Operator shall comply with applicable recommendations resulting from Resource Development Coordinating Committee review. Statements attached.

6. This proposed well is located in an area for which drilling units (well spacing patterns) have not been established through an order of the Board of Oil, Gas and Mining (the "Board"). In order to avoid the possibility of waste or injury to correlative rights, the operator is requested, once the well has been drilled, completed, and has produced, to analyze geological and engineering data generated therefrom, as well as any similar data from surrounding areas if available. As soon as is practicable after completion of its analysis, and if the analysis suggests an area larger than the quarter-quarter section upon which the well is located is being drained, the operator is requested to seek an appropriate order from the Board establishing drilling and spacing units in conformance with such analysis by filing a Request for Agency Action with the Board.
7. Surface casing shall be cemented to the surface.

STATE OF UTAH  
DEPARTMENT OF NATURAL RESOURCES  
DIVISION OF OIL, GAS AND MINING

CONFIDENTIAL

FORM 9

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.

1. TYPE OF WELL OIL WELL <input checked="" type="checkbox"/> GAS WELL <input type="checkbox"/> OTHER <input type="checkbox"/>		5. LEASE DESIGNATION AND SERIAL NUMBER: <u>Patented</u>
2. NAME OF OPERATOR: <u>Petro Hunt LLC</u>		6. IF INDIAN, ALLOTTEE OR TRIBE NAME: <u>N/A</u>
3. ADDRESS OF OPERATOR: <u>258 119th Ave S</u> CITY <u>Killdeer</u> STATE <u>ND</u> ZIP <u>58640</u>		7. UNIT or CA AGREEMENT NAME: <u>N/A</u>
4. LOCATION OF WELL FOOTAGES AT SURFACE: <u>712' FNL 2584' FWL</u> QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: <u>NENW 31 15S 3E 5</u>		8. WELL NAME and NUMBER: <u>LAAA Trust 31A-1-1</u>
PHONE NUMBER: <u>701-863-6622</u>		9. API NUMBER: <u>43-039-30034</u>
		10. FIELD AND POOL, OR WILDCAT: <u>Wildcat</u>
		COUNTY: <u>Slope</u>
		STATE: <u>UTAH</u>

11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION		
<input checked="" type="checkbox"/> NOTICE OF INTENT (Submit in Duplicate) Approximate date work will start: _____	<input type="checkbox"/> ACIDIZE	<input type="checkbox"/> DEEPEN	<input type="checkbox"/> REPERFORATE CURRENT FORMATION
	<input type="checkbox"/> ALTER CASING	<input type="checkbox"/> FRACTURE TREAT	<input type="checkbox"/> SIDETRACK TO REPAIR WELL
	<input type="checkbox"/> CASING REPAIR	<input type="checkbox"/> NEW CONSTRUCTION	<input type="checkbox"/> TEMPORARILY ABANDON
	<input type="checkbox"/> CHANGE TO PREVIOUS PLANS	<input type="checkbox"/> OPERATOR CHANGE	<input type="checkbox"/> TUBING REPAIR
	<input type="checkbox"/> CHANGE TUBING	<input type="checkbox"/> PLUG AND ABANDON	<input type="checkbox"/> VENT OR FLARE
<input type="checkbox"/> SUBSEQUENT REPORT (Submit Original Form Only) Date of work completion: _____	<input type="checkbox"/> CHANGE WELL NAME	<input type="checkbox"/> PLUG BACK	<input type="checkbox"/> WATER DISPOSAL
	<input type="checkbox"/> CHANGE WELL STATUS	<input type="checkbox"/> PRODUCTION (START/RESUME)	<input type="checkbox"/> WATER SHUT-OFF
	<input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS	<input type="checkbox"/> RECLAMATION OF WELL SITE	<input checked="" type="checkbox"/> OTHER: <u>Extension</u>
	<input type="checkbox"/> CONVERT WELL TYPE	<input type="checkbox"/> RECOMPLETE - DIFFERENT FORMATION	

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.

Sundry for extension of approved drilling permit.

Approved by the  
Utah Division of  
Oil, Gas and Mining

Date: 01-07-08  
By: [Signature]

NAME (PLEASE PRINT) L. Michael Endred TITLE Production Manager  
SIGNATURE [Signature] DATE 1-4-08

(This space for State use only)

(5/2000)

COPY SENT TO OPERATOR  
Date: 1-8-2008  
Initials: VS

(See Instructions on Reverse Side)

RECEIVED

JAN 07 2008

DIV. OF OIL, GAS & MINING

**Application for Permit to Drill  
Request for Permit Extension  
Validation**

(this form should accompany the Sundry Notice requesting permit extension)

API: 43 039-30034

Well Name: LAMB TRUST 31B-1-1

Location: 712' ENL 2584 FWL SEC 31 T15S, R3E, Sanpete Co, Utah

Company Permit Issued to: Petro Hunt LLC

Date Original Permit Issued: 1-18-07

The undersigned as owner with legal rights to drill on the property as permitted above, hereby verifies that the information as submitted in the previously approved application to drill, remains valid and does not require revision.

Following is a checklist of some items related to the application, which should be verified.

If located on private land, has the ownership changed, if so, has the surface agreement been updated? Yes ☐ No ☒

Have any wells been drilled in the vicinity of the proposed well which would affect the spacing or siting requirements for this location? Yes ☐ No ☒

Has there been any unit or other agreements put in place that could affect the permitting or operation of this proposed well? Yes ☐ No ☒

Have there been any changes to the access route including ownership, or right-of-way, which could affect the proposed location? Yes ☐ No ☒

Has the approved source of water for drilling changed? Yes ☐ No ☒

Have there been any physical changes to the surface location or access route which will require a change in plans from what was discussed at the onsite evaluation? Yes ☐ No ☒

Is bonding still in place, which covers this proposed well? Yes ☒ No ☐

J. Michael Enchel  
Signature

1-4-08  
Date

Title: Prod. Manager

Representing: Petro Hunt LLC

**RECEIVED**

**JAN 07 2008**

**DIV. OF OIL, GAS & MINING**

**STATE OF UTAH**  
DEPARTMENT OF NATURAL RESOURCES  
DIVISION OF OIL, GAS AND MINING

FORM 9

**SUNDRY NOTICES AND REPORTS ON WELLS**

Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.

1 TYPE OF WELL OIL WELL <input checked="" type="checkbox"/> GAS WELL <input type="checkbox"/> OTHER _____		5 LEASE DESIGNATION AND SERIAL NUMBER: PATENTED
2 NAME OF OPERATOR: PETRO-HUNT, L. L. C.		6 IF INDIAN, ALLOTTEE OR TRIBE NAME: N/A
3 ADDRESS OF OPERATOR: 258 119TH AVENUE S.W. CITY KILLDEER STATE ND ZIP 58640		7 UNIT or CA AGREEMENT NAME: N/A
4 LOCATION OF WELL FOOTAGES AT SURFACE: 1569' FNL & 1154' FEL		8 WELL NAME and NUMBER: RON LAMB 31A-4-1
QTR/QTR. SECTION, TOWNSHIP, RANGE, MERIDIAN: SENE 31 15S 3E S		9 API NUMBER: 4303930034
COUNTY: SANPETE		10 FIELD AND POOL OR WILDCAT: WILDCAT
STATE: UTAH		

11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION		
<input checked="" type="checkbox"/> NOTICE OF INTENT (Submit In Duplicate) Approximate date work will start: 10/1/2008	<input type="checkbox"/> ACIDIZE	<input type="checkbox"/> DEEPEN	<input type="checkbox"/> REPERFORATE CURRENT FORMATION
	<input checked="" type="checkbox"/> ALTER CASING	<input type="checkbox"/> FRACTURE TREAT	<input type="checkbox"/> SIDETRACK TO REPAIR WELL
	<input type="checkbox"/> CASING REPAIR	<input type="checkbox"/> NEW CONSTRUCTION	<input type="checkbox"/> TEMPORARILY ABANDON
	<input checked="" type="checkbox"/> CHANGE TO PREVIOUS PLANS	<input type="checkbox"/> OPERATOR CHANGE	<input type="checkbox"/> TUBING REPAIR
	<input type="checkbox"/> CHANGE TUBING	<input type="checkbox"/> PLUG AND ABANDON	<input type="checkbox"/> VENT OR FLARE
<input type="checkbox"/> SUBSEQUENT REPORT (Submit Original Form Only) Date of work completion:	<input checked="" type="checkbox"/> CHANGE WELL NAME	<input type="checkbox"/> PLUG BACK	<input type="checkbox"/> WATER DISPOSAL
	<input type="checkbox"/> CHANGE WELL STATUS	<input type="checkbox"/> PRODUCTION (START/RESUME)	<input type="checkbox"/> WATER SHUT-OFF
	<input type="checkbox"/> COMINGLE PRODUCING FORMATIONS	<input type="checkbox"/> RECLAMATION OF WELL SITE	<input type="checkbox"/> OTHER: _____
	<input type="checkbox"/> CONVERT WELL TYPE	<input type="checkbox"/> RECOMPLETE - DIFFERENT FORMATION	

12 DESCRIBE PROPOSED OR COMPLETED OPERATIONS Clearly show all pertinent details including dates, depths, volumes, etc

Petro-Hunt, L. L. C. proposes to move the originally permitted Lamb Trust 31B-1-1 well from 712' FNL & 2584' FWL of Section 31, T15S, R3E, S. L. B. & M., Sanpete County, UT, to a new surface location. The new well will be the Ron Lamb 31A-4-1 well located 1569' FNL & 1154' FEL of Section 31, T15S, R3E, S. L. B. & M., Sanpete County, UT. The landowner will remain the same. A drilling pad was built in preparation to drill the Lamb Trust 31B-1-1 well and a portion of those materials will be utilized on the new location for the Ron Lamb 31A-4-1 well. Please see attached location plat.

Petro-Hunt, L. L. C. also proposes to drill the Ron Lamb 31A-4-1 well to a total permitted depth of 16,000' MD. Please see attached revised drilling plan and BOPE schematic.

Please see attached revised casing design.

**COPY SENT TO OPERATOR**

Date: 8.14.2008

Initials: KG

**CONFIDENTIAL**

NAME (PLEASE PRINT) <u>Cary J. Vice</u>	TITLE <u>Sr. Drilling Engineer</u>
SIGNATURE <u>Cary J. Vice</u>	DATE <u>6/24/2008</u>

(This space for State use only)

**APPROVED BY THE STATE  
OF UTAH DIVISION OF  
OIL, GAS, AND MINING**

DATE: 08-13-08 (See Instructions on Reverse Side)

BY: [Signature]

\* Surface casing shall be cemented back to surface  
\* Production casing shall be cemented back inside  
intermediate shoe (± 8000' MD)

**RECEIVED**

**JUL 09 2008**

DIV. OF OIL, GAS & MINING

STATE OF UTAH  
DEPARTMENT OF NATURAL RESOURCES  
DIVISION OF OIL, GAS AND MINING

FORM 3

AMENDED REPORT ☒  
(highlight changes)

APPLICATION FOR PERMIT TO DRILL			5. MINERAL LEASE NO: Patented	6. SURFACE: Fee
1A. TYPE OF WORK: DRILL <input checked="" type="checkbox"/> REENTER <input type="checkbox"/> DEEPEN <input type="checkbox"/>			7. IF INDIAN, ALLOTTEE OR TRIBE NAME: N/A	
B. TYPE OF WELL: OIL <input checked="" type="checkbox"/> GAS <input type="checkbox"/> OTHER _____ SINGLE ZONE <input type="checkbox"/> MULTIPLE ZONE <input checked="" type="checkbox"/>			8. UNIT or CA AGREEMENT NAME: N/A	
2. NAME OF OPERATOR: PETRO-HUNT, L.L.C.			9. WELL NAME and NUMBER: RON LAMB TRUST 31A-4-1	
3. ADDRESS OF OPERATOR: 258 - 119th Ave. SW CITY Killdeer STATE ND ZIP 58640		PHONE NUMBER: (701) 863-6622	10. FIELD AND POOL, OR WILDCAT: Wildcat	
4. LOCATION OF WELL (FOOTAGES) AT SURFACE: 1,569' FNL & 1,154' FEL AT PROPOSED PRODUCING ZONE:			11. QTR/CTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: SENE 31 15S 3E S	
14. DISTANCE IN MILES AND DIRECTION FROM NEAREST TOWN OR POST OFFICE: 1.35 miles south of Wales, Utah			12. COUNTY: Sanpete	13. STATE: UTAH
15. DISTANCE TO NEAREST PROPERTY OR LEASE LINE (FEET) 1,154'		16. NUMBER OF ACRES IN LEASE: 21	17. NUMBER OF ACRES ASSIGNED TO THIS WELL: 40	
18. DISTANCE TO NEAREST WELL (DRILLING, COMPLETED, OR APPLIED FOR) ON THIS LEASE (FEET) None		19. PROPOSED DEPTH: 16,000	20. BOND DESCRIPTION: Statewide Surety RLB0008181	
21. ELEVATIONS (SHOW WHETHER DF, RT, GR, ETC.): 5,545' GR		22. APPROXIMATE DATE WORK WILL START: 10/1/2008	23. ESTIMATED DURATION: 90 days	

24. PROPOSED CASING AND CEMENTING PROGRAM				
SIZE OF HOLE	CASING SIZE, GRADE, AND WEIGHT PER FOOT			SETTING DEPTH
26"	20"	H-40 BTC	94.0 #	1,000
17-1/2"	13-3/8"	K-55 BTC	68.0#	4,500
12-1/4"	9-5/8"	L-80 LTC	47.0#	8,300
8-1/2"	5-1/2"	L-80 BTC	20.0#	16,000
				API = 4303930034

25. ATTACHMENTS	
VERIFY THE FOLLOWING ARE ATTACHED IN ACCORDANCE WITH THE UTAH OIL AND GAS CONSERVATION GENERAL RULES:	
<input checked="" type="checkbox"/> WELL PLAT OR MAP PREPARED BY LICENSED SURVEYOR OR ENGINEER	<input checked="" type="checkbox"/> COMPLETE DRILLING PLAN
<input type="checkbox"/> EVIDENCE OF DIVISION OF WATER RIGHTS APPROVAL FOR USE OF WATER	<input type="checkbox"/> FORM 5, IF OPERATOR IS PERSON OR COMPANY OTHER THAN THE LEASE OWNER

**CONFIDENTIAL**

NAME (PLEASE PRINT) <u>Don Hamilton</u>	TITLE <u>Agent for Petro-Hunt, L.L.C</u>
SIGNATURE <u>Don Hamilton</u>	DATE <u>6/26/2008</u>

(This space for State use only)


API NUMBER ASSIGNED: \_\_\_\_\_

APPROVAL: \_\_\_\_\_

RECEIVED  
JUL 09 2008

DIV. OF OIL, GAS & MINING

# Section 31, T.15 S., R.3 E., S.L.B. & M.



## PROJECT Petro-Hunt, L.L.C.

WELL LOCATION, LOCATED AS SHOWN IN THE S.E. 1/4 OF THE N.E. 1/4 OF SECTION 31, T.15 S., R.3 E., S.L.B. & M. SANPETE COUNTY, UTAH

### LEGEND

- ✕ = SECTION CORNERS (LOCATED)
- ✕ = QUARTER SECTION CORNERS (LOCATED)
- ✕ = SECTION CORNERS (NOT LOCATED)
- ✕ = QUARTER SECTION CORNERS (NOT LOCATED)
- ⊙ = PROPOSED WELL HEAD

NOTE: THE PURPOSE OF THIS SURVEY WAS TO PLAT THE PETRO-HUNT, L.L.C. RON LAMB No. 31A-4-1 LOCATION, LOCATED IN THE S.E. 1/4 OF THE N.E. 1/4 OF SECTION 31, T.15 S., R.3 E., S.L.B. & M., SANPETE COUNTY, UTAH.

### BASIS OF ELEVATION

ELEVATION BASED ON THE SOUTHWEST CORNER OF SECTION 6, T.16 S., R.3 E., S.L.B. & M. WHICH IS A SANPETE COUNTY ALUM CAP WITH AN ELEVATION OF 5559.00'.



### CERTIFICATE

THIS IS TO CERTIFY THAT THIS PLAT WAS PREPARED FROM FIELD NOTES OF ACTUAL SURVEYS MADE BY ME OR UNDER MY SUPERVISION, AND THAT THE SAME ARE TRUE AND CORRECT TO THE BEST OF MY KNOWLEDGE AND BELIEF.



**Jones & DeMille Engineering**  
1535 South 100 West - Richfield, Utah 84701  
Phone (435) 896-8266  
Fax (435) 896-8268  
www.jonesanddemille.com

### Well Location Plat for


**Petro-Hunt, L.L.C. Ron Lamb No. 31A-4-1**

DESIGNED	SURVEYED	CHECKED	DRAWN	PROJECT NO.	SHEET NO.
-	K.O.B.	T.R.G.	T.W.G.	0805-198	1
DATE	DWG NAME	SCALE			
05/27/08	WELL_LOC..	1"=1000'			


Cut = 13,205 c.y. (INCLUDES PIT AND RIG FOUNDATION EXCAVATION)  
Fill = 8,617 c.y. (NO SHRINK APPLIED)  
Net = 4,588 c.y.  
ESTIMATED UNCOMPACTED EMBANKMENT (• 20% SHRINK): 2865 c.y.

PIT CAPACITY (W/2' FREEBOARD): 37,007 bbls  
PIT EXCAVATION: 9,447 c.y.

PAD SURFACE AREA: 3.12 ac.  
PIT SURFACE AREA: 0.55 ac.  
DISTURBED AREA: 3.75 ac.




**PETRO HUNT**  
**LOCATION LAYOUT FOR**  
**RON LAMB No. 31A-4-1 WELL**  
**SECTION 31, T.15S., R.3E., S.L.B. & M.**








**PETRO HUNT  
LOCATION LAYOUT FOR  
RON LAMB No. 31A-4-1 WELL  
SECTION 31, T.15S., R.3E., S.L.B. & M.**





**SECTION 11+00**



**SECTION 11+60**



**SECTION 12+60**



**SECTION 14+00**

DATE	08/25/2008
BY	CS-01
CHECKED	
APPROVED	
PROJECT NUMBER	0805-198
CROSS SECTIONS	
RON LAMB NO. 31A-4-1	
PETRO HUNT	
SANPETE COUNTY	
SHEET NO.	CS-01



## DRILLING PLAN

### APPROVAL OF OPERATIONS

6-25-08 Revised

#### Attachment for Form 9 – Sundry Notices and Reports on Wells

Name of Operator: Petro-Hunt, L. L. C.  
Address: 258 119<sup>th</sup> Avenue S.W.  
Killdeer, ND 58640

Well Location: Ron Lamb 31A-4-1  
Sanpete County, UT

1. GEOLOGIC SURFACE FORMATION Tertiary Undivided

2. ESTIMATED DEPTHS OF IMPORTANT GEOLOGIC MARKERS

<u>Formation</u>	<u>Depth MD</u>
Jurassic Upper Twin Creek	8,550'
Jurassic Lower Twin Creek	9,100'
Jurassic Navajo	9,550'
Jurassic Lower Twin Creek	13,000'
Jurassic Navajo	13,450'
Proposed Total Depth	16,000'

3. ESTIMATED DEPTHS OF ANTICIPATED WATER, OIL, GAS OR MINERALS

<u>Formation</u>	<u>Depth</u>	<u>Type</u>
Jurassic Lower Twin Creek	9,100'	Oil
Jurassic Navajo	9,550'	Oil
Jurassic Lower Twin Creek	13,000'	Oil
Jurassic Navajo	13,450'	Oil

4. PROPOSED CASING PROGRAM

All casing used to drill this well will be new casing.

<u>Type</u>	<u>Size</u>	<u>Weight</u>	<u>Grade</u>	<u>Conn.</u>	<u>Top</u>	<u>Bottom</u>	<u>Hole</u>
Conductor	20"	94.0 ppf	H-40	BTC	0'	1000'	26"
Surface	13-3/8"	68.0 ppg	K-55	BTC	0'	4,500'	17-1/2"
Intermediate	9-5/8"	47.0 ppf	L-80	LTC	0'	8,300'	12-1/4"
Production	5-1/2"	20.0 ppf	L-80	BTC	0'	16,000'	8-1/2"

Note: The drilled depth of the surface hole and the setting depth of the surface casing may vary from 4,000' to 4,500'.  
Should a lost circulation zone be encountered while drilling, casing will be set approximately 300' below the lost circulation zone. If no lost circulation zone is encountered, casing to be set at 4,500'±.

5. OPERATOR'S MINIMUM SPECIFICATIONS FOR PRESSURE CONTROL

Conductor hole: No BOPE will be utilized. Air, foam, mist, rotating head and diverter system may be utilized.

Surface hole: No BOPE will be utilized. Air, foam, mist, rotating head and diverter system may be utilized.

Intermediate hole: Prior to drilling out the surface casing shoe, intermediate and drilling liner, 5,000 psi or greater BOP equipment will be installed. The pipe rams will be operated at least once per day below surface casing to total depth if operations permit. The blind rams will be functioned once per day from below surface casing to total depth if operations permit.

**CONFIDENTIAL**



**RON LAMB 31A-4-1  
SANPETE COUNTY, UTAH  
DRILLING PLAN**

A diagram of the planned BOP equipment for normal drilling operations in this area is attached. There will be two valves and one check valve on the kill line, two valves on the choke line, and an adjustable choke on the manifold system. The BOP "stack" will consist of two BOP rams (1 pipe, 1 blind), rated to 5,000 psi working pressure and one annular type preventer, rated to a minimum of 5,000 psi working pressure.

The BOP equipment will be pressure tested prior to drilling out surface casing shoe and anytime a new casing string is set. All test pressures will be maintained for five (5) minutes without any significant pressure decrease. Clear water will be circulated into the BOP stack and lines prior to pressure testing. The following test pressures will be used as a minimum for various equipment items.

1.	Annular BOP	1,500 psi
2.	Ram type BOP	5,000 psi
3.	Kill line valves	5,000 psi
4.	Choke line valves and choke manifold valves	5,000 psi
5.	Chokes	5,000 psi
6.	Casing, casinghead & weld	1,500 psi
7.	Upper kelly cock and safety valve	5,000 psi
8.	Dart valve	5,000 psi

**6. MUD SYSTEMS**

- A freshwater / gel system will be used to drill the conductor and surface hole.
- A salt saturated mud system will be used to drill well thru the anticipated salt section.
- A lignosulfonate system will be used to drill the well below the salt section to total depth.
- The mud system will be monitored manually/visually.

<u>Depths</u>	<u>Mud Weight (ppg)</u>	<u>Mud System</u>
0' – 1,000'	8.4 – 9.0	Freshwater / gel system
1,000' – 4,500'	8.6 – 9.0	Freshwater / gel system
4,500' – 8,300'	9.0 – 10.5	Saturated salt mud system
8,300 – 16,000'	9.0 – 10.4	Lignosulfonate mud system

**7. AUXILIARY EQUIPMENT TO BE USED**

- a. Kelly cock.
- b. Full opening valve with drill pipe connection will be kept on floor. Valve will be used when the kelly is not in string.

**8. TESTING, LOGGING, AND CORING PROGRAMS TO BE FOLLOWED**

- A drillstem test in the Navajo is possible.
- Four electric wireline logs will be runs from total depth to surface are anticipated for this well.
- The gamma ray will be left on to record from total depth to surface.
- Other log curves (resistivity, porosity, and caliper) will record from total depth to surface.
- A dipmeter and rotary sidewall cores may be run over selected intervals.

**9. ANTICIPATED ABNORMAL PRESSURES OR TEMPERATURES EXPECTED**

- Expected BHP 8,070 psi (approximately equal to normal 9.7 ppg pressure gradient)
- No abnormal temperature or pressures are anticipated.
- The formations to be penetrated do not contain known H<sub>2</sub>S gas.

**10. WATER SUPPLY**

- The water supply for construction, drilling and operations will be provided from two existing privately owned water wells in the area.
- No new water well is proposed with this application.
- Should additional water sources be pursued they will be properly permitted through the State of Utah – Division of Water Rights

**RON LAMB 31A-4-1**  
**SANPETE COUNTY, UTAH**  
**DRILLING PLAN**

**11. CEMENT SYSTEMS\***

**a. Conductor Cement:**

- Drill 26" hole to 1,000'±, run and cement 20" to surface (depth to vary based on depth of lost circulation zone).
- Pump 20 bbls fresh water spacer. Displace with mud.
- Casing to be run with: a) double valve float shoe b) twelve (12) centralizers, two on the first joint and one per joint for the next ten joints c) pump job with top plug only.
- Cement the casing annulus to surface. Top out job to be performed if needed, a 1" tubing string may or may not be utilized.

<u>Type</u>	<u>Sacks</u>	<u>Interval</u>	<u>Density</u>	<u>Yield</u>	<u>Hole</u> <u>Volume</u>	<u>Cement</u> <u>Volume</u>
Lead	710	0'-650'	12.7 ppg	1 769 CFS	624 CF	1247 CF
Tail	640	650'-1,000'	15.6 ppg	1 198 CFS	335CF	671 CF
Top Out	200	0'-80'	14.6 ppg	1.552 CFS	180 CF	310 CF

Conductor design volumes based on 100% excess of gauge hole. (Typical design, subject to change).

Lead Mix:	ECONOCEM + 2% Calcium Chloride + .125#/sx Poly-E-Flake			
Slurry yield:	1 769 cf/sack	Slurry weight:	12.7 #/gal	
Water requirement:	9.491 gal/sack			
Tail Mix:	Premium + 2% CaCl + .125 #/sx Poly-E-Flake			
Slurry yield:	1.198 cf/sack	Slurry weight:	15.6 #/gal	
Water requirement:	5.251 gal/sack			
Top Out:	Premium + 12% Cal-Seal 60 + 3% Versaset			
Slurry yield:	1.552 cf/sack	Slurry weight:	14.60 #/gal.	
Water requirement:	7.374 gal/sack			

**b. Surface Cement:**

- Drill 17-1/2" hole to 4,500'±, run and cement 13-3/8" to surface (depth to vary based on depth of lost circulation zone).
- Pump 40 bbls Mud Flush III spacer. Displace with mud.
- Casing to be run with: a) float shoe b) float collar c) twelve (12) centralizers, two on the first joint and one per joint for the next ten joints d) bottom two joints thread locked f) pump job with top and bottom plugs.
- Cement the casing annulus to surface. Top out job to be performed if needed, a 1" tubing string may or may not be utilized.

<u>Type</u>	<u>Sacks</u>	<u>Interval</u>	<u>Density</u>	<u>Yield</u>	<u>Hole</u> <u>Volume</u>	<u>Cement</u> <u>Volume</u>
Lead	1330	0'-4,000'	11.6 ppg	3.137 CFS	2083 CF	3125 CF
Tail	470	4,000'-4,500'	15.6 ppg	1.198 CFS	347CF	520 CF
Top Out	100	0'-100'	15.6 ppg	1.198 CFS	101 CF	310 CF

Surface design volumes based on 50% excess of gauge hole. (Typical design, subject to change).

Lead Mix:	ECONOCEM			
	Slurry yield:	3.13798 cf/sack	Slurry weight:	11.6 #/gal.
	Water requirement:	17.903 gal/sack		
Tail Mix:	Premium + 2% CaCl + .125 #/sx Poly-E-Flake			
	Slurry yield:	1.198 cf/sack	Slurry weight:	15.6 #/gal.
	Water requirement:	5.251 gal/sack		
Top Out:	Premium + 12% Cal-Seal +3% Versaset			
	Slurry yield:	1.552 cf/sack	Slurry weight:	14.6 #/gal.
	Water requirement:	7.374 gal/sack		

**RON LAMB 31A-4-1**  
**SANPETE COUNTY, UTAH**  
**DRILLING PLAN**

c. Intermediate Casing Cement:

- Drill 12-1/4" hole to 8,300'  $\pm$ , run and cement 9-5/8"
- Pump 40 bbl Tuned Spacer III. Displace with 8.4 ppg salt saturated mud.
- Casing to be run with: a) float shoe b) float collar c) twelve (12) centralizers, two on the first joint and one per joint for the next ten joints d) bottom two joints thread locked f) pump job with top and bottom plugs.

Type	Sacks	Interval	Density	Yield	Hole Volume	Cement Volume
Lead	720	3500'–7,300'	11.0 ppg*	1.472 CFS*	1211 CF	1431 CF
Tail	290	7,300' – 8,300'	14.3 ppg	1.472 CFS	313 CF	391 CF

\* = density & yield prior to foaming.

Intermediate design volumes are estimates based on 25% excess of gauge hole. Actual volumes will be calculated from caliper log to bring cement to 1,000' above 13 3/8" surface casing shoe + 15% excess. (Typical design, subject to change).

Lead Mix: ELASTISEAL + 20% SSA-1 + 5#/sx Silicalite + .1% Versaset + 1.5% FDP-C760-04 + .5% FDP-C766-05

Slurry yield:	1.472 cf/sack *	Slurry weight:	14.3 #/gal*
Water requirement:	6.399 gal/sack	Slurry weight:	11.0 #/gal (after foam)

\* = density & yield prior to foaming

Tail Mix: ELASTISEAL + 20% SSA-1 + 5#/sx Silicalite + .1% Versaset + .5% FDP-C766-05

Slurry yield:	1.472 cf/sack	Slurry weight:	14.3 #/gal.
Water requirement:	6.399 gal/sack		

d. Production Casing Cement:

- Drill 8-1/2" hole to 16,000'  $\pm$ , run and cement 5 1/2" production casing.
- Pump 40 bbl 8.4 ppg Mud Flush III spacer.
- Displace with 2% KCL completion fluid.

Type	Sacks	Interval	Density	Yield	Hole Volume	Cement Volume
Lead	710	10,000'– 14,500'	13.0 ppg	1.826 CFS	1030 CF	1288 CF
Lead	320	14,500'– 16,000'	14.35 ppg	1.419 CFS	343 CF	429 CF

Production design volumes are estimates based on 25% excess of gauge hole. Actual volumes will be calculated from caliper log + 15% excess. (Typical design, subject to change)

Lead Mix: 50/50 Poz + .3% CFR3 + .4% HR5 + .4% Halad R344 + 20% SSA-1

Slurry yield:	1.826 cf/sack	Slurry weight:	13.0 #/gal.
Water requirement:	9.161 gal/sack		

Tail Mix: 50/50 Poz + .3% CFR3 + .4% HR5 + .4% Halad R344 + 20% SSA-1 + .2% Super CBL.


Slurry yield:	1.419 cf/sack	Slurry weight:	14.35 #/gal.
Water requirement:	6.108 gal/sack		

\* Actual cement designs may vary dependent upon selected vendor, casing depths, temperatures and well conditions.

**12. ANTICIPATED STARTING DATE AND DURATION OF THE OPERATIONS**

Starting Date:	October 1, 2008
Duration:	100 Days

BOP STACK AND  
CHOKE MANIFOLD  
SCHEMATIC



# CASING DESIGN CHART

WELL:

RON LAMB 31A-4-1

FIELD:

WILDCAT - SANPETE COUNTY, UT

06/16/08

CJV




SIZE	WT/FT	GRADE	CONN	LENGTH OF SECTION	SETTING DEPTH TVD	SETTING DEPTH MD	EST. MUD WT.	PRESS GRAD PPG/FT	EST. BHP MW-7ppg	EST. FRAC. GRAD, PPG	EST. GAS GRAD.	CALC HYDRO PRESS	WT IN AIR		COLLAPSE RATING		TENS. STRENGTH		BURST RATING
													SECTION 1000 LBS	CUMM 1000 LBS	100% PSI	ADJUSTED TENSILE	JOINT 1000 LBS	BODY 1000 LBS	
30	.375" wall	B	P.E.	80	80	80													
20"	94.00	H40	BTC	1000	1000	1000	9	0.468	0.432	12.1	0.10	468	94	94	520	520	1041	1077	1530
13 3/8"	68.00	K55	BTC	4500	4500	4500	9	0.468	0.432	14.4	0.10	2106	306	306	1950	1950	1300	1069	3450
9 5/8"	47.00	L80	LTC	8300	8300	8300	10.5	0.546	0.510	16.0	0.10	4532	390	390	4760	4760	893	1086	6970
5 1/2"	20.00	L80	BTC	14200	14200	14200	10.4	0.541	0.504	N/A	0.15	7679	284	284	8830	8830	503	466	8990
2 7/8" Tbg	6.50	L80	EUE	14000	14000	14000	10.4	0.541	0.504	N/A	0.15	7571	91	91	11170	11170	145	145	10570

SIZE	SAFETY FACTORS									
	DRILLING			PROD.						
	COL	TENS	BURST	BURST	ASP	ASP	DRIFT	PR	CSG	CPLG
20"	1.100	1.600	1.200	1.200	DRLG	PROD	BODY	I. D.	I. D.	O. D.
13 3/8"	1.413	11.074	2.89	N/A	529	N/A	18.936	19.124	19.124	21
9 5/8"	1.178	3.493	1.2	N/A	2920	N/A	12.259	12.415	12.415	14.375
5 1/2"	1.500	2.289	2.20	N/A	3130	5575	SP DFT 8.625	8.681	8.681	10.625
2 7/8" Tbg	1.591	1.641	N/A	1.613	N/A	5575	4.767	4.892	4.892	6.050
	2.042	1.593	N/A	1.896	N/A	5575	2.347	2.441	2.441	3.668
BHP = MUD WT @ TD - 0.7 PPG X .052 X TVD =							7162			



# 43039300340000 Ron Lamb Trust 31A-4-1

## Casing Schematic



Well name:	<b>43039300340000 Ron Lamb Trust 31A-4-1</b>		
Operator:	<b>Petro-Hunt L.L.C.</b>		
String type:	Conductor	Project ID:	43-039-30034 (rev 2006-11)
Location:	Sanpete County		

**Design parameters:**
**Collapse**

Mud weight: 9.000 ppg  
Internal fluid density: 2.330 ppg

**Minimum design factors:**
**Collapse:**

Design factor 1.125

**Environment:**

H2S considered? No  
Surface temperature: 75 °F  
Bottom hole temperature: 89 °F  
Temperature gradient: 1.40 °F/100ft  
Minimum section length: 250 ft

**Burst:**

Design factor 1.00

Cement top: 314 ft

**Burst**

Max anticipated surface pressure: 347 psi  
Internal gradient: 0.120 psi/ft  
Calculated BHP 467 psi

No backup mud specified.

**Tension:**

8 Round STC: 1.80 (J)  
8 Round LTC: 1.80 (J)  
Buttress: 1.60 (J)  
Premium: 1.50 (J)  
Body yield: 1.50 (B)

**Non-directional string.**

Tension is based on buoyed weight.  
Neutral point: 866 ft

Run Seq	Segment Length (ft)	Size (in)	Nominal Weight (lbs/ft)	Grade	End Finish	True Vert Depth (ft)	Measured Depth (ft)	Drift Diameter (in)	Internal Capacity (ft³)
1	1000	20	94.00	H-40	Buttress	1000	1000	18.999	1994.5

Run Seq	Collapse Load (psi)	Collapse Strength (psi)	Collapse Design Factor	Burst Load (psi)	Burst Strength (psi)	Burst Design Factor	Tension Load (Kips)	Tension Strength (Kips)	Tension Design Factor
1	346	520	1.501	467	1530	3.27	81	1041	12.79 J

Prepared Helen Sadik-Macdonald  
by: Div of Oil, Gas & Minerals

Phone: 801-538-5357  
FAX: 801-359-3940

Date: August 6, 2008  
Salt Lake City, Utah

**Remarks:**

Collapse is based on a vertical depth of 1000 ft, a mud weight of 9 ppg. An internal gradient of .121 psi/ft was used for collapse from TD to Collapse strength is based on the Westcott, Dunlop & Kemler method of biaxial correction for tension.

Burst strength is not adjusted for tension.

*Engineering responsibility for use of this design will be that of the purchaser.*

Well name:

**43039300340000 Ron Lamb Trust 31A-4-1**Operator: **Petro-Hunt L.L.C.**String type: **Surface**

Project ID:

43-039-30034 (rev 2006-11)

Location: **Sanpete County****Design parameters:****Collapse**

Mud weight: 9.000 ppg

Internal fluid density: 2.330 ppg

**Minimum design factors:****Collapse:**

Design factor 1.125

**Burst:**

Design factor 1.00

**Environment:**

H2S considered? No

Surface temperature: 75 °F

Bottom hole temperature: 138 °F

Temperature gradient: 1.40 °F/100ft

Minimum section length: 250 ft

Cement top: 656 ft

**Burst**

Max anticipated surface pressure:

3,531 psi

Internal gradient:

0.120 psi/ft

Calculated BHP

4,071 psi

Annular backup:

2.33 ppg

**Tension:**

8 Round STC: 1.80 (J)

8 Round LTC: 1.80 (J)

Buttress: 1.60 (J)

Premium: 1.50 (J)

Body yield: 1.50 (B)

Tension is based on buoyed weight.

Neutral point: 3,898 ft

**Non-directional string.****Re subsequent strings:**

Next setting depth: 8,300 ft

Next mud weight: 10.500 ppg

Next setting BHP: 4,527 psi

Fracture mud wt: 19.250 ppg

Fracture depth: 4,500 ft

Injection pressure: 4,500 psi

Run Seq	Segment Length (ft)	Size (in)	Nominal Weight (lbs/ft)	Grade	End Finish	True Vert Depth (ft)	Measured Depth (ft)	Drift Diameter (in)	Internal Capacity (ft³)
1	4500	13.375	68.00	K-55	Buttress	4500	4500	12.29	3782.8
Run Seq	Collapse Load (psi)	Collapse Strength (psi)	Collapse Design Factor	Burst Load (psi)	Burst Strength (psi)	Burst Design Factor	Tension Load (Kips)	Tension Strength (Kips)	Tension Design Factor
1	1559	1950	1.251	3531	3450	0.98	265	1069	4.03 B

From pressure @ next setting depth  
Casing cemented, true gradient probably  
less than 1 psi/ft → O.K. w/ PetroHunt  
assumptions

Prepared by: Helen Sadik-Macdonald  
Div of Oil, Gas & MineralsPhone: 801-538-5357  
FAX: 801-359-3940Date: August 6, 2008  
Salt Lake City, Utah**Remarks:**

Collapse is based on a vertical depth of 4500 ft, a mud weight of 9 ppg. An internal gradient of .121 psi/ft was used for collapse from TD to  
Collapse strength is based on the Westcott, Dunlop & Kemler method of biaxial correction for tension.

Burst strength is not adjusted for tension.

Engineering responsibility for use of this design will be that of the purchaser.

Well name:	<b>43039300340000 Ron Lamb Trust 31A-4-1</b>		
Operator:	<b>Petro-Hunt L.L.C.</b>	Project ID:	43-039-30034 (rev 2006-11)
String type:	Intermediate		
Location:	Sanpete County		

**Design parameters:**
**Collapse**

Mud weight: 10.500 ppg  
Internal fluid density: 2.330 ppg

**Minimum design factors:**
**Collapse:**

Design factor 1.125

**Environment:**

H2S considered? No  
Surface temperature: 75 °F  
Bottom hole temperature: 191 °F  
Temperature gradient: 1.40 °F/100ft  
Minimum section length: 1,500 ft

**Burst:**

Design factor 1.00

Cement top: 5,453 ft

**Burst**

Max anticipated surface pressure: 5,124 psi  
Internal gradient: 0.220 psi/ft  
Calculated BHP 6,950 psi

Annular backup: 2.33 ppg

**Tension:**

8 Round STC: 1.80 (J)  
8 Round LTC: 1.80 (J)  
Buttress: 1.60 (J)  
Premium: 1.50 (J)  
Body yield: 1.50 (B)

Tension is based on buoyed weight.  
Neutral point: 6,993 ft

**Non-directional string.**
**Re subsequent strings:**

Next setting depth: 16,000 ft  
Next mud weight: 10.400 ppg  
Next setting BHP: 8,644 psi  
Fracture mud wt: 19.250 ppg  
Fracture depth: 8,300 ft  
Injection pressure: 8,300 psi

Run Seq	Segment Length (ft)	Size (in)	Nominal Weight (lbs/ft)	Grade	End Finish	True Vert Depth (ft)	Measured Depth (ft)	Drift Diameter (in)	Internal Capacity (ft³)
1	8300	9.625	47.00	L-80	LT&C	8300	8300	8.625	3411.5

Run Seq	Collapse Load (psi)	Collapse Strength (psi)	Collapse Design Factor	Burst Load (psi)	Burst Strength (psi)	Burst Design Factor	Tension Load (Kips)	Tension Strength (Kips)	Tension Design Factor
1	3523	4760	1.351	5946	6870	1.16	329	893	2.72 J

Prepared by: Helen Sadik-Macdonald  
Div of Oil, Gas & Minerals

Phone: 801-538-5357  
FAX: 801-359-3940

Date: August 6, 2008  
Salt Lake City, Utah

**Remarks:**

Collapse is based on a vertical depth of 8300 ft, a mud weight of 10.5 ppg. An internal gradient of .121 psi/ft was used for collapse from TD. Collapse strength is based on the Westcott, Dunlop & Kemler method of biaxial correction for tension.

Burst strength is not adjusted for tension.

Engineering responsibility for use of this design will be that of the purchaser.

Well name:	<b>43039300340000 Ron Lamb Trust 31A-4-1</b>		
Operator:	<b>Petro-Hunt L.L.C.</b>	Project ID:	43-039-30034 (rev 2006-11)
String type:	Production		
Location:	Sanpete County		

**Design parameters:**
**Collapse**

Mud weight: 10.400 ppg  
Internal fluid density: 2.330 ppg

**Minimum design factors:**
**Collapse:**

Design factor 1.125

**Environment:**

H2S considered? No  
Surface temperature: 75 °F  
Bottom hole temperature: 299 °F  
Temperature gradient: 1.40 °F/100ft  
Minimum section length: 1,500 ft

**Burst:**

Design factor 1.00

Cement top: 10,675 ft

**Burst**

Max anticipated surface pressure: 5,124 psi  
Internal gradient: 0.220 psi/ft  
Calculated BHP 8,644 psi

No backup mud specified.

**Tension:**

8 Round STC: 1.80 (J)  
8 Round LTC: 1.80 (J)  
Buttress: 1.60 (J)  
Premium: 1.50 (J)  
Body yield: 1.50 (B)

**Non-directional string.**

Tension is based on buoyed weight.

Neutral point: 13,481 ft

Run Seq	Segment Length (ft)	Size (in)	Nominal Weight (lbs/ft)	Grade	End Finish	True Vert Depth (ft)	Measured Depth (ft)	Drift Diameter (in)	Internal Capacity (ft³)
1	16000	5.5	20.00	L-80	Buttress	16000	16000	4.653	1992.2
Run Seq	Collapse Load (psi)	Collapse Strength (psi)	Collapse Design Factor	Burst Load (psi)	Burst Strength (psi)	Burst Design Factor	Tension Load (Kips)	Tension Strength (Kips)	Tension Design Factor
1	6707	8830	1.316	8644	8990	1.04	270	466	1.73 B

Prepared by: Helen Sadik-Macdonald  
Div of Oil, Gas & Minerals

Phone: 801-538-5357  
FAX: 801-359-3940

Date: August 6, 2008  
Salt Lake City, Utah

**Remarks:**

Collapse is based on a vertical depth of 16000 ft, a mud weight of 10.4 ppg. An internal gradient of .121 psi/ft was used for collapse from TD. Collapse strength is based on the Westcott, Dunlop & Kemler method of biaxial correction for tension.

Burst strength is not adjusted for tension.

*Engineering responsibility for use of this design will be that of the purchaser.*

**Helen Sadik-Macdonald - Ron Lamb 31A-4-1 - Casing / BOPE**

---

**From:** "Cary Vice"  
**To:** "Helen Sadik-Macdonald"  
**Date:** 08/07/2008 10:04 AM  
**Subject:** Ron Lamb 31A-4-1 - Casing / BOPE  
**CC:** "Dustin Doucet"

---

Helen,  
 Petro-Hunt, L. L. C. uses the formulas listed below for casing design. I have used them extensively throughout the Gulf coast for land and offshore operations. Petro-Hunt, L. L. C.'s acceptable safety factors are 1.1 for collapse, 1.2 for burst and 1.6 for tension.

For Conductor and Surface casing, we use the following formula which assumes the hole would be voided of mud and filled with gas:

$$\text{Collapse} = \frac{\text{casing collapse rating}}{(\text{MW})(.052)(\text{TVDscp}) - (\text{Gg})(\text{TVDscp})}$$

MW = mud weight; TVDscp = tvd at conductor / surface casing point;  
 Gg = gas gradient.

---

For Intermediate and Drilling liners, we use the following formula which assumes a maximum of 50% evacuation of mud in the hole, replaced by a gas gradient:

$$\text{Collapse} = \frac{\text{casing collapse rating}}{(\text{MWicp})(.052)(\text{TVDicp}) - (\text{Gg})(\text{LG}) - (\text{MMW})(.052)(\text{LM})}$$

MWicp = mud wt at inter. csg pt; TVDicp = tvd at inter. csg pt; Gg = gas gradient;  
 LG = length of gas (tvd); LM = length of max. mud (tvd); MMW = maximum mud weight this casing will see.  
 Length of gas and length of maximum mud is based on hole being 50% voided at next casing point.

---

For conductor and surface casing, we use the following formula which assumes the weakest point to be the fracture gradient and the shoe:

$$\text{Top burst} = \frac{\text{casing burst rating}}{\text{ASP}}$$

$$\text{ASP} = (\text{FGscp})(.052) - (\text{Ggscp})(\text{TVDscp})$$

ASP = anticipated surface pressure; FGscp = frac.gradient at surf.csg point;

Ggscp = gas gradient at surf. csg point; TVDscp = tvd at surf. csg pt.

---

For intermediate casing, we use the following formula which assumes a 50% evacuation of mud in the hole:

**Top burst = casing burst rating**

---

### **ASP Drilling**

ASP DRILLING =  $FP - (MM)(.052)(LM) - (Gg)(LG)$

FP = formation pressure at next csg seat;

MM = maximum mud weight at this csg will see;

LM = length of mud based on 50% void;

As far as the BOPE for the surface hole, we plan to use a rotating head and diverter system. This would include a diverter spool and 20" annular preventer installed on top of the 20" conductor casing. I may have mistated this in the sundry drilling plan. I am assuming that with the submission of this data, you will now be able to approve our sundry. If you have any other questions, please do not hesitate to call or email.

Thanks,

**Cary J. Vice**  
**Petro-Hunt, L. L. C.**  
**Drilling / Completion Engr.**  
**214 880-7173 office**  
**985 855-2661 cell**

*7% conversion  
w/ Cary on 8/7/08  
afternoon*  
 "weakest point is 1 ft below previous <sup>surface</sup> csg shoe (frac. gradient is less than mud wt. from downhole)"  
 "Look at Ben Eaton Frac gradient chart. Won't get to 12 lbs at 4500 ft. Formation will fail first."

**Helen Sadik-Macdonald - Ron Lamb 31A-4-1**

---

**From:** Helen Sadik-Macdonald  
**To:** "Cary Vice"  
**Date:** 08/06/2008 2:52 PM  
**Subject:** Ron Lamb 31A-4-1  
**CC:** Dustin Doucet

---

Cary,  
I perform preliminary engineering evaluation on APDs for the Utah Division of Oil, Gas, & Mining.

For the above-cited well, all four proposed casing strings fail for collapse (SF 1.125).  
Surface and intermediate strings fail for burst (SF 1.0)

From past discussions with Dustin, you have been apprised DOGM uses the following safety factors:

burst 1.0  
collapse 1.125  
tension 1.80 (STC, LTC) 1.60 (BTC)  
in evacuated pipe, no annular backup.

Please provide me the assumptions you utilized for the design of the Ron Lamb 31A-4-1. Regardless of correspondence on previous wells, this information is necessary to complete the APD record on any well that does not meet our SFs.

Additionally, BOPE will be required for drilling the surface hole to 4500 feet.

Thank you and I look forward to your response.  
Respectfully,

*Helen Sadik-Macdonald, CPG, PG  
Petroleum Engineering Services  
Utah Div. of Oil, Gas & Mining  
PO Box 145801  
Salt Lake City, UT 84114-5801*

*801/538-5357 Desk  
801/359-3940 Fax*



# BOPE REVIEW

Petro Hunt Ron Lamb 31A-4-1(rev 2006-11) API 43-039-00

Well Name	Petro Hunt Ron Lamb 31A-4-1(rev 2006-11) API 43-039-0034-0000			
	String 1	String 2	String 3	String 4
Casing Size (")	20	13 3/8	9 5/8	5 1/2
Setting Depth (TVD)	1000	4500	8300	16000
Previous Shoe Setting Depth (TVD)	0	1000	4500	8300
Max Mud Weight (ppg)	9	9	10.5	10.4
BOPE Proposed (psi)	0	500	5000	5000
Casing Internal Yield (psi)	1530	3450	6870	8990
Operators Max Anticipated Pressure (psi)	8070			9.7 ppg

<b>Calculations</b>	<b>String 1</b>	<b>20 "</b>	
Max BHP [psi]	.052*Setting Depth*MW =		468
			BOPE Adequate For Drilling And Setting Casing at Depth?
MASP (Gas) [psi]	Max BHP-(0.12*Setting Depth) =	348	NO
MASP (Gas/Mud) [psi]	Max BHP-(0.22*Setting Depth) =	248	NO
			*Can Full Expected Pressure Be Held At Previous Shoe?
Pressure At Previous Shoe	HP-.22*(Setting Depth - Previous Shoe Depth) =	248	NO <i>σ-vl</i>
Required Casing/BOPE Test Pressure		500 psi	
*Max Pressure Allowed @ Previous Casing Shoe =		0 psi	*Assumes 1psi/ft frac gradient

<b>Calculations</b>	<b>String 2</b>	<b>13 3/8 "</b>	
Max BHP [psi]	.052*Setting Depth*MW =		2106
			BOPE Adequate For Drilling And Setting Casing at Depth?
MASP (Gas) [psi]	Max BHP-(0.12*Setting Depth) =	1566	NO Rotating head and diverter system will be utilized
MASP (Gas/Mud) [psi]	Max BHP-(0.22*Setting Depth) =	1116	NO
			*Can Full Expected Pressure Be Held At Previous Shoe?
Pressure At Previous Shoe	HP-.22*(Setting Depth - Previous Shoe Depth) =	1336	NO <i>no expected pressure - drilled similarly in area</i>
Required Casing/BOPE Test Pressure		2415 psi	
*Max Pressure Allowed @ Previous Casing Shoe =		1000 psi	*Assumes 1psi/ft frac gradient

<b>Calculations</b>	<b>String 3</b>	<b>9 5/8 "</b>	
Max BHP [psi]	.052*Setting Depth*MW =		4532
			BOPE Adequate For Drilling And Setting Casing at Depth?
MASP (Gas) [psi]	Max BHP-(0.12*Setting Depth) =	3536	YES ✓
MASP (Gas/Mud) [psi]	Max BHP-(0.22*Setting Depth) =	2706	YES
			*Can Full Expected Pressure Be Held At Previous Shoe?
Pressure At Previous Shoe	HP-.22*(Setting Depth - Previous Shoe Depth) =	3696	YES ✓
Required Casing/BOPE Test Pressure		4809 psi	
*Max Pressure Allowed @ Previous Casing Shoe =		3450 psi	*Assumes 1psi/ft frac gradient

<b>Calculations</b>	<b>String 4</b>	<b>5 1/2 "</b>	
Max BHP [psi]	.052*Setting Depth*MW =		8653
			BOPE Adequate For Drilling And Setting Casing at Depth?
MASP (Gas) [psi]	Max BHP-(0.12*Setting Depth) =	6733	NO
MASP (Gas/Mud) [psi]	Max BHP-(0.22*Setting Depth) =	5133	NO <i>Expected BHP 8070 psi → MASP = 4550 psi OK for this scenario.</i>
			*Can Full Expected Pressure Be Held At Previous Shoe?
Pressure At Previous Shoe	HP-.22*(Setting Depth - Previous Shoe Depth) =	6959	YES ✓
Required Casing/BOPE Test Pressure		5000 psi	
*Max Pressure Allowed @ Previous Casing Shoe =		6870 psi	*Assumes 1psi/ft frac gradient

## **SURFACE DAMAGE AGREEMENT**

This Agreement is between, **Alfred Ron Lamb and Nicole Lamb**, as joint tenants, hereinafter referred to as "Lessor", whose address is **HC13 Box 4205 Wales, Utah 84667** and **Petro-Hunt, L.L.C.**, hereinafter referred to as "Operator", whose address is **Suite 3400; 1601 Elm Street; Dallas, Texas 75201**

**The above parties agree to the basic understanding as follows:**

Prior to the commencement of any drilling operation by Operator on any land in Sanpete County, Utah on which Lessor own surface rights ("Subject Land"), Operator shall make the following payments as full and complete compensation for damage to the surface:

- \$500 per acre for each drill-site location and its associated access road

Operator's use of, and access to, the Subject Lands is at its own cost and risk. Operator agrees to bear all liabilities caused by its operation. A copy of Operator's State of Utah Blanket Bon in the amount of up to \$120,000 is attached hereto as Exhibit 'A'. Operator's proof of liability insurance will be furnished to Lessor.

(1) Operator shall obtain Lessor's consent to the location of all access roads, which consent shall not be unreasonably withheld. Access roads shall not exceed 30 feet in width. All pipelines, power lines, and telephone lines that will be permanent will be buried below plow depth and mapped unless otherwise agreed. In the event of a dry hole, the drill site and roadways will be restored as required by law to as near as original condition as possible, or to Lessor's specification. Lessor Hereby gives its consent to the approximate location of the access road for the **Ron Lamb Well** as depicted on the plat attached hereto as Exhibit "B".

(2) Unauthorized personnel, contractors, etc. will not have access to or be allowed on any drilling locations hereunder. Operator will make a reasonable effort to have company representative on the location at all times during drilling/completion operation. Firearms, liquor, and drugs shall be prohibited from all well location and access roads covered by this agreement.

(3) Operator will reimburse Lessor for loss, damage, injury or death of Lessor's livestock caused by or directly related to Operator's exploration and production of oil or gas on any lands covered by this agreement. Operator will recompense Lessor at fir market value plus associated replacement costs, if any, relative to any livestock covered by this paragraph 3.

(4) Operator will not bring permanent electric utilities onto the subject Property without first receiving written approval from Lessor, which shall not be unreasonably withheld.

(5) Unless otherwise agreed, Operator will at all times keep all fencing and gates within the vicinity of the roads and drilling site utilized by the Operator under this agreement in a condition suitable to contain livestock.

## **PROPERTY RECLAMATION AGREEMENT**

1. All topsoil will be stripped, stockpiled, and then replaced to support re-vegetation.
2. Ditches and culverts, gates, cattle guards will be returned as nearly as possible to original condition as required by law.
3. Reclamation work will be accomplished in a timely manner. Natural causes such as unusual weather conditions or ground settling or other force major events may delay reclamation.


4. All construction and maintenance costs relating to roads, drill pads, equipment and facilities hereunder shall be born by Operator.


This agreement shall be binding upon Operator and Lessor, their respective heirs, executors, administrator, successor, and assigns and upon Operator, its executors, administrators, successors, and assigns. This agreement pertains to only to all surface areas owned by Lessor which may be disturbed in exploration and/or development by Operator, its contractors, subcontractors and/or designees.

Dated this 14th day of July, 2008.

**Lessor and Surface Owner:**


Alfred Ron Lamb and Nicole Lamb, as joint tenants  
HC13 Box 4205  
Wales, Utah 84667

  
Alfred Ron Lamb

  
Nicole Lamb

**Operator:**

Petro-Hunt, L.L.C.

  
Dennis Ludington

**ACKNOWLEDGMENT**


STATE OF Utah )

COUNTY OF Sanpete )


**INDIVIDUAL**  
(For use in all states)

On this 14th day of July, 2008, before me, the undersigned Notary Public in and for said county and state, personally appeared, **Alfred Ron Lamb and Nicole Lamb**, known to me to be the person(s) whose name(s) **ARE subscribed** to the foregoing instrument, and **THEY** acknowledged that the same was executed and delivered as **THEIR** free and voluntary act for the purposes therein set forth. In witness whereof I hereunto set my hand and official seal as of the date hereinabove stated.

SEAL



  
Notary Public  
My Commission Expires: 3-22-09



July 18, 2008

Mrs. Diana Mason  
State of Utah  
Division of Oil Gas and Mining  
P.O. Box 145801  
Salt Lake City, Utah 84114-5801

RE: Request for Exception to Spacing- Petro-Hunt, L.L.C.  
**Ron Lamb 31A-4-1** – 1,569' FNL & 1,154' FEL, SE/4 NE/4  
Section 31, T15S, R3E, SLB&M, Sanpete County, Utah

Dear Mrs. Mason:

On behalf of Petro-Hunt, L.L.C.. (Petro-Hunt), Buys & Associates, Inc. respectfully submits this request for exception to spacing. A request for exception to spacing (R649-3-2) is hereby requested based on topography since the well is located within 460' of the drilling unit boundary. Petro-Hunt is the only owner and operator within 460' of the proposed well and all points along the intended wellbore path.

Please accept this letter as Petro-Hunt's, written request for confidential treatment of all information contained in and pertaining to this pending application.

Thank you very much for your timely consideration of this application. Please feel free to contact myself or Mick Homiston of Petro-Hunt at 701-863-6622 if you have any questions or need additional information.

Sincerely,

*Don Hamilton*

Don Hamilton  
Agent for Petro-Hunt

cc: Mick Homiston, Petro-Hunt  
Cary Vice, Petro-Hunt

RECEIVED

JUL 23 2008

DIV. OF OIL, GAS & MINING

CONFIDENTIAL

**DIVISION OF OIL, GAS AND MINING**

**SPUDDING INFORMATION**

Name of Company: PETRO-HUNT, LLC

Well Name: RON LAMB 31A-4-1

Api No: 43-039-30034 Lease Type: FEE

Section 31 Township 15S Range 03E County SANPETE

Drilling Contractor PETE MARTIN DRLG RIG # RATHOLE

**SPUDDED:**

Date 10/20/08

Time

How DRY

**Drilling will Commence:**

Reported by JUNIOR LAMB

Telephone # (601) 842-2638

Date 10/27//08 Signed CHD

CONFIDENTIAL

STATE OF UTAH  
DEPARTMENT OF NATURAL RESOURCES  
DIVISION OF OIL, GAS AND MINING

FORM 9

5. LEASE DESIGNATION AND SERIAL NUMBER:

Patented

6. IF INDIAN, ALLOTTEE OR TRIBE NAME:

NA

7. UNIT or CA AGREEMENT NAME:

NA

8. WELL NAME and NUMBER:

Ron Lamb 31A-4-1

9. API NUMBER:

43-039-30034

10. FIELD AND POOL, OR WILDCAT:

Wildcat

# SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.

1. TYPE OF WELL

OIL WELL ☒GAS WELL ☐

OTHER

2. NAME OF OPERATOR:

Petro-Hunt L.L.C.

3. ADDRESS OF OPERATOR:

258 119th Ave SW

Killdeer

ND

58640

PHONE NUMBER:

(701) 863-6622

4. LOCATION OF WELL

FOOTAGES AT SURFACE: 1569' FNL 1154' FEL

COUNTY: San Pete

QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN SENE 31 15S 03E S

STATE:

UTAH

## 11 CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION		
<input type="checkbox"/> NOTICE OF INTENT (Submit in Duplicate) Approximate date work will start:	<input type="checkbox"/> ACIDIZE	<input type="checkbox"/> DEEPEN	<input type="checkbox"/> REPERFORATE CURRENT FORMATION
	<input type="checkbox"/> ALTER CASING	<input type="checkbox"/> FRACTURE TREAT	<input type="checkbox"/> SIDETRACK TO REPAIR WELL
	<input type="checkbox"/> CASING REPAIR	<input type="checkbox"/> NEW CONSTRUCTION	<input type="checkbox"/> TEMPORARILY ABANDON
	<input type="checkbox"/> CHANGE TO PREVIOUS PLANS	<input type="checkbox"/> OPERATOR CHANGE	<input type="checkbox"/> TUBING REPAIR
	<input type="checkbox"/> CHANGE TUBING	<input type="checkbox"/> PLUG AND ABANDON	<input type="checkbox"/> VENT OR FLARE
<input checked="" type="checkbox"/> SUBSEQUENT REPORT (Submit Original Form Only) Date of work completion:	<input type="checkbox"/> CHANGE WELL NAME	<input type="checkbox"/> PLUG BACK	<input type="checkbox"/> WATER DISPOSAL
10/22/2008	<input type="checkbox"/> CHANGE WELL STATUS	<input type="checkbox"/> PRODUCTION (START/RESUME)	<input type="checkbox"/> WATER SHUT-OFF
	<input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS	<input type="checkbox"/> RECLAMATION OF WELL SITE	<input checked="" type="checkbox"/> OTHER: spud conductor hole
	<input type="checkbox"/> CONVERT WELL TYPE	<input type="checkbox"/> RECOMPLETE - DIFFERENT FORMATION	

2. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.

Pete Martin Drilling Inc. drilled 80' of 48" hole and ran 80' of 30" conductor pipe for Petro-Hunt at this well site on 10-20-2008. Pro-Petro Services then cemented the annulus with 675 sacks of G cement containing 2% calcium chloride. Cement came to surface and stayed there. Pete Martin Drilling also drilled the 20" mousehole and ran 14" pipe then it was cemented with 100 sacks of G cement.

NAME (PLEASE PRINT) Michael Homiston

TITLE District Engineer

SIGNATURE



DATE 10/28/2008

(This space for State use only)

RECEIVED

OCT 28 2008

DIV. OF OIL, GAS &amp; MINING

STATE OF UTAH  
DEPARTMENT OF NATURAL RESOURCES  
DIVISION OF OIL, GAS AND MINING

FORM 6

**ENTITY ACTION FORM**

Operator: Petro-Hunt L.L.C. Operator Account Number: N 2815  
Address: 258 119th Ave SW  
city Killdeer  
state ND zip 58640 Phone Number: (701) 863-6622

**Well 1**

API Number	Well Name		QQ	Sec	Twp	Rng	County
039-30034	Ron Lamb 31A-4-1		SENE	31	15S	03E	San Pete
Action Code	Current Entity Number	New Entity Number	Spud Date			Entity Assignment Effective Date	
A	99999	17170	10/20/2008			10/28/08	
Comments: <u>Drill conductor hole prior to moving in rotary rig.</u> <u>NAVA</u> <div style="float: right; font-weight: bold; font-size: 1.2em;">CONFIDENTIAL</div>							

**Well 2**

API Number	Well Name		QQ	Sec	Twp	Rng	County
Action Code	Current Entity Number	New Entity Number	Spud Date			Entity Assignment Effective Date	
Comments: 							

**Well 3**

API Number	Well Name		QQ	Sec	Twp	Rng	County
Action Code	Current Entity Number	New Entity Number	Spud Date			Entity Assignment Effective Date	
Comments: 							

**ACTION CODES:**

- A - Establish new entity for new well (single well only)
- B - Add new well to existing entity (group or unit well)
- C - Re-assign well from one existing entity to another existing entity
- D - Re-assign well from one existing entity to a new entity
- E - Other (Explain in 'comments' section)

Michael Homiston

Name (Please Print)

*Michael Homiston*

Signature

District Engineer

Title

10/28/2008

Date

RECEIVED

OCT 28 2008

DIV. OF OIL, GAS & MINING



CONFIDENTIAL

**STATE OF UTAH**  
DEPARTMENT OF NATURAL RESOURCES  
DIVISION OF OIL, GAS AND MINING

FORM 9

**SUNDRY NOTICES AND REPORTS ON WELLS**

Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.

5. LEASE DESIGNATION AND SERIAL NUMBER: <b>PATENTED</b>
6. IF INDIAN, ALLOTTEE OR TRIBE NAME: <b>N/A</b>
7. UNIT or CA AGREEMENT NAME: <b>N/A</b>
8. WELL NAME and NUMBER: <b>RON LAMB 31A-4-1</b>
9. API NUMBER: <b>4303930034</b>
10. FIELD AND POOL, OR WILDCAT: <b>WILDCAT</b>

1. TYPE OF WELL <b>OIL WELL</b> <input checked="" type="checkbox"/> <b>GAS WELL</b> <input type="checkbox"/> <b>OTHER</b> _____	
2. NAME OF OPERATOR: <b>PETRO-HUNT, L. L. C.</b>	
3. ADDRESS OF OPERATOR: <b>258 119TH AVENUE SW</b> CITY <b>KILLDEER</b> STATE <b>ND</b> ZIP <b>58640</b>	
4. LOCATION OF WELL FOOTAGES AT SURFACE: <b>1569' FNL &amp; 1154' FEL</b>	

PHONE NUMBER:  
**(701) 863-6622**COUNTY: **SANPETE**QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: **SENE 31 15S 3E S**STATE: **UTAH****11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA**

TYPE OF SUBMISSION	TYPE OF ACTION		
<input checked="" type="checkbox"/> <b>NOTICE OF INTENT</b> (Submit in Duplicate) Approximate date work will start: <b>1/18/2009</b>	<input type="checkbox"/> ACIDIZE	<input type="checkbox"/> DEEPEN	<input type="checkbox"/> REPERFORATE CURRENT FORMATION
	<input checked="" type="checkbox"/> ALTER CASING	<input type="checkbox"/> FRACTURE TREAT	<input type="checkbox"/> SIDETRACK TO REPAIR WELL
	<input type="checkbox"/> CASING REPAIR	<input type="checkbox"/> NEW CONSTRUCTION	<input type="checkbox"/> TEMPORARILY ABANDON
	<input checked="" type="checkbox"/> CHANGE TO PREVIOUS PLANS	<input type="checkbox"/> OPERATOR CHANGE	<input type="checkbox"/> TUBING REPAIR
	<input type="checkbox"/> CHANGE TUBING	<input type="checkbox"/> PLUG AND ABANDON	<input type="checkbox"/> VENT OR FLARE
<input type="checkbox"/> <b>SUBSEQUENT REPORT</b> (Submit Original Form Only) Date of work completion:	<input type="checkbox"/> CHANGE WELL NAME	<input type="checkbox"/> PLUG BACK	<input type="checkbox"/> WATER DISPOSAL
	<input type="checkbox"/> CHANGE WELL STATUS	<input type="checkbox"/> PRODUCTION (START/RESUME)	<input type="checkbox"/> WATER SHUT-OFF
	<input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS	<input type="checkbox"/> RECLAMATION OF WELL SITE	<input type="checkbox"/> OTHER: _____
	<input type="checkbox"/> CONVERT WELL TYPE	<input type="checkbox"/> RECOMPLETE - DIFFERENT FORMATION	

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.

We are currently drilling the Ron Lamb 31A-4-1 wildcat well at 9,761' RKB with a mud weight of 10.6 ppg and a 13 3/8" shoe test at 4,490' RKB of 11.5 ppg. We are allowing hole conditions to dictate the 9 5/8" intermediate casing point. We are looking for an "oolite" marker and the Navajo formation. With your approval, our current plans are to drill into the Navajo formation, which should occur prior to 11,500' RKB, and log this well. At that time, the decision will be made whether to run 9 5/8" intermediate casing, plugback for sidetrack operations or plug & abandon the well.

I have attached a revised casing design.

The revised two stage cement volumes for 9 5/8" intermediate at 11,500' with the diverter tool at 4,500' are as follows:


Stage	Type	Sacks	Interval	Density	Yield	Hole Volume	Cement Volume
1	Lead	1164	3,500' - 10,500'	11.5 ppg	2.71 cf/sx	2214 cf	3155 cf
1	Tail	412	10,500' - 11,500'	14.3 ppg	5.42 cf/sx	313 cf	469 cf
2	Lead	160	3,000' - 4,300'	11.5 ppg	2.72 cf/sx	432 cf	432 cf
2	Tail	95	4,300' - 4,500'	15.8 ppg	1.25 cf/sx	93 cf	93 cf

Cement volumes may vary dependent upon actual casing setting depth, hole caliper results and diverter tool depth.

NAME (PLEASE PRINT) **Cary J. Vice**TITLE **Sr. Drilling Engineer**SIGNATURE DATE **1/18/2009**

(This space for State use only)

**APPROVED BY THE STATE  
OF UTAH DIVISION OF  
OIL, GAS, AND MINING**

DATE **1/20/09**  
BY: 

\* Verbal given 1/18/09

COPY SENT TO OPERATOR

Date: **1.21.2009**Initials: **KS****RECEIVED****JAN 20 2009**

DIV. OF OIL, GAS &amp; MINING

# CASING DESIGN CHART

WELL:  
FIELD:

RON LAMB 31A-4-1  
WILDCAT - SANPETE COUNTY, UT

01/18/09 revised

cjv




SIZE	WT/FT	GRADE	CONN	LENGTH OF SECTION	SETTING DEPTH TVD	SETTING DEPTH MD	EST. MUD WT.	PRESS GRAD PSI/FT	EST. BHP MW-7ppg	EST. FRAC. GRAD. PPG	EST. GAS GRAD.	CALC HYDRO PRESS	WT IN AIR		COLLAPSE RATING		TENS. STRENGTH		BURST RATING
													SECTION 1000 LBS	CUMM 1000 LBS	100% PSI	ADJUSTED TENSILE	JOINT 1000 LBS	BODY 1000 LBS	
30	.375" wall	B	P.E.	80	80	80													
20"	94.00	J/K55	BTC	1026	1026	1026	9	0.468	0.432	12.1	0.10	480	96	96	520	520	1479	1480	2110
13 3/8"	68.00	HCL80	BTC	4490	4490	4490	10.2	0.530	0.494	14.4	0.10	2381	305	305	2910	2910	1692	1556	5020
9 5/8"	47.00	L80	LTC	11500	11500	11500	10.6	0.551	0.515	16.0	0.15	6339	541	541	4760	4760	893	1086	6870
5 1/2" on top	20.00	L80	BTC	8100	8100	8100	10.4	0.541	0.504	N/A	0.10	4380	162	284	8830	8830	503	466	8990
5 1/2" on btm	20.00	L80	LTC	6100	14200	14200	10.4	0.541	0.504	N/A	0.15	7679	122	122	8830	8830	416	466	9190
2 7/8" Tbg	6.50	L80	EUE	14000	14000	14000	10.4	0.541	0.504	N/A	0.15	7571	91	91	11170	11170	145	145	10570

SIZE	SAFETY FACTORS									
	DRILLING			PROD.						
	COL	TENS	BURST	BURST	ASP	ASP	DRIFT	PIN	CSG	CPLG
20"	1.100	1.600	1.200	1.200	DRLG	PROD	BODY	I. D.	I. D.	O. D.
13 3/8"	1.377	15.335	3.89	N/A	543	N/A	18.936	19.124	19.124	21
9 5/8"	1.506	5.096	1.7	N/A	2913	N/A	12.259	12.415	12.415	14.375
5 1/2"	1.645	1.652	2.48	N/A	2775	5575	SP DFT 8.625	8.681	8.681	10.625
5 1/2"	2.473	1.641	N/A	1.613	N/A	5575	4.767	4.892	4.892	6.050
5 1/2"	1.591	3.410	N/A	1.648	N/A	5575	4.767	4.892	4.892	6.050
2 7/8" Tbg	2.042	1.593	N/A	1.896	N/A	5575	2.347	2.441	2.441	3.668

BHP = MUD WT @ TD - 0.7 PPG X .052 X TVD =

7162

Casing Schematic



Well name:	<b>43039300340000 Ron Lamb Trust 31A-4-1rev.1-09</b>		
Operator:	<b>Petro-Hunt L.L.C.</b>		
String type:	Intermediate	Project ID:	43-039-30034 (rev 2006-11)
Location:	Sanpete County		

**Design parameters:**
**Collapse**

Mud weight: 10.600 ppg  
Internal fluid density: 5.300 ppg

**Minimum design factors:**
**Collapse:**

Design factor 1.125

**Burst:**

Design factor 1.00

**Environment:**

H2S considered? No  
Surface temperature: 75 °F  
Bottom hole temperature: 236 °F  
Temperature gradient: 1.40 °F/100ft  
Minimum section length: 1,500 ft

Cement top: 3,107 ft

**Burst**

Max anticipated surface pressure: 4,340 psi  
Internal gradient: 0.220 psi/ft  
Calculated BHP: 6,870 psi  
  
Annular backup: 2.33 ppg

**Tension:**

8 Round STC: 1.80 (J)  
8 Round LTC: 1.80 (J)  
Buttress: 1.60 (J)  
Premium: 1.50 (J)  
Body yield: 1.50 (B)

**Non-directional string.**
**Re subsequent strings:**

Next setting depth: 16,000 ft  
Next mud weight: 10.600 ppg  
Next setting BHP: 8,810 psi  
Fracture mud wt: 11.500 ppg  
Fracture depth: 11,500 ft  
Injection pressure: 6,870 psi

Tension is based on buoyed weight.  
Neutral point: 9,671 ft

Run Seq	Segment Length (ft)	Size (in)	Nominal Weight (lbs/ft)	Grade	End Finish	True Vert Depth (ft)	Measured Depth (ft)	Drift Diameter (in)	Internal Capacity (ft³)
1	11500	9.625	47.00	L-80	LT&C	11500	11500	8.625	4726.8
Run Seq	Collapse Load (psi)	Collapse Strength (psi)	Collapse Design Factor	Burst Load (psi)	Burst Strength (psi)	Burst Design Factor	Tension Load (Kips)	Tension Strength (Kips)	Tension Design Factor
1	3166	4760	1.503	5478	6870	1.25	455	893	1.96 J

Prepared by: Helen Sadik-Macdonald  
Div of Oil, Gas & Mining

Phone: 801-538-5357  
FAX: 801-359-3940

Date: January 20, 2009  
Salt Lake City, Utah

**Remarks:**

Collapse is based on a vertical depth of 11500 ft, a mud weight of 10.6 ppg. An internal gradient of .275 psi/ft was used for collapse from TD. Collapse strength is based on the Westcott, Dunlop & Kemler method of biaxial correction for tension.

Burst strength is not adjusted for tension.

*Engineering responsibility for use of this design will be that of the purchaser.*

**STATE OF UTAH**  
DEPARTMENT OF NATURAL RESOURCES  
DIVISION OF OIL, GAS AND MINING

**SUNDRY NOTICES AND REPORTS ON WELLS**

Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.

1. TYPE OF WELL OIL WELL <input checked="" type="checkbox"/> GAS WELL <input type="checkbox"/> OTHER _____		5. LEASE DESIGNATION AND SERIAL NUMBER: <b>PATENTED</b>
2. NAME OF OPERATOR: <b>PETRO-HUNT, L. L. C.</b>		6. IF INDIAN, ALLOTTEE OR TRIBE NAME: N/A
3. ADDRESS OF OPERATOR: 258 119TH AVENUE SW CITY KILLDEER STATE ND ZIP 58640		7. UNIT or CA AGREEMENT NAME: N/A
PHONE NUMBER: (701) 863-6622		8. WELL NAME and NUMBER: <b>RON LAMB 31A-4-1</b>
4. LOCATION OF WELL FOOTAGES AT SURFACE: 1569' FNL & 1154' FEL		9. API NUMBER: 4303930034
QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: SENE 31 15S 3E S		10. FIELD AND POOL, OR WILDCAT: WILDCAT

COUNTY: SANPETE

STATE: UTAH

**11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA**

TYPE OF SUBMISSION	TYPE OF ACTION		
<input checked="" type="checkbox"/> NOTICE OF INTENT (Submit in Duplicate) Approximate date work will start: <u>2/5/2009</u>	<input type="checkbox"/> ACIDIZE	<input type="checkbox"/> DEEPEN	<input type="checkbox"/> REPERFORATE CURRENT FORMATION
<input type="checkbox"/> SUBSEQUENT REPORT (Submit Original Form Only) Date of work completion:	<input checked="" type="checkbox"/> ALTER CASING	<input type="checkbox"/> FRACTURE TREAT	<input type="checkbox"/> SIDETRACK TO REPAIR WELL
	<input type="checkbox"/> CASING REPAIR	<input type="checkbox"/> NEW CONSTRUCTION	<input type="checkbox"/> TEMPORARILY ABANDON
	<input checked="" type="checkbox"/> CHANGE TO PREVIOUS PLANS	<input type="checkbox"/> OPERATOR CHANGE	<input type="checkbox"/> TUBING REPAIR
	<input type="checkbox"/> CHANGE TUBING	<input type="checkbox"/> PLUG AND ABANDON	<input type="checkbox"/> VENT OR FLARE
	<input type="checkbox"/> CHANGE WELL NAME	<input type="checkbox"/> PLUG BACK	<input type="checkbox"/> WATER DISPOSAL
	<input type="checkbox"/> CHANGE WELL STATUS	<input type="checkbox"/> PRODUCTION (START/RESUME)	<input type="checkbox"/> WATER SHUT-OFF
	<input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS	<input type="checkbox"/> RECLAMATION OF WELL SITE	<input type="checkbox"/> OTHER: _____
	<input type="checkbox"/> CONVERT WELL TYPE	<input type="checkbox"/> RECOMPLETE - DIFFERENT FORMATION	

**12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS.** Clearly show all pertinent details including dates, depths, volumes, etc.

We are currently drilling the Ron Lamb 31A-4-1 wildcat well at 11,554' RKB with a mud weight of 10.6 ppg and a 13 3/8" shoe test at 4,490' RKB of 11.5 ppg. We are allowing the hole conditions to dictate the 9 5/8" intermediate casing point. We are looking for an "oolite" marker and the Navajo formation. With your approval, our current plans are to drill into the Navajo formation, which should occur prior to 15,000' RKB, and log this well. At that time, the decision will be made whether to run 9 5/8" intermediate casing, plugback for sidetrack operations or plug & abandon the well.

I have attached a revised casing design.

The revised two stage cement volumes for 9 5/8" intermediate at 15,000' with the diverter tool at 9,200' are as follows:

Stage	Type	Sacks	Interval	Density	Yield	Hole Volume	Cement Volume
1	Lead	520	11,000' - 14,000'	11.5 ppg	2.71 cf/sx	939 cf	1409 cf
1	Tail	412	14,000' - 15,000'	14.3 ppg	1.23 cf/sx	313 cf	506 cf
2	Lead	740	3,000' - 9,000'	11.5 ppg	2.72 cf/sx	2012 cf	2013 cf
2	Tail	95	9,000' - 9,200'	15.8 ppg	1.25 cf/sx	87 cf	118 cf

NAME (PLEASE PRINT) Cary J. Vice TITLE Sr. Drilling Engineer  
SIGNATURE Cary J. Vice DATE 2/5/2009

(This space for State use only)

**COPY SENT TO OPERATOR**

**APPROVED BY THE STATE  
OF UTAH DIVISION OF  
OIL, GAS, AND MINING**

Date: 2.9.2009  
Initials: KS

DATE: 2/5/09  
BY: [Signature]

(See Instructions on Reverse Side)

**RECEIVED**  
**FEB 05 2009**  
**DIV. OF OIL, GAS & MINING**

# CASING DESIGN CHART

WELL:  
FIELD:

RON LAMB 31A-4-1  
WILDCAT - SANPETE COUNTY, UT



02/05/09 revised

cjv

SIZE	WT/FT	GRADE	CONN	LENGTH OF SECTION	SETTING DEPTH TVD	SETTING DEPTH MD	EST. MUD WT.	PRESS GRAD PSI/FT	EST. BHP MW-7ppg	EST. FRAC. GRAD. PPG	EST. GAS GRAD.	CALC HYDRO PRESS	WT IN AIR		COLLAPSE RATING		TENS. STRENGTH		BURST RATING
													SECTION 1000 LBS	CUMM 1000 LBS	100% PSI	ADJUSTED TENSILE	JOINT 1000 LBS	BODY 1000 LBS	
30	.375" wall	B	P.E.	80	80	80													
20"	94.00	J/K55	BTC	1026	1026	1026	9	0.468	0.432	12.1	0.10	480	96	96	520	520	1479	1480	2110
13 3/8"	68.00	HCL80	BTC	4490	4490	4490	10.2	0.530	0.494	14.4	0.10	2381	305	305	2910	2910	1692	1556	5020
9 5/8"	47.00	HCP110	LTC	5500	5500	5500	10.6	0.551	0.515	16.0	0.10	3032	259	705	7100	7100	1213	1493	9440
9 5/8"	47.00	L80	LTC	9500	15000	15000	10.6	0.551	0.515	16.0	0.15	8268	447	447	4760	4760	893	1086	6870
5 1/2" on top	20.00	L80	BTC	8000	8000	8000	10.4	0.541	0.504	N/A	0.10	4326	160	320	8830	8830	503	466	8990
5 1/2" on btm	20.00	L80	LTC	8000	16000	16000	10.4	0.541	0.504	N/A	0.15	8653	160	160	8830	8830	416	466	9190
2 7/8" Tbg	6.50	L80	EUE	15800	15800	15800	10.4	0.541	0.504	N/A	0.15	8545	103	103	11170	11170	145	145	10570

SIZE	SAFETY FACTORS									
	DRILLING			PROD.						
	COL	TENS	BURST	BURST	ASP	ASP	DRIFT	PIN	CSG	CPLG
20"	1.100	1.600	1.200	1.200	DRLG	PROD	BODY	I. D.	I. D.	O. D.
13 3/8"	1.377	15.335	3.89	N/A	543	N/A	18.936	19.124	19.124	21
9 5/8"	1.506	5.096	1.7	N/A	2913	N/A	12.259	12.415	12.415	14.375
9 5/8"	2.750	1.721	5.35	N/A	1763	6207	SP DFT 8.625	8.681	8.681	10.625
9 5/8"	1.450	2.000	2.20	N/A	3126	6032	SP DFT 8.625	8.681	8.681	10.625
5 1/2"	2.504	1.456	N/A	1.490	N/A	6032	4.767	4.892	4.892	6.050
5 1/2"	1.412	2.600	N/A	1.524	N/A	6032	4.767	4.892	4.892	6.050
2 7/8" Tbg	1.809	1.412	N/A	1.752	N/A	6032	2.347	2.441	2.441	3.668
BHP = MUD WT @ TD - 0.7 PPG X .052 X TVD =							8070			

Well name:	<b>43039300340000 Ron Lamb Trust 31A-4-1rev.2-09</b>	
Operator:	<b>Petro-Hunt L.L.C.</b>	Project ID:
String type:	Intermediate	43-039-30034 (rev 2006-11)
Location:	Sanpete County	

**Design parameters:**
**Collapse**

Mud weight: 10.600 ppg  
Internal fluid density: 5.300 ppg

**Minimum design factors:**
**Collapse:**

Design factor 1.125

**Burst:**

Design factor 1.00

**Environment:**

H2S considered? No  
Surface temperature: 75 °F  
Bottom hole temperature: 285 °F  
Temperature gradient: 1.40 °F/100ft  
Minimum section length: 1,500 ft

Cement top: 4,463 ft

**Burst**

Max anticipated surface pressure: 5,290 psi  
Internal gradient: 0.220 psi/ft  
Calculated BHP: 8,590 psi  
  
Annular backup: 2.33 ppg

**Tension:**

8 Round STC: 1.80 (J)  
8 Round LTC: 1.80 (J)  
Buttress: 1.60 (J)  
Premium: 1.50 (J)  
Body yield: 1.50 (B)

Tension is based on buoyed weight.  
Neutral point: 12,615 ft

**Non-directional string.**
**Re subsequent strings:**

Next setting depth: 16,000 ft  
Next mud weight: 10.600 ppg  
Next setting BHP: 8,810 psi  
Fracture mud wt: 11.500 ppg  
Fracture depth: 15,000 ft  
Injection pressure: 8,961 psi

Run Seq	Segment Length (ft)	Size (in)	Nominal Weight (lbs/ft)	Grade	End Finish	True Vert Depth (ft)	Measured Depth (ft)	Drift Diameter (in)	Internal Capacity (ft³)
2	5500	9.625	47.00	HCP-110	LT&C	5500	5500	8.625	2260.6
1	9500	9.625	47.00	L-80	LT&C	15000	15000	8.625	3904.7

Run Seq	Collapse Load (psi)	Collapse Strength (psi)	Collapse Design Factor	Burst Load (psi)	Burst Strength (psi)	Burst Design Factor	Tension Load (Kips)	Tension Strength (Kips)	Tension Design Factor
2	1514	6520	4.306	5835	9440	1.62	593	1213	2.05 J
1	4130	4760	1.153	6775	6870	1.01	334	893	2.67 J

Prepared by: Helen Sadik-Macdonald  
Div of Oil, Gas & Mining

Phone: 801-538-5357  
FAX: 801-359-3940

Date: February 5, 2009  
Salt Lake City, Utah


**Remarks:**

Collapse is based on a vertical depth of 15000 ft, a mud weight of 10.6 ppg. An internal gradient of .275 psi/ft was used for collapse from TD. Collapse strength is based on the Westcott, Dunlop & Kemler method of biaxial correction for tension.

Burst strength is not adjusted for tension.

Engineering responsibility for use of this design will be that of the purchaser.

Casing Schematic





STATE OF UTAH  
DEPARTMENT OF NATURAL RESOURCES  
DIVISION OF OIL, GAS AND MINING

CONFIDENTIAL

FORM 9

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.

5. LEASE DESIGNATION AND SERIAL NUMBER:

PATENTED

6. IF INDIAN, ALLOTTEE OR TRIBE NAME:

N/A

7. UNIT or CA AGREEMENT NAME:

N/A

8. WELL NAME and NUMBER:

RON LAMB 31A-4-1

9. API NUMBER:

4303930034

10. FIELD AND POOL, OR WILDCAT:

WILDCAT

1. TYPE OF WELL OIL WELL ☐ GAS WELL ☐ OTHER DRY HOLE

2. NAME OF OPERATOR:  
PETRO-HUNT, L. L. C.

3. ADDRESS OF OPERATOR:  
258 119TH AVENUE SW CITY KILLDEER STATE ND ZIP 58640

PHONE NUMBER:  
(701) 863-6622

4. LOCATION OF WELL

FOOTAGES AT SURFACE: 1569' FNL & 1154' FEL

COUNTY: SANPETE

QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: SENE 31 15S 3E S

STATE: UTAH

11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION			
<input checked="" type="checkbox"/> NOTICE OF INTENT (Submit in Duplicate) Approximate date work will start: 2/21/2009	<input type="checkbox"/> ACIDIZE	<input type="checkbox"/> DEEPEN	<input type="checkbox"/> REPERFORATE CURRENT FORMATION	
	<input type="checkbox"/> ALTER CASING	<input type="checkbox"/> FRACTURE TREAT	<input type="checkbox"/> SIDETRACK TO REPAIR WELL	
	<input type="checkbox"/> CASING REPAIR	<input type="checkbox"/> NEW CONSTRUCTION	<input checked="" type="checkbox"/> TEMPORARILY ABANDON	
	<input type="checkbox"/> CHANGE TO PREVIOUS PLANS	<input type="checkbox"/> OPERATOR CHANGE	<input type="checkbox"/> TUBING REPAIR	
	<input type="checkbox"/> CHANGE TUBING	<input type="checkbox"/> PLUG AND ABANDON	<input type="checkbox"/> VENT OR FLARE	
<input type="checkbox"/> SUBSEQUENT REPORT (Submit Original Form Only) Date of work completion:	<input type="checkbox"/> CHANGE WELL NAME	<input type="checkbox"/> PLUG BACK	<input type="checkbox"/> WATER DISPOSAL	
	<input type="checkbox"/> CHANGE WELL STATUS	<input type="checkbox"/> PRODUCTION (START/RESUME)	<input type="checkbox"/> WATER SHUT-OFF	
	<input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS	<input type="checkbox"/> RECLAMATION OF WELL SITE	<input type="checkbox"/> OTHER: _____	
	<input type="checkbox"/> CONVERT WELL TYPE	<input type="checkbox"/> RECOMPLETE - DIFFERENT FORMATION		

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.

Per verbal approval from Mr. Dustin Doucet - Utah - Division of Oil, Gas and Mining 2-21-09, Petro-Hunt, L. L. C. will proceed with plugging and temporary abandonment of the Ron Lamb 31A-4-1 well in Sanpete Co., UT. There were no hydrocarbons in the open hole. A cement retainer will be set at +/- 4,290', 300' of cement will be squeezed below and 100' of cement will be spotted on top of the retainer. This cement plug will be tagged. A cement plug will be set from 826' - 1,226' and pressure tested with 500 psi. A surface cement plug will be set from 10' - 210' and this plug will be visually inspected. A dry hole tree will be installed on top of the wellhead equipment. (see attached Proposed T&A Schematic).

COPY SENT TO OPERATOR

Date: 3.5.2009

Initials: KS

RECEIVED

FEB 23 2009

DIV. OF OIL, GAS & MINING

NAME (PLEASE PRINT) Cary J. Vice

TITLE Sr. Drilling Engineer

SIGNATURE

*Cary J. Vice*

DATE 2/23/2009

(This space for State use only)

APPROVED BY THE STATE  
OF UTAH DIVISION OF  
OIL, GAS, AND MINING

DATE: 2/23/09

BY: *[Signature]*

(See Instructions on Reverse Side)

\* A well Completion Report should be submitted  
\* ultimate P&A would require DHM

RECEIVED  
FEB 23 2009  
DIV. OF OIL, GAS & MINING


# PROPOSED T&A SCHEMATIC

# PETRO HUNT L. L. C.

## DRILLING PROGRAM

cjv

COMPANY NAME	PETRO HUNT L. L. C.	DATE	2/21/2009
WELL NAME	RON LAMB 31A-4-1	TD:	12670 RKB
FIELD	WILDCAT	STATE:	UTAH
PROSPECT:	WALES	COUNTY:	SANPETE
LOCATION	SECTION 31, T 15S, R 3E	WATER DEPTH:	N/A
OBJECTIVE ZONE(S)	JURASSIC LOWER TWIN CREEK AND JURASSIC NAVAJO		



STATE OF UTAH  
DEPARTMENT OF NATURAL RESOURCES  
DIVISION OF OIL, GAS AND MINING

**CONFIDENTIAL** **COPY**

FORM 9

**SUNDRY NOTICES AND REPORTS ON WELLS**

Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.

1. TYPE OF WELL OIL WELL <input type="checkbox"/> GAS WELL <input type="checkbox"/> OTHER <u>DRY HOLE</u>		5. LEASE DESIGNATION AND SERIAL NUMBER <b>PATENTED</b>
2. NAME OF OPERATOR <b>PETRO-HUNT LLC</b>		6. IF INDIAN, ALLOTTEE OR TRIBE NAME <b>NA</b>
3. ADDRESS OF OPERATOR 258 119TH AVE SW CITY <b>KILDEER</b> STATE <b>ND</b> ZIP <b>58640</b>		7. UNIT or CO-AGREEMENT NAME <b>NA</b>
PHONE NUMBER <b>(701) 863-6622</b>		8. WELL NAME and NUMBER <b>RON LAMB 31A-4-1</b>
4. LOCATION OF WELL FOOTAGES AT SURFACE: <b>1569 FNL 1154 FEL</b>		9. API NUMBER <b>4303930034</b>
QTR/CTR, SECTION, TOWNSHIP, RANGE, MERIDIAN <b>SENE 31 15S 3E S</b>		10. FIELD AND POOL, OR WILDCAT <b>WILDCAT</b>
STATE <b>UTAH</b>		

11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA			
TYPE OF SUBMISSION		TYPE OF ACTION	
<input type="checkbox"/> NOTICE OF INTENT (Submit in Duplicate) Approximate date work will start:  	<input type="checkbox"/> ACIDIZE <input type="checkbox"/> ALTER CASING <input type="checkbox"/> CASING REPAIR <input type="checkbox"/> CHANGE TO PREVIOUS PLANS <input type="checkbox"/> CHANGE TUBING <input type="checkbox"/> CHANGE WELL NAME <input type="checkbox"/> CHANGE WELL STATUS <input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS <input type="checkbox"/> CONVERT WELL TYPE	<input type="checkbox"/> DEEPEN <input type="checkbox"/> FRACTURE TREAT <input type="checkbox"/> NEW CONSTRUCTION <input type="checkbox"/> OPERATOR CHANGE <input type="checkbox"/> PLUG AND ABANDON <input type="checkbox"/> PLUG BACK <input type="checkbox"/> PRODUCTION (START/RESUME) <input type="checkbox"/> RECLAMATION OF WELL SITE <input type="checkbox"/> RECOMPLETE - DIFFERENT FORMATION	<input type="checkbox"/> REPERFORATE CURRENT FORMATION <input type="checkbox"/> SIDETRACK TO REPAIR WELL <input checked="" type="checkbox"/> TEMPORARILY ABANDON <input type="checkbox"/> TUBING REPAIR <input type="checkbox"/> VENT OR FLARE <input type="checkbox"/> WATER DISPOSAL <input type="checkbox"/> WATER SHUT-OFF <input type="checkbox"/> OTHER: _____
<input checked="" type="checkbox"/> SUBSEQUENT REPORT (Submit Original Form Only) Date of work completion: <b>2/24/2009</b>			

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.

PETRO-HUNT LLC TEMPORARILY ABANDONED THE WELL BY SETTING THE FOLLOWING CEMENT PLUGS;

1. CEMENT RETAINER SET AT 4290'. SQUEEZED 136 SX CEMENT BELOW RETAINER AND SPOTTED 68 SX CEMENT ON TOP OF RETAINER. PLUG LENGTH (4203'-4492'). TAG CEMENT AT 4203'.

2. SPOT BALANCED 292 SX CEMENT PLUG FROM 808'-1208'. PRESSURE TEST TO 500#, HELD OK.

3. SPOT BALANCED 147 SX CEMENT PLUG FROM 27'-221'.

ABANDONMENT WITNESSED BY MARK JONES - UTAH OIL & GAS DIVISION.

NAME (PLEASE PRINT) <b>MICHAEL HOMISTON</b>	TITLE <b>DISTRICT ENGINEER</b>
SIGNATURE <i>M Homiston</i>	DATE <b>3/27/2009</b>

(This space for State use only)

(5/2/00)

(See Instructions on Reverse Side)

**RECEIVED**

**APR 06 2009**

**DIV. OF OIL, GAS & MINING**

RECEIVED

MAY 05 2009

DIV. OF OIL, GAS & MINING

## Petro-Hunt, LLC

Sanpete County, UT

Sec. 31-T15S-R3E

Ron Lamb 31A-4-1

Plan #1

43-039-2002A

CONFIDENTIAL

Design: Gyrodata Gyro and Sperry MWD Survey

# Sperry Drilling Services Standard Report

06 April, 2009

Well Coordinates: 6,976,041.82 N, 1,605,521.44 E (39° 28' 15.34" N, 111° 37' 25.01" W)

Ground Level: 5,543.40 ft

Local Coordinate Origin:

Centered on Well Ron Lamb 31A-4-1

Viewing Datum:

RKB 28' @ 5571.40ft (Original Well Elev)

TVDs to System:

N

North Reference:

True

Unit System:

API - US Survey Feet

Geodetic Scale Factor Applied

Version: 2003.14 Build: 57

HALLIBURTON

**Design Report for Ron Lamb 31A-4-1 - Plan #1 - Gyrodata Gyro and Sperry MWD Survey**

Measured Depth (ft)	Inclination (°)	Azimuth (°)	Vertical Depth (ft)	+N/-S (ft)	+E/-W (ft)	Vertical Section (ft)	Dogleg Rate (°/100ft)
0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
200.00	0.38	342.58	200.00	0.63	-0.20	0.39	0.19
<b>Surveys from 200.00ft to 2940.00ft are Gyrodata Gyro Surveys</b>							
400.00	0.67	3.33	399.99	2.43	-0.33	1.76	0.17
600.00	0.44	22.04	599.98	4.31	0.03	3.49	0.14
800.00	0.56	18.12	799.97	5.95	0.62	5.16	0.06
1,000.00	0.61	12.97	999.96	7.92	1.16	7.07	0.04
1,100.00	0.52	350.94	1,099.96	8.89	1.21	7.87	0.23
1,200.00	0.73	26.61	1,199.95	9.90	1.42	8.82	0.43
1,300.00	0.76	26.00	1,299.94	11.07	2.00	10.10	0.03
1,400.00	0.60	22.14	1,399.94	12.15	2.49	11.26	0.17
1,500.00	0.96	24.34	1,499.93	13.40	3.03	12.59	0.36
1,600.00	0.93	31.25	1,599.91	14.86	3.80	14.21	0.12
1,700.00	1.46	27.60	1,699.89	16.68	4.81	16.28	0.54
1,800.00	1.69	28.11	1,799.85	19.11	6.09	19.00	0.23
1,900.00	1.93	22.22	1,899.80	21.97	7.42	22.09	0.30
2,000.00	1.93	19.37	1,999.75	25.12	8.62	25.34	0.10
2,100.00	2.22	14.40	2,099.68	28.58	9.66	28.74	0.34
2,200.00	2.34	10.71	2,199.60	32.46	10.52	32.38	0.19
2,300.00	2.31	2.00	2,299.52	36.48	10.97	35.88	0.35
2,400.00	2.29	356.71	2,399.44	40.49	10.93	39.08	0.21
2,500.00	2.08	350.21	2,499.37	44.27	10.50	41.88	0.32
2,600.00	1.90	338.71	2,599.31	47.61	9.59	44.02	0.44
2,700.00	2.06	331.68	2,699.25	50.73	8.14	45.68	0.29
2,800.00	2.57	326.16	2,799.17	54.18	6.04	47.21	0.56
2,900.00	2.95	322.22	2,899.05	58.07	3.21	48.67	0.42
2,940.00	3.16	321.65	2,938.99	59.75	1.90	49.24	0.53
<b>Tie-On to Gyrodata Gyro Survey</b>							
3,025.00	3.54	334.54	3,023.85	63.96	-0.68	51.10	0.99
<b>First Sperry MWD Survey</b>							
3,117.00	4.07	321.71	3,115.65	69.09	-3.93	53.30	1.09
3,210.00	4.73	324.53	3,208.37	74.80	-8.20	55.37	0.75
3,302.00	5.27	329.01	3,300.02	81.51	-12.57	58.18	0.72
3,334.00	5.33	327.14	3,331.89	84.02	-14.14	59.27	0.57
3,364.00	4.71	323.90	3,361.77	86.18	-15.62	60.14	2.27
3,394.00	4.85	329.52	3,391.67	88.27	-16.99	61.01	1.63
3,426.00	3.92	327.45	3,423.57	90.36	-18.26	61.93	2.95
3,457.00	3.29	334.02	3,454.51	92.05	-19.22	62.73	2.43
3,488.00	2.40	332.41	3,485.47	93.43	-19.91	63.43	2.88
3,520.00	2.15	330.14	3,517.45	94.54	-20.52	63.96	0.83
3,552.00	1.84	335.50	3,549.43	95.53	-21.03	64.45	1.13
3,583.00	0.88	327.27	3,580.42	96.18	-21.37	64.78	3.15
3,614.00	1.12	329.66	3,611.41	96.65	-21.65	64.99	0.79
3,644.00	1.58	321.74	3,641.41	97.22	-22.06	65.21	1.65
3,676.00	2.52	314.62	3,673.39	98.06	-22.83	65.43	3.04
3,706.00	3.13	318.50	3,703.35	99.14	-23.84	65.70	2.13
3,736.00	3.91	324.85	3,733.29	100.59	-24.97	66.19	2.90
3,768.00	4.35	327.58	3,765.21	102.51	-26.25	66.98	1.51
3,798.00	5.76	342.19	3,795.09	104.90	-27.32	68.27	6.33

## Design Report for Ron Lamb 31A-4-1 - Plan #1 - Gyrodata Gyro and Sperry MWD Survey

Measured Depth (ft)	Inclination (°)	Azimuth (°)	Vertical Depth (ft)	+N/-S (ft)	+E/-W (ft)	Vertical Section (ft)	Dogleg Rate (°/100ft)
3,827.00	7.13	347.80	3,823.91	108.05	-28.15	70.31	5.19
3,857.00	8.40	352.06	3,853.63	112.04	-28.84	73.12	4.64
3,888.00	8.53	355.20	3,884.30	116.57	-29.35	76.47	1.55
3,918.00	8.28	355.87	3,913.97	120.94	-29.69	79.78	0.89
3,950.00	7.81	356.59	3,945.66	125.41	-29.99	83.21	1.50
3,980.00	7.56	357.45	3,975.39	129.42	-30.20	86.31	0.92
4,011.00	7.26	358.57	4,006.13	133.41	-30.34	89.44	1.07
4,041.00	7.11	0.93	4,035.89	137.16	-30.35	92.45	1.10
4,072.00	6.38	0.31	4,066.68	140.80	-30.31	95.41	2.37
4,103.00	5.93	2.89	4,097.50	144.12	-30.22	98.14	1.70
4,129.00	5.41	3.02	4,123.37	146.69	-30.09	100.28	2.00
4,161.00	4.87	9.63	4,155.25	149.54	-29.78	102.76	2.50
4,191.00	4.22	19.29	4,185.15	151.83	-29.21	104.95	3.34
4,223.00	3.66	31.13	4,217.08	153.82	-28.29	107.09	3.08
4,255.00	3.45	45.03	4,249.02	155.37	-27.08	109.06	2.76
4,290.00	3.64	63.87	4,283.95	156.61	-25.34	111.09	3.36
4,320.00	3.88	81.02	4,313.89	157.18	-23.48	112.65	3.82
4,351.00	4.05	89.01	4,344.81	157.37	-21.35	114.06	1.86
4,382.00	3.70	91.57	4,375.74	157.36	-19.25	115.30	1.26
4,413.00	2.20	97.59	4,406.70	157.25	-17.66	116.16	4.93
4,426.00	1.45	87.49	4,419.69	157.23	-17.25	116.38	6.26
4,507.00	0.34	313.85	4,500.68	157.44	-16.40	117.05	2.10
4,537.00	0.49	298.70	4,530.68	157.56	-16.58	117.05	0.62
4,567.00	0.75	306.18	4,560.68	157.74	-16.85	117.03	0.91
4,599.00	0.75	291.93	4,592.68	157.94	-17.21	116.98	0.58
4,629.00	0.77	249.59	4,622.68	157.94	-17.58	116.76	1.83
4,660.00	1.14	222.90	4,653.67	157.65	-17.99	116.28	1.84
4,690.00	1.59	227.48	4,683.66	157.15	-18.50	115.57	1.54
4,721.00	1.49	217.32	4,714.65	156.53	-19.06	114.75	0.94
4,752.00	1.28	222.56	4,745.64	155.96	-19.54	114.00	0.79
4,783.00	0.58	194.50	4,776.64	155.55	-19.81	113.51	2.63
4,814.00	0.53	164.43	4,807.64	155.26	-19.81	113.28	0.94
4,845.00	0.44	155.88	4,838.64	155.02	-19.73	113.13	0.37
4,876.00	0.73	126.28	4,869.64	154.79	-19.52	113.07	1.32
4,908.00	0.68	132.66	4,901.63	154.54	-19.21	113.05	0.29
4,939.00	0.76	145.75	4,932.63	154.25	-18.96	112.96	0.59
4,971.00	0.65	155.66	4,964.63	153.91	-18.77	112.81	0.51
5,001.00	0.81	152.76	4,994.63	153.56	-18.60	112.63	0.55
5,032.00	0.64	173.14	5,025.62	153.19	-18.48	112.40	0.99
5,062.00	0.90	180.40	5,055.62	152.79	-18.46	112.09	0.92
5,093.00	1.23	172.38	5,086.62	152.22	-18.42	111.65	1.17
5,123.00	1.92	170.55	5,116.60	151.40	-18.29	111.07	2.31
5,154.00	2.23	176.56	5,147.58	150.29	-18.17	110.25	1.22
5,184.00	2.48	174.28	5,177.56	149.06	-18.07	109.32	0.89
5,214.00	2.53	175.99	5,207.53	147.76	-17.96	108.33	0.30
5,245.00	2.71	179.39	5,238.50	146.34	-17.91	107.22	0.77
5,275.00	2.69	175.38	5,268.46	144.93	-17.84	106.13	0.63
5,306.00	2.81	180.78	5,299.43	143.44	-17.79	104.96	0.92
5,336.00	2.92	184.67	5,329.39	141.95	-17.87	103.71	0.74
5,368.00	2.90	181.50	5,361.35	140.33	-17.95	102.35	0.51

## Design Report for Ron Lamb 31A-4-1 - Plan #1 - Gyrodata Gyro and Sperry MWD Survey

Measured Depth (ft)	Inclination (°)	Azimuth (°)	Vertical Depth (ft)	+N/-S (ft)	+E/-W (ft)	Vertical Section (ft)	Dogleg Rate (°/100ft)
5,398.00	2.59	178.36	5,391.32	138.89	-17.95	101.20	1.15
5,428.00	2.83	178.19	5,421.28	137.47	-17.91	100.08	0.80
5,459.00	2.91	183.23	5,452.24	135.92	-17.93	98.82	0.85
5,489.00	3.15	178.68	5,482.20	134.34	-17.96	97.53	1.13
5,521.00	3.33	174.24	5,514.15	132.53	-17.84	96.14	0.96
5,551.00	3.39	171.46	5,544.10	130.79	-17.62	94.87	0.58
5,582.00	3.13	163.18	5,575.05	129.07	-17.24	93.71	1.73
5,612.00	3.06	156.81	5,605.00	127.55	-16.69	92.82	1.17
5,643.00	2.90	150.00	5,635.96	126.11	-15.97	92.08	1.25
5,674.00	2.70	144.54	5,666.93	124.84	-15.16	91.54	1.07
5,705.00	2.80	136.73	5,697.89	123.69	-14.21	91.18	1.25
5,737.00	2.65	122.90	5,729.85	122.72	-13.06	91.08	2.10
5,767.00	2.50	121.51	5,759.82	122.00	-11.92	91.18	0.54
5,798.00	1.91	116.91	5,790.80	121.42	-10.88	91.32	1.99
5,828.00	1.87	116.31	5,820.78	120.97	-10.00	91.49	0.15
5,859.00	1.94	114.88	5,851.77	120.53	-9.07	91.68	0.27
5,889.00	1.96	116.72	5,881.75	120.08	-8.15	91.87	0.22
5,921.00	1.95	113.13	5,913.73	119.62	-7.16	92.08	0.38
5,951.00	2.03	120.90	5,943.71	119.15	-6.23	92.25	0.94
5,983.00	2.20	119.66	5,975.69	118.56	-5.21	92.38	0.55
6,014.00	2.52	124.63	6,006.67	117.87	-4.13	92.47	1.22
6,045.00	2.33	138.17	6,037.64	117.02	-3.15	92.36	1.94
6,075.00	1.91	154.70	6,067.62	116.11	-2.53	92.00	2.46
6,107.00	1.91	162.89	6,099.60	115.12	-2.15	91.43	0.85
6,137.00	2.22	158.71	6,129.58	114.10	-1.79	90.82	1.15
6,169.00	2.44	163.27	6,161.55	112.87	-1.37	90.08	0.90
6,199.00	2.05	165.39	6,191.53	111.74	-1.05	89.36	1.33
6,229.00	1.05	151.56	6,221.52	110.98	-0.78	88.90	3.54
6,261.00	0.70	107.34	6,253.52	110.66	-0.46	88.84	2.29
6,291.00	0.81	50.25	6,283.51	110.74	-0.12	89.11	2.43
6,322.00	0.85	43.22	6,314.51	111.05	0.21	89.55	0.35
6,352.00	0.77	44.68	6,344.51	111.36	0.50	89.97	0.28
6,384.00	0.81	43.50	6,376.50	111.67	0.81	90.41	0.13
6,415.00	0.96	34.72	6,407.50	112.05	1.11	90.88	0.65
6,446.00	0.75	36.25	6,438.50	112.42	1.37	91.34	0.68
6,476.00	0.43	19.55	6,468.50	112.69	1.53	91.65	1.20
6,507.00	0.09	42.68	6,499.50	112.81	1.58	91.78	1.13
6,538.00	0.19	43.04	6,530.50	112.87	1.64	91.86	0.32
6,569.00	0.07	300.10	6,561.50	112.92	1.65	91.91	0.70
6,599.00	0.12	149.27	6,591.50	112.90	1.65	91.89	0.61
6,630.00	0.13	177.19	6,622.50	112.84	1.67	91.85	0.20
6,660.00	0.22	97.95	6,652.50	112.79	1.73	91.86	0.78
6,691.00	0.29	190.69	6,683.49	112.71	1.78	91.81	1.20
6,721.00	0.33	142.55	6,713.49	112.57	1.81	91.72	0.85
6,752.00	0.37	164.36	6,744.49	112.40	1.90	91.63	0.45
6,783.00	0.37	164.98	6,775.49	112.21	1.95	91.51	0.01
6,815.00	0.48	162.11	6,807.49	111.98	2.02	91.37	0.35
6,847.00	0.69	174.48	6,839.49	111.66	2.08	91.15	0.76
6,877.00	0.68	169.55	6,869.49	111.30	2.13	90.89	0.20
6,907.00	0.93	165.26	6,899.49	110.89	2.22	90.61	0.86

## Design Report for Ron Lamb 31A-4-1 - Plan #1 - Gyrodata Gyro and Sperry MWD Survey

Measured Depth (ft)	Inclination (°)	Azimuth (°)	Vertical Depth (ft)	+N/-S (ft)	+E/-W (ft)	Vertical Section (ft)	Dogleg Rate (°/100ft)
6,938.00	0.96	166.39	6,930.48	110.40	2.34	90.29	0.11
6,969.00	0.95	158.05	6,961.48	109.91	2.50	89.99	0.45
7,000.00	1.08	167.81	6,992.47	109.38	2.66	89.66	0.70
7,031.00	1.28	168.77	7,023.47	108.76	2.79	89.23	0.65
7,063.00	1.23	170.50	7,055.46	108.07	2.92	88.75	0.20
7,093.00	1.35	166.58	7,085.45	107.41	3.05	88.30	0.50
7,125.00	1.32	167.18	7,117.44	106.68	3.22	87.82	0.10
7,156.00	1.24	162.96	7,148.43	106.01	3.40	87.38	0.40
7,187.00	1.27	157.41	7,179.43	105.37	3.63	87.00	0.40
7,218.00	1.12	164.45	7,210.42	104.77	3.84	86.64	0.68
7,249.00	1.45	165.56	7,241.41	104.09	4.02	86.21	1.07
7,279.00	1.32	153.58	7,271.40	103.42	4.27	85.81	1.06
7,310.00	1.53	157.67	7,302.39	102.71	4.58	85.43	0.75
7,340.00	1.48	156.21	7,332.38	101.99	4.89	85.03	0.21
7,372.00	1.49	150.93	7,364.37	101.25	5.26	84.65	0.43
7,402.00	1.76	158.68	7,394.36	100.48	5.62	84.24	1.16
7,432.00	1.72	147.94	7,424.35	99.67	6.02	83.83	1.09
7,464.00	1.92	149.95	7,456.33	98.80	6.55	83.44	0.66
7,494.00	2.26	161.67	7,486.31	97.80	6.99	82.90	1.81
7,525.00	2.27	168.33	7,517.29	96.62	7.30	82.13	0.85
7,555.00	2.22	171.89	7,547.26	95.46	7.50	81.32	0.49
7,585.00	1.64	156.35	7,577.25	94.49	7.76	80.69	2.59
7,616.00	1.34	146.10	7,608.24	93.78	8.14	80.35	1.29
7,647.00	1.55	158.12	7,639.23	93.09	8.50	80.00	1.19
7,679.00	1.48	163.23	7,671.22	92.30	8.78	79.53	0.48
7,711.00	1.70	176.78	7,703.20	91.43	8.92	78.91	1.36
7,741.00	2.00	178.04	7,733.19	90.46	8.97	78.16	1.01
7,772.00	1.91	179.97	7,764.17	89.40	8.99	77.32	0.36
7,802.00	2.08	190.03	7,794.15	88.37	8.89	76.43	1.30
7,833.00	2.11	184.49	7,825.13	87.24	8.75	75.44	0.66
7,863.00	2.35	186.50	7,855.11	86.08	8.64	74.44	0.84
7,895.00	2.35	183.25	7,887.08	84.78	8.52	73.32	0.42
7,925.00	2.52	181.95	7,917.05	83.50	8.47	72.26	0.60
7,955.00	2.25	181.78	7,947.03	82.25	8.43	71.23	0.90
7,986.00	1.90	180.90	7,978.01	81.13	8.40	70.31	1.13
8,016.00	1.80	177.37	8,007.99	80.16	8.41	69.54	0.51
8,046.00	2.12	179.64	8,037.97	79.14	8.44	68.73	1.10
8,077.00	2.03	180.79	8,068.95	78.02	8.43	67.82	0.32
8,107.00	2.04	177.56	8,098.93	76.95	8.45	66.98	0.38
8,137.00	2.49	178.53	8,128.91	75.77	8.49	66.05	1.51
8,168.00	2.32	174.57	8,159.88	74.47	8.57	65.05	0.77
8,200.00	2.49	172.39	8,191.86	73.14	8.72	64.06	0.60
8,232.00	2.62	171.98	8,223.82	71.72	8.91	63.04	0.41
8,262.00	2.80	171.37	8,253.79	70.32	9.12	62.03	0.61
8,294.00	2.34	181.08	8,285.76	68.89	9.22	60.95	1.97
8,324.00	2.19	180.94	8,315.73	67.71	9.20	59.98	0.50
8,356.00	2.24	192.34	8,347.71	66.49	9.06	58.91	1.38
8,386.00	1.93	190.60	8,377.69	65.42	8.84	57.92	1.05
8,416.00	2.01	183.64	8,407.67	64.39	8.71	57.02	0.84
8,447.00	1.93	185.98	8,438.66	63.33	8.63	56.11	0.37



## Design Report for Ron Lamb 31A-4-1 - Plan #1 - Gyrodata Gyro and Sperry MWD Survey

Measured Depth (ft)	Inclination (°)	Azimuth (°)	Vertical Depth (ft)	+N/-S (ft)	+E/-W (ft)	Vertical Section (ft)	Dogleg Rate (°/100ft)
8,477.00	1.88	179.28	8,468.64	62.34	8.58	55.29	0.76
8,509.00	1.83	179.39	8,500.62	61.30	8.59	54.46	0.16
8,539.00	2.18	181.10	8,530.60	60.25	8.58	53.61	1.18
8,570.00	2.29	176.07	8,561.58	59.05	8.62	52.66	0.73
8,601.00	2.27	181.50	8,592.56	57.81	8.64	51.68	0.70
8,632.00	2.31	181.85	8,623.53	56.58	8.61	50.66	0.14
8,663.00	1.95	186.19	8,654.51	55.43	8.53	49.69	1.27
8,695.00	1.95	187.44	8,686.49	54.35	8.40	48.74	0.13
8,725.00	1.91	182.31	8,716.47	53.34	8.31	47.88	0.59
8,757.00	1.90	183.17	8,748.46	52.28	8.26	47.00	0.09
8,789.00	1.81	174.30	8,780.44	51.25	8.28	46.18	0.94
8,819.00	1.92	179.45	8,810.42	50.27	8.34	45.42	0.67
8,851.00	2.06	176.97	8,842.40	49.16	8.37	44.55	0.51
8,882.00	2.17	176.15	8,873.38	48.02	8.44	43.67	0.37
8,913.00	2.31	177.35	8,904.36	46.81	8.51	42.74	0.48
8,943.00	2.16	173.58	8,934.34	45.64	8.60	41.85	0.70
8,973.00	2.37	175.09	8,964.31	44.46	8.72	40.97	0.73
9,004.00	2.26	175.33	8,995.29	43.22	8.82	40.03	0.36
9,034.00	2.16	179.10	9,025.27	42.06	8.88	39.13	0.59
9,065.00	1.85	186.01	9,056.25	40.98	8.83	38.24	1.27
9,095.00	1.72	186.98	9,086.23	40.05	8.73	37.43	0.44
9,125.00	1.67	188.55	9,116.22	39.17	8.61	36.65	0.23
9,157.00	1.72	191.85	9,148.20	38.24	8.44	35.80	0.34
9,187.00	1.81	191.33	9,178.19	37.34	8.26	34.96	0.30
9,218.00	1.86	189.05	9,209.17	36.36	8.08	34.07	0.29
9,248.00	1.94	186.64	9,239.16	35.37	7.95	33.20	0.38
9,280.00	2.06	184.19	9,271.14	34.26	7.84	32.24	0.46
9,310.00	2.17	182.07	9,301.12	33.16	7.78	31.31	0.45
9,342.00	2.18	182.39	9,333.10	31.94	7.73	30.31	0.05
9,372.00	2.11	185.18	9,363.07	30.82	7.66	29.36	0.42
9,403.00	2.01	185.62	9,394.05	29.71	7.55	28.41	0.33
9,434.00	1.97	184.68	9,425.04	28.64	7.46	27.49	0.17
9,466.00	1.82	188.28	9,457.02	27.59	7.34	26.57	0.60
9,498.00	1.88	189.19	9,489.00	26.57	7.18	25.65	0.21
9,528.00	1.84	193.02	9,518.99	25.61	7.00	24.77	0.44
9,558.00	1.96	193.30	9,548.97	24.65	6.77	23.86	0.40
9,590.00	2.10	199.39	9,580.95	23.56	6.45	22.80	0.80
9,620.00	2.17	198.34	9,610.93	22.50	6.09	21.73	0.27
9,651.00	2.17	193.53	9,641.91	21.37	5.77	20.63	0.59
9,682.00	1.89	194.20	9,672.89	20.31	5.50	19.62	0.91
9,713.00	1.96	192.35	9,703.87	19.30	5.26	18.66	0.30
9,743.00	1.87	191.29	9,733.85	18.31	5.06	17.75	0.32
9,774.00	1.85	189.89	9,764.84	17.33	4.87	16.84	0.16
9,805.00	1.92	186.17	9,795.82	16.32	4.73	15.94	0.45
9,836.00	1.72	182.30	9,826.80	15.33	4.66	15.11	0.76
9,867.00	1.73	177.62	9,857.79	14.40	4.66	14.36	0.46
9,898.00	1.56	171.32	9,888.78	13.52	4.74	13.70	0.80
9,928.00	1.64	160.78	9,918.76	12.71	4.94	13.17	1.01
9,960.00	1.56	156.17	9,950.75	11.88	5.27	12.69	0.47
9,990.00	1.73	147.99	9,980.74	11.12	5.68	12.32	0.96

## Design Report for Ron Lamb 31A-4-1 - Plan #1 - Gyrodata Gyro and Sperry MWD Survey

Measured Depth (ft)	Inclination (°)	Azimuth (°)	Vertical Depth (ft)	+N/-S (ft)	+E/-W (ft)	Vertical Section (ft)	Dogleg Rate (°/100ft)
10,021.00	1.68	138.14	10,011.73	10.38	6.23	12.05	0.96
10,052.00	1.85	132.32	10,042.71	9.71	6.90	11.91	0.80
10,083.00	1.81	123.65	10,073.70	9.10	7.68	11.88	0.90
10,113.00	2.03	121.02	10,103.68	8.57	8.53	11.95	0.79
10,145.00	2.20	115.77	10,135.66	8.01	9.57	12.12	0.80
10,168.00	2.53	116.00	10,158.64	7.59	10.42	12.29	1.44
10,199.00	2.23	101.59	10,189.61	7.17	11.63	12.67	2.15
10,230.00	2.84	101.15	10,220.58	6.90	12.97	13.25	1.97
10,261.00	2.68	98.77	10,251.54	6.64	14.44	13.91	0.63
10,291.00	1.72	128.13	10,281.52	6.26	15.49	14.22	4.84
10,322.00	1.87	120.28	10,312.51	5.71	16.29	14.26	0.93
10,353.00	0.92	154.89	10,343.50	5.23	16.83	14.20	3.97
10,385.00	0.41	187.17	10,375.50	4.89	16.93	13.97	1.92
10,416.00	0.98	168.08	10,406.49	4.52	16.97	13.70	1.96
10,447.00	0.68	168.83	10,437.49	4.08	17.06	13.40	0.97
10,508.00	1.11	145.65	10,498.48	3.24	17.46	12.96	0.91
10,569.00	1.11	134.80	10,559.47	2.33	18.21	12.68	0.34
10,599.00	1.29	137.71	10,589.47	1.88	18.65	12.57	0.63
10,629.00	1.01	128.41	10,619.46	1.46	19.08	12.49	1.12
10,690.00	0.15	71.69	10,680.46	1.15	19.58	12.54	1.53
10,751.00	0.42	111.37	10,741.46	1.10	19.86	12.66	0.52
10,813.00	0.33	150.35	10,803.45	0.86	20.16	12.65	0.43
10,874.00	0.50	134.80	10,864.45	0.52	20.44	12.54	0.33
10,936.00	0.91	70.85	10,926.45	0.49	21.10	12.90	1.33
10,997.00	1.68	55.17	10,987.43	1.16	22.29	14.15	1.38
11,028.00	1.38	64.32	11,018.42	1.58	23.00	14.91	1.25
11,059.00	2.05	48.76	11,049.41	2.11	23.75	15.78	2.61
11,090.00	1.59	60.61	11,080.39	2.68	24.54	16.71	1.91
11,120.00	1.31	82.25	11,110.38	2.94	25.25	17.33	2.03
11,152.00	2.07	61.31	11,142.37	3.26	26.11	18.11	3.02
11,182.00	2.19	68.27	11,172.35	3.73	27.12	19.09	0.95
11,213.00	2.43	67.47	11,203.32	4.21	28.28	20.15	0.78
11,244.00	2.34	75.88	11,234.30	4.61	29.50	21.21	1.16
11,275.00	2.01	74.93	11,265.27	4.91	30.64	22.12	1.07
11,305.00	2.01	80.74	11,295.26	5.13	31.67	22.91	0.68
11,337.00	1.59	82.11	11,327.24	5.28	32.66	23.62	1.32
11,368.00	1.29	69.48	11,358.23	5.46	33.41	24.21	1.40
11,398.00	1.65	60.59	11,388.22	5.79	34.11	24.89	1.42
11,429.00	1.86	65.83	11,419.21	6.22	34.95	25.73	0.85
11,459.00	1.68	61.20	11,449.19	6.63	35.78	26.55	0.77
11,489.00	1.98	50.59	11,479.18	7.17	36.57	27.46	1.50
11,520.00	1.98	64.40	11,510.16	7.74	37.47	28.45	1.54
11,550.00	1.66	78.12	11,540.14	8.05	38.36	29.23	1.79
11,581.00	1.36	68.41	11,571.13	8.28	39.14	29.88	1.27
11,613.00	1.53	79.11	11,603.12	8.50	39.91	30.51	0.99
11,643.00	1.57	79.40	11,633.11	8.65	40.71	31.11	0.14
11,673.00	1.97	80.43	11,663.10	8.81	41.62	31.78	1.34
11,705.00	1.97	82.13	11,695.08	8.98	42.71	32.56	0.18
11,737.00	1.58	85.87	11,727.06	9.09	43.69	33.23	1.27
11,769.00	1.50	78.07	11,759.05	9.21	44.54	33.82	0.70

## Design Report for Ron Lamb 31A-4-1 - Plan #1 - Gyrodata Gyro and Sperry MWD Survey

Measured Depth (ft)	Inclination (°)	Azimuth (°)	Vertical Depth (ft)	+N/-S (ft)	+E/-W (ft)	Vertical Section (ft)	Dogleg Rate (°/100ft)
11,800.00	0.88	87.55	11,790.04	9.30	45.18	34.28	2.09
11,819.00	0.16	83.93	11,809.04	9.31	45.35	34.39	3.79
11,831.00	0.39	246.43	11,821.04	9.30	45.33	34.36	4.54
11,847.00	1.05	251.79	11,837.04	9.23	45.14	34.20	4.14
11,863.00	1.88	248.64	11,853.04	9.09	44.76	33.85	5.21
11,895.00	1.38	260.22	11,885.02	8.83	43.89	33.13	1.86
11,927.00	2.14	278.77	11,917.01	8.86	42.92	32.58	2.94
11,959.00	2.43	272.49	11,948.98	8.98	41.65	31.92	1.20
11,989.00	2.55	268.48	11,978.95	8.99	40.35	31.16	0.70
12,022.00	2.37	272.90	12,011.92	9.00	38.93	30.33	0.79
12,054.00	2.41	273.42	12,043.90	9.07	37.60	29.60	0.14
12,086.00	2.13	275.26	12,075.87	9.17	36.34	28.93	0.90
12,118.00	1.73	271.17	12,107.85	9.23	35.26	28.34	1.32
12,150.00	1.87	267.22	12,139.84	9.22	34.26	27.73	0.58
12,182.00	1.99	282.15	12,171.82	9.31	33.19	27.18	1.61
12,214.00	2.31	279.31	12,203.80	9.53	32.01	26.66	1.05
12,246.00	2.37	281.55	12,235.77	9.77	30.73	26.08	0.34
12,277.00	1.80	293.36	12,266.75	10.09	29.65	25.71	2.29
12,309.00	2.55	286.08	12,298.73	10.49	28.51	25.35	2.49
12,341.00	2.50	283.18	12,330.69	10.84	27.14	24.82	0.43
12,373.00	2.46	289.58	12,362.66	11.23	25.82	24.35	0.87
12,405.00	3.01	284.26	12,394.63	11.67	24.36	23.84	1.89
12,437.00	2.73	282.44	12,426.59	12.04	22.80	23.21	0.92
12,469.00	2.88	284.79	12,458.55	12.41	21.28	22.61	0.59
12,488.00	3.06	284.19	12,477.52	12.66	20.32	22.24	0.96
12,520.00	2.98	284.62	12,509.48	13.07	18.69	21.61	0.26
12,551.00	3.00	286.89	12,540.44	13.51	17.13	21.04	0.39
12,583.00	2.98	285.93	12,572.39	13.99	15.53	20.47	0.17
12,604.00	2.97	285.51	12,593.37	14.28	14.48	20.09	0.11
<b>Final Sperry MWD Survey</b>							
12,670.00	2.97	285.51	12,659.28	15.19	11.19	18.87	0.00
<b>Survey Projection to TD of Sperry Directional Work</b>							

### Design Annotations

Measured Depth (ft)	Vertical Depth (ft)	Local Coordinates +N/-S (ft)	+E/-W (ft)	Comment
200.00	200.00	0.63	-0.20	Surveys from 200.00ft to 2940.00ft are Gyrodata Gyro Surveys
2,940.00	2,938.99	59.75	1.90	Tie-On to Gyrodata Gyro Survey
3,025.00	3,023.85	63.96	-0.68	First Sperry MWD Survey
12,604.00	12,593.37	14.28	14.48	Final Sperry MWD Survey
12,670.00	12,659.28	15.19	11.19	Survey Projection to TD of Sperry Directional Work

### Vertical Section Information

Angle Type	Target	Azimuth (°)	Origin Type	Origin +N/-S (ft)	+E/-W (ft)	Start TVD (ft)
TD	No Target (Freehand)	36.36	Slot	0.00	0.00	0.00

---

Design Report for Ron Lamb 31A-4-1 - Plan #1 - Gyrodata Gyro and Sperry MWD Survey

---


Survey tool program

From (ft)	To (ft)	Survey/Plan	Survey Tool
200.00	2,940.00	Gyrodata Gyro Surveys	NS-GYRO-MS
3,025.00	12,670.00	Sperry MWD Surveys	MWD

Project: Sanpete County, UT  
Site: Sec. 31-T15S-R3E  
Well: Ron Lamb 31A-4-1  
Wellbore: Plan #1

# Petro-Hunt, LLC

**HALLIBURTON**




Project: Sanpete County, UT  
Site: Sec. 31-T15S-R3E  
Well: Ron Lamb 31A-4-1

# Petro-Hunt, LLC

HALLIBURTON

## LEGEND

- Ron Lamb 31A-4-1, Plan #1, Plan #1 Proposal V0
- Gyrodata Gyro and Sperry MWD Survey



STATE OF UTAH  
DEPARTMENT OF NATURAL RESOURCES  
DIVISION OF OIL, GAS AND MINING

AMENDED REPORT ☐ FORM 8  
(highlight changes)

WELL COMPLETION OR RECOMPLETION REPORT AND LOG

1a. TYPE OF WELL: OIL WELL ☐ GAS WELL ☐ DRY ☒ OTHER ☐

b. TYPE OF WORK: NEW WELL ☒ HORIZ. LATS. ☐ DEEP-EN ☐ RE-ENTRY ☐ DIFF. RESVR. ☐ OTHER ☐

2. NAME OF OPERATOR:  
PETRO-HUNT, L. L. C.

3. ADDRESS OF OPERATOR: 258 119TH AVE. SW CITY KILLDEER STATE ND ZIP 58640 PHONE NUMBER: (701) 863-6622

4. LOCATION OF WELL (FOOTAGES)  
AT SURFACE: 1569' FNL & 1154' FEL  
AT TOP PRODUCING INTERVAL REPORTED BELOW:  
54' 43'  
AT TOTAL DEPTH: 1569' FNL & 1154' FEL  
Per HSM Review

5. LEASE DESIGNATION AND SERIAL NUMBER:

PATENTED

6. IF INDIAN, ALLOTTEE OR TRIBE NAME  
N/A

7. UNIT or CA AGREEMENT NAME  
N/A

8. WELL NAME and NUMBER:  
RON LAMB 31A-4-1

9. API NUMBER:  
4303930034

10. FIELD AND POOL, OR WILDCAT  
WILDCAT

11. QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN:  
SENE 31 15S 3E S

12. COUNTY  
SANPETE

13. STATE  
UTAH

14. DATE SPUDDED: 11/28/2008 15. DATE T.D. REACHED: 2/17/2009 16. DATE COMPLETED: 2/24/2009 ABANDONED ☒ READY TO PRODUCE ☐

17. ELEVATIONS (DF, RKB, RT, GL):  
RKB = 5571'

18. TOTAL DEPTH: MD 12,670 TVD 12,659' 19. PLUG BACK T.D.: MD 10' TVD 10' 20. IF MULTIPLE COMPLETIONS, HOW MANY? \*

21. DEPTH BRIDGE MD 4,290 PLUG SET: TVD 4,290

22. TYPE ELECTRIC AND OTHER MECHANICAL LOGS RUN (Submit copy of each)

AT 1026' - GR/AIT/BHC; AT 4490' - GR/HRSLA/DIP/CAL; AT 12670' - FMI/DSL/SGTN/VSP

23. WAS WELL CORED? NO ☒ YES ☐ (Submit analysis)  
WAS DST RUN? NO ☒ YES ☐ (Submit report)  
DIRECTIONAL SURVEY? NO ☒ YES ☒ (Submit copy)

24. CASING AND LINER RECORD (Report all strings set in well)

HOLE SIZE	SIZE/GRADE	WEIGHT (#/ft)	TOP (MD)	BOTTOM (MD)	STAGE CEMENTER DEPTH	CEMENT TYPE & NO. OF SACKS	SLURRY VOLUME (BBL)	CEMENT TOP **	AMOUNT PULLED
48"	30 X52	234	0	80		G 675	109	0	0
26"	20 JK55	94	0	1,026		CBM 1,435	583	0	0
17.5"	13 3/8 HCP	68	0	4,490		ECO/G 1,940	1,041	0	0

25. TUBING RECORD

SIZE	DEPTH SET (MD)	PACKER SET (MD)	SIZE	DEPTH SET (MD)	PACKER SET (MD)	SIZE	DEPTH SET (MD)	PACKER SET (MD)

26. PRODUCING INTERVALS

FORMATION NAME	TOP (MD)	BOTTOM (MD)	TOP (TVD)	BOTTOM (TVD)	INTERVAL (Top/Bot - MD)	SIZE	NO. HOLES	PERFORATION STATUS
(A)								Open <input type="checkbox"/> Squeezed <input type="checkbox"/>
(B)								Open <input type="checkbox"/> Squeezed <input type="checkbox"/>
(C)								Open <input type="checkbox"/> Squeezed <input type="checkbox"/>
(D)								Open <input type="checkbox"/> Squeezed <input type="checkbox"/>

28. ACID, FRACTURE, TREATMENT, CEMENT SQUEEZE, ETC.

DEPTH INTERVAL	AMOUNT AND TYPE OF MATERIAL
4203' - 4490'	EZSV @ 4290'; SQZD 168 SX CMT BELOW, SPOTTED 68 SX ON TOP.
808' - 1208'	SPOTTED 292 SX BALANCED CMT PLUG.
10' - 221'	SPOTTED 147 SX BALANCED CMT PLUG.

29. ENCLOSED ATTACHMENTS:

☒ ELECTRICAL/MECHANICAL LOGS ☐ GEOLOGIC REPORT ☐ DST REPORT ☐ DIRECTIONAL SURVEY  
☒ SUNDRY NOTICE FOR PLUGGING AND CEMENT VERIFICATION ☐ CORE ANALYSIS ☐ OTHER:

30. WELL STATUS:

TA

RECEIVED  
JUL 26 2010

## 31. INITIAL PRODUCTION

## INTERVAL A (As shown in item #26)

DATE FIRST PRODUCED:		TEST DATE:		HOURS TESTED:		TEST PRODUCTION RATES: →	OIL – BBL:	GAS – MCF:	WATER – BBL:	PROD. METHOD:
CHOKE SIZE:	TBG. PRESS.	CSG. PRESS.	API GRAVITY	BTU – GAS	GAS/OIL RATIO	24 HR PRODUCTION RATES: →	OIL – BBL:	GAS – MCF:	WATER – BBL:	INTERVAL STATUS:

## INTERVAL B (As shown in item #26)

DATE FIRST PRODUCED:		TEST DATE:		HOURS TESTED:		TEST PRODUCTION RATES: →	OIL – BBL:	GAS – MCF:	WATER – BBL:	PROD. METHOD:
CHOKE SIZE:	TBG. PRESS.	CSG. PRESS.	API GRAVITY	BTU – GAS	GAS/OIL RATIO	24 HR PRODUCTION RATES: →	OIL – BBL:	GAS – MCF:	WATER – BBL:	INTERVAL STATUS:

## INTERVAL C (As shown in item #26)

DATE FIRST PRODUCED:		TEST DATE:		HOURS TESTED:		TEST PRODUCTION RATES: →	OIL – BBL:	GAS – MCF:	WATER – BBL:	PROD. METHOD:
CHOKE SIZE:	TBG. PRESS.	CSG. PRESS.	API GRAVITY	BTU – GAS	GAS/OIL RATIO	24 HR PRODUCTION RATES: →	OIL – BBL:	GAS – MCF:	WATER – BBL:	INTERVAL STATUS:

## INTERVAL D (As shown in item #26)

DATE FIRST PRODUCED:		TEST DATE:		HOURS TESTED:		TEST PRODUCTION RATES: →	OIL – BBL:	GAS – MCF:	WATER – BBL:	PROD. METHOD:
CHOKE SIZE:	TBG. PRESS.	CSG. PRESS.	API GRAVITY	BTU – GAS	GAS/OIL RATIO	24 HR PRODUCTION RATES: →	OIL – BBL:	GAS – MCF:	WATER – BBL:	INTERVAL STATUS:

## 32. DISPOSITION OF GAS (Sold, Used for Fuel, Vented, Etc.)

## 33. SUMMARY OF POROUS ZONES (Include Aquifers):

Show all important zones of porosity and contents thereof: Cored intervals and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures and recoveries.

## 34. FORMATION (Log) MARKERS:

Formation	Top (MD)	Bottom (MD)	Descriptions, Contents, etc.	Name	Top (Measured Depth)
Quat. Alluvium	25	140	SS/SLST/SH, WATER BEARING		
Miocene Moroni	140	2,210	LMST/SS/SH, WATER BEARING		
Miocene Volcanic	2,210	2,320	RHYOLITE, WATER BEARING		
Eocene Colton	2,320	3,475	SH/SLST/SS, WATER BEARING		
Paleo. Flag./Nhor	3,475	4,445	LMST/SH/SS, WATER BEARING		

## 35. ADDITIONAL REMARKS (Include plugging procedure)

PLEASE SEE ATTACHED PLUGGING SCHEMATIC.

36. I hereby certify that the foregoing and attached information is complete and correct as determined from all available records.

NAME (PLEASE PRINT) MIKE ENDRUD

TITLE DISTRICT MANAGER

SIGNATURE \_\_\_\_\_

DATE 7/22/2010

This report must be submitted within 30 days of

- completing or plugging a new well
- drilling horizontal laterals from an existing well bore
- recompleting to a different producing formation

- reentering a previously plugged and abandoned well
- significantly deepening an existing well bore below the previous bottom-hole depth
- drilling hydrocarbon exploratory holes, such as core samples and stratigraphic tests

\* ITEM 20: Show the number of completions if production is measured separately from two or more formations.

\*\* ITEM 24: Cement Top – Show how reported top(s) of cement were determined (circulated (CIR), calculated (CAL), cement bond log (CBL), temperature survey (TS)).

Send to: Utah Division of Oil, Gas and Mining  
1594 West North Temple, Suite 1210  
Box 145801  
Salt Lake City, Utah 84114-5801

Phone: 801-538-5340

Fax: 801-359-3940



ACTUAL T&A SCHEMATIC

PETRO HUNT L. L. C.

DRILLING PROGRAM

COMPANY NAME	PETRO HUNT L. L. C.	DATE	6/28/2010
WELL NAME	RON LAMB 31A-4-1	TD:	12670 RKB
FIELD	WILDCAT	PROSPECT:	WALES
LOCATION	SECTION 31, T 15S, R 3E	STATE:	UTAH
OBJECTIVE ZONE(S)	JURASSIC LOWER TWIN CREEK AND JURASSIC NAVAJO	COUNTY:	SANPETE
		WATER DEPTH:	N/A

cjv

GEOLOGICAL		MECHANICAL		
LOGS / SURVEYS	DEPTH	HOLE SIZE	CASING SIZE	MUD TYPE / MUD WEIGHT
DID NOT CUT CASING STRINGS LEFT WELLHEAD & INSTALLED DRY HOLE TREE	80'		30" X 0.375" Conductor Pipe	
SPOTTED SURFACE CEMENT PLUG 10 - 221' 147 SX, 15.8 PPG, 1.15 YLD - CLASS G VISUALLY INSPECTED PLUG				
SPOTTED CEMENT PLUG 808 - 1,208' 292 SX, 15.8 PPG, 1.23 YLD - CLASS G PRESSURE TESTED PLUG WITH 500 PSI				
1026' RKB		26"	20" 94# J/K55 BTC	9.0 PPG Brine
			F. G. 12.1 PPG	
EZSV @ 4,290', TAGGED TOP OF CEMENT @ 4,203' SQUEEZED 168 SX CEMENT BELOW RETAINER 4290-4490' SPOTTED 68 SX CEMENT ON TOP OF RETAINER 204 SX, 15.8 PPG, 1.23 YLD - CLASS G + 15% SALT				
4490' RKB		17 1/2"	13 3/8" 68# HCL80 BTC	9.0 PPG Brine
			F. G. 14.4 PPG / SHOE TEST 11.5 PPG	
NO HYDROCARBONS IN OPEN HOLE				
TD 12670' RKB		12 1/4"		10.4 PPG Salt Saturated

WELLHEAD EQUIPMENT LEFT ON WELL:  
FMC - 20-" SOW X 20 3/4" 3K STARTING HEAD  
FMC - 20 3/4" 3K X 13 5/8" 5K CASING SPOOL  
FMC - 13 5/8" 5K DRY HOLE TREE ON TOP

THIS TEMPORARY ABANDONMENT  
SCHEMATIC WAS APPROVED BY  
DUSTIN DOUCET 2-21-09 @ 1530 HR.  
HOME #(801) 733-0983

# **Petro-Hunt, LLC**

Sanpete County, UT

Sec. 31-T15S-R3E

Ron Lamb 31A-4-1

Plan #1

Design: Gyrodata Gyro and Sperry MWD Survey

## **Sperry Drilling Services Standard Report**

06 April, 2009

Well Coordinates: 6,976,041.82 N, 1,605,521.44 E (39° 28' 15.34" N, 111° 37' 25.01" W)

Ground Level: 5,543.40 ft

Local Coordinate Origin:

Centered on Well Ron Lamb 31A-4-1

Viewing Datum:

RKB 28' @ 5571.40ft (Original Well Elev)

TVDs to System:

N

North Reference:

True

Unit System:

API - US Survey Feet

Geodetic Scale Factor Applied

Version: 2003.14 Build: 57

**RECEIVED**

**HALLIBURTON**

**JUL 26 2010**

**DIV. OF OIL, GAS & MINING**

## Design Report for Ron Lamb 31A-4-1 - Plan #1 - Gyrodata Gyro and Sperry MWD Survey

Measured Depth (ft)	Inclination (°)	Azimuth (°)	Vertical Depth (ft)	+N/-S (ft)	+E/-W (ft)	Vertical Section (ft)	Dogleg Rate (°/100ft)
0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
200.00	0.38	342.58	200.00	0.63	-0.20	0.39	0.19
Surveys from 200.00ft to 2940.00ft are Gyrodata Gyro Surveys							
400.00	0.67	3.33	399.99	2.43	-0.33	1.76	0.17
600.00	0.44	22.04	599.98	4.31	0.03	3.49	0.14
800.00	0.56	18.12	799.97	5.95	0.62	5.16	0.06
1,000.00	0.61	12.97	999.96	7.92	1.16	7.07	0.04
1,100.00	0.52	350.94	1,099.96	8.89	1.21	7.87	0.23
1,200.00	0.73	26.61	1,199.95	9.90	1.42	8.82	0.43
1,300.00	0.76	26.00	1,299.94	11.07	2.00	10.10	0.03
1,400.00	0.60	22.14	1,399.94	12.15	2.49	11.26	0.17
1,500.00	0.96	24.34	1,499.93	13.40	3.03	12.59	0.36
1,600.00	0.93	31.25	1,599.91	14.86	3.80	14.21	0.12
1,700.00	1.46	27.60	1,699.89	16.68	4.81	16.28	0.54
1,800.00	1.69	28.11	1,799.85	19.11	6.09	19.00	0.23
1,900.00	1.93	22.22	1,899.80	21.97	7.42	22.09	0.30
2,000.00	1.93	19.37	1,999.75	25.12	8.62	25.34	0.10
2,100.00	2.22	14.40	2,099.68	28.58	9.66	28.74	0.34
2,200.00	2.34	10.71	2,199.60	32.46	10.52	32.38	0.19
2,300.00	2.31	2.00	2,299.52	36.48	10.97	35.88	0.35
2,400.00	2.29	356.71	2,399.44	40.49	10.93	39.08	0.21
2,500.00	2.08	350.21	2,499.37	44.27	10.50	41.88	0.32
2,600.00	1.90	338.71	2,599.31	47.61	9.59	44.02	0.44
2,700.00	2.06	331.68	2,699.25	50.73	8.14	45.68	0.29
2,800.00	2.57	326.16	2,799.17	54.18	6.04	47.21	0.56
2,900.00	2.95	322.22	2,899.05	58.07	3.21	48.67	0.42
2,940.00	3.16	321.65	2,938.99	59.75	1.90	49.24	0.53
Tie-On to Gyrodata Gyro Survey							
3,025.00	3.54	334.54	3,023.85	63.96	-0.68	51.10	0.99
First Sperry MWD Survey							
3,117.00	4.07	321.71	3,115.65	69.09	-3.93	53.30	1.09
3,210.00	4.73	324.53	3,208.37	74.80	-8.20	55.37	0.75
3,302.00	5.27	329.01	3,300.02	81.51	-12.57	58.18	0.72
3,334.00	5.33	327.14	3,331.89	84.02	-14.14	59.27	0.57
3,364.00	4.71	323.90	3,361.77	86.18	-15.62	60.14	2.27
3,394.00	4.85	329.52	3,391.67	88.27	-16.99	61.01	1.63
3,426.00	3.92	327.45	3,423.57	90.36	-18.26	61.93	2.95
3,457.00	3.29	334.02	3,454.51	92.05	-19.22	62.73	2.43
3,488.00	2.40	332.41	3,485.47	93.43	-19.91	63.43	2.88
3,520.00	2.15	330.14	3,517.45	94.54	-20.52	63.96	0.83
3,552.00	1.84	335.50	3,549.43	95.53	-21.03	64.45	1.13
3,583.00	0.88	327.27	3,580.42	96.18	-21.37	64.78	3.15
3,614.00	1.12	329.66	3,611.41	96.65	-21.65	64.99	0.79
3,644.00	1.58	321.74	3,641.41	97.22	-22.06	65.21	1.65
3,676.00	2.52	314.62	3,673.39	98.06	-22.83	65.43	3.04
3,706.00	3.13	318.50	3,703.35	99.14	-23.84	65.70	2.13
3,736.00	3.91	324.85	3,733.29	100.59	-24.97	66.19	2.90
3,768.00	4.35	327.58	3,765.21	102.51	-26.25	66.98	1.51
3,798.00	5.76	342.19	3,795.09	104.90	-27.32	68.27	6.33

## Design Report for Ron Lamb 31A-4-1 - Plan #1 - Gyrodata Gyro and Sperry MWD Survey

Measured Depth (ft)	Inclination (°)	Azimuth (°)	Vertical Depth (ft)	+N/-S (ft)	+E/-W (ft)	Vertical Section (ft)	Dogleg Rate (°/100ft)
3,827.00	7.13	347.80	3,823.91	108.05	-28.15	70.31	5.19
3,857.00	8.40	352.06	3,853.63	112.04	-28.84	73.12	4.64
3,888.00	8.53	355.20	3,884.30	116.57	-29.35	76.47	1.55
3,918.00	8.28	355.87	3,913.97	120.94	-29.69	79.78	0.89
3,950.00	7.81	356.59	3,945.66	125.41	-29.99	83.21	1.50
3,980.00	7.56	357.45	3,975.39	129.42	-30.20	86.31	0.92
4,011.00	7.26	358.57	4,006.13	133.41	-30.34	89.44	1.07
4,041.00	7.11	0.93	4,035.89	137.16	-30.35	92.45	1.10
4,072.00	6.38	0.31	4,066.68	140.80	-30.31	95.41	2.37
4,103.00	5.93	2.89	4,097.50	144.12	-30.22	98.14	1.70
4,129.00	5.41	3.02	4,123.37	146.69	-30.09	100.28	2.00
4,161.00	4.87	9.63	4,155.25	149.54	-29.78	102.76	2.50
4,191.00	4.22	19.29	4,185.15	151.83	-29.21	104.95	3.34
4,223.00	3.66	31.13	4,217.08	153.82	-28.29	107.09	3.08
4,255.00	3.45	45.03	4,249.02	155.37	-27.08	109.06	2.76
4,290.00	3.64	63.87	4,283.95	156.61	-25.34	111.09	3.36
4,320.00	3.88	81.02	4,313.89	157.18	-23.48	112.65	3.82
4,351.00	4.05	89.01	4,344.81	157.37	-21.35	114.06	1.86
4,382.00	3.70	91.57	4,375.74	157.36	-19.25	115.30	1.26
4,413.00	2.20	97.59	4,406.70	157.25	-17.66	116.16	4.93
4,426.00	1.45	87.49	4,419.69	157.23	-17.25	116.38	6.26
4,507.00	0.34	313.85	4,500.68	157.44	-16.40	117.05	2.10
4,537.00	0.49	298.70	4,530.68	157.56	-16.58	117.05	0.62
4,567.00	0.75	306.18	4,560.68	157.74	-16.85	117.03	0.91
4,599.00	0.75	291.93	4,592.68	157.94	-17.21	116.98	0.58
4,629.00	0.77	249.59	4,622.68	157.94	-17.58	116.76	1.83
4,660.00	1.14	222.90	4,653.67	157.65	-17.99	116.28	1.84
4,690.00	1.59	227.48	4,683.66	157.15	-18.50	115.57	1.54
4,721.00	1.49	217.32	4,714.65	156.53	-19.06	114.75	0.94
4,752.00	1.28	222.56	4,745.64	155.96	-19.54	114.00	0.79
4,783.00	0.58	194.50	4,776.64	155.55	-19.81	113.51	2.63
4,814.00	0.53	164.43	4,807.64	155.26	-19.81	113.28	0.94
4,845.00	0.44	155.88	4,838.64	155.02	-19.73	113.13	0.37
4,876.00	0.73	126.28	4,869.64	154.79	-19.52	113.07	1.32
4,908.00	0.68	132.66	4,901.63	154.54	-19.21	113.05	0.29
4,939.00	0.76	145.75	4,932.63	154.25	-18.96	112.96	0.59
4,971.00	0.65	155.66	4,964.63	153.91	-18.77	112.81	0.51
5,001.00	0.81	152.76	4,994.63	153.56	-18.60	112.63	0.55
5,032.00	0.64	173.14	5,025.62	153.19	-18.48	112.40	0.99
5,062.00	0.90	180.40	5,055.62	152.79	-18.46	112.09	0.92
5,093.00	1.23	172.38	5,086.62	152.22	-18.42	111.65	1.17
5,123.00	1.92	170.55	5,116.60	151.40	-18.29	111.07	2.31
5,154.00	2.23	176.56	5,147.58	150.29	-18.17	110.25	1.22
5,184.00	2.48	174.28	5,177.56	149.06	-18.07	109.32	0.89
5,214.00	2.53	175.99	5,207.53	147.76	-17.96	108.33	0.30
5,245.00	2.71	179.39	5,238.50	146.34	-17.91	107.22	0.77
5,275.00	2.69	175.38	5,268.46	144.93	-17.84	106.13	0.63
5,306.00	2.81	180.78	5,299.43	143.44	-17.79	104.96	0.92
5,336.00	2.92	184.67	5,329.39	141.95	-17.87	103.71	0.74
5,368.00	2.90	181.50	5,361.35	140.33	-17.95	102.35	0.51

## Design Report for Ron Lamb 31A-4-1 - Plan #1 - Gyrodata Gyro and Sperry MWD Survey

Measured Depth (ft)	Inclination (°)	Azimuth (°)	Vertical Depth (ft)	+N/-S (ft)	+E/-W (ft)	Vertical Section (ft)	Dogleg Rate (°/100ft)
5,398.00	2.59	178.36	5,391.32	138.89	-17.95	101.20	1.15
5,428.00	2.83	178.19	5,421.28	137.47	-17.91	100.08	0.80
5,459.00	2.91	183.23	5,452.24	135.92	-17.93	98.82	0.85
5,489.00	3.15	178.68	5,482.20	134.34	-17.96	97.53	1.13
5,521.00	3.33	174.24	5,514.15	132.53	-17.84	96.14	0.96
5,551.00	3.39	171.46	5,544.10	130.79	-17.62	94.87	0.58
5,582.00	3.13	163.18	5,575.05	129.07	-17.24	93.71	1.73
5,612.00	3.06	156.81	5,605.00	127.55	-16.69	92.82	1.17
5,643.00	2.90	150.00	5,635.96	126.11	-15.97	92.08	1.25
5,674.00	2.70	144.54	5,666.93	124.84	-15.16	91.54	1.07
5,705.00	2.80	136.73	5,697.89	123.69	-14.21	91.18	1.25
5,737.00	2.65	122.90	5,729.85	122.72	-13.06	91.08	2.10
5,767.00	2.50	121.51	5,759.82	122.00	-11.92	91.18	0.54
5,798.00	1.91	116.91	5,790.80	121.42	-10.88	91.32	1.99
5,828.00	1.87	116.31	5,820.78	120.97	-10.00	91.49	0.15
5,859.00	1.94	114.88	5,851.77	120.53	-9.07	91.68	0.27
5,889.00	1.96	116.72	5,881.75	120.08	-8.15	91.87	0.22
5,921.00	1.95	113.13	5,913.73	119.62	-7.16	92.08	0.38
5,951.00	2.03	120.90	5,943.71	119.15	-6.23	92.25	0.94
5,983.00	2.20	119.66	5,975.69	118.56	-5.21	92.38	0.55
6,014.00	2.52	124.63	6,006.67	117.87	-4.13	92.47	1.22
6,045.00	2.33	138.17	6,037.64	117.02	-3.15	92.36	1.94
6,075.00	1.91	154.70	6,067.62	116.11	-2.53	92.00	2.46
6,107.00	1.91	162.89	6,099.60	115.12	-2.15	91.43	0.85
6,137.00	2.22	158.71	6,129.58	114.10	-1.79	90.82	1.15
6,169.00	2.44	163.27	6,161.55	112.87	-1.37	90.08	0.90
6,199.00	2.05	165.39	6,191.53	111.74	-1.05	89.36	1.33
6,229.00	1.05	151.56	6,221.52	110.98	-0.78	88.90	3.54
6,261.00	0.70	107.34	6,253.52	110.66	-0.46	88.84	2.29
6,291.00	0.81	50.25	6,283.51	110.74	-0.12	89.11	2.43
6,322.00	0.85	43.22	6,314.51	111.05	0.21	89.55	0.35
6,352.00	0.77	44.68	6,344.51	111.36	0.50	89.97	0.28
6,384.00	0.81	43.50	6,376.50	111.67	0.81	90.41	0.13
6,415.00	0.96	34.72	6,407.50	112.05	1.11	90.88	0.65
6,446.00	0.75	36.25	6,438.50	112.42	1.37	91.34	0.68
6,476.00	0.43	19.55	6,468.50	112.69	1.53	91.65	1.20
6,507.00	0.09	42.68	6,499.50	112.81	1.58	91.78	1.13
6,538.00	0.19	43.04	6,530.50	112.87	1.64	91.86	0.32
6,569.00	0.07	300.10	6,561.50	112.92	1.65	91.91	0.70
6,599.00	0.12	149.27	6,591.50	112.90	1.65	91.89	0.61
6,630.00	0.13	177.19	6,622.50	112.84	1.67	91.85	0.20
6,660.00	0.22	97.95	6,652.50	112.79	1.73	91.86	0.78
6,691.00	0.29	190.69	6,683.49	112.71	1.78	91.81	1.20
6,721.00	0.33	142.55	6,713.49	112.57	1.81	91.72	0.85
6,752.00	0.37	164.36	6,744.49	112.40	1.90	91.63	0.45
6,783.00	0.37	164.98	6,775.49	112.21	1.95	91.51	0.01
6,815.00	0.48	162.11	6,807.49	111.98	2.02	91.37	0.35
6,847.00	0.69	174.48	6,839.49	111.66	2.08	91.15	0.76
6,877.00	0.68	169.55	6,869.49	111.30	2.13	90.89	0.20
6,907.00	0.93	165.26	6,899.49	110.89	2.22	90.61	0.86

## Design Report for Ron Lamb 31A-4-1 - Plan #1 - Gyrodata Gyro and Sperry MWD Survey

Measured Depth (ft)	Inclination (°)	Azimuth (°)	Vertical Depth (ft)	+N/-S (ft)	+E/-W (ft)	Vertical Section (ft)	Dogleg Rate (°/100ft)
6,938.00	0.96	166.39	6,930.48	110.40	2.34	90.29	0.11
6,969.00	0.95	158.05	6,961.48	109.91	2.50	89.99	0.45
7,000.00	1.08	167.81	6,992.47	109.38	2.66	89.66	0.70
7,031.00	1.28	168.77	7,023.47	108.76	2.79	89.23	0.65
7,063.00	1.23	170.50	7,055.46	108.07	2.92	88.75	0.20
7,093.00	1.35	166.58	7,085.45	107.41	3.05	88.30	0.50
7,125.00	1.32	167.18	7,117.44	106.68	3.22	87.82	0.10
7,156.00	1.24	162.96	7,148.43	106.01	3.40	87.38	0.40
7,187.00	1.27	157.41	7,179.43	105.37	3.63	87.00	0.40
7,218.00	1.12	164.45	7,210.42	104.77	3.84	86.64	0.68
7,249.00	1.45	165.56	7,241.41	104.09	4.02	86.21	1.07
7,279.00	1.32	153.58	7,271.40	103.42	4.27	85.81	1.06
7,310.00	1.53	157.67	7,302.39	102.71	4.58	85.43	0.75
7,340.00	1.48	156.21	7,332.38	101.99	4.89	85.03	0.21
7,372.00	1.49	150.93	7,364.37	101.25	5.26	84.65	0.43
7,402.00	1.76	158.68	7,394.36	100.48	5.62	84.24	1.16
7,432.00	1.72	147.94	7,424.35	99.67	6.02	83.83	1.09
7,464.00	1.92	149.95	7,456.33	98.80	6.55	83.44	0.66
7,494.00	2.26	161.67	7,486.31	97.80	6.99	82.90	1.81
7,525.00	2.27	168.33	7,517.29	96.62	7.30	82.13	0.85
7,555.00	2.22	171.89	7,547.26	95.46	7.50	81.32	0.49
7,585.00	1.64	156.35	7,577.25	94.49	7.76	80.69	2.59
7,616.00	1.34	146.10	7,608.24	93.78	8.14	80.35	1.29
7,647.00	1.55	158.12	7,639.23	93.09	8.50	80.00	1.19
7,679.00	1.48	163.23	7,671.22	92.30	8.78	79.53	0.48
7,711.00	1.70	176.78	7,703.20	91.43	8.92	78.91	1.36
7,741.00	2.00	178.04	7,733.19	90.46	8.97	78.16	1.01
7,772.00	1.91	179.97	7,764.17	89.40	8.99	77.32	0.36
7,802.00	2.08	190.03	7,794.15	88.37	8.89	76.43	1.30
7,833.00	2.11	184.49	7,825.13	87.24	8.75	75.44	0.66
7,863.00	2.35	186.50	7,855.11	86.08	8.64	74.44	0.84
7,895.00	2.35	183.25	7,887.08	84.78	8.52	73.32	0.42
7,925.00	2.52	181.95	7,917.05	83.50	8.47	72.26	0.60
7,955.00	2.25	181.78	7,947.03	82.25	8.43	71.23	0.90
7,986.00	1.90	180.90	7,978.01	81.13	8.40	70.31	1.13
8,016.00	1.80	177.37	8,007.99	80.16	8.41	69.54	0.51
8,046.00	2.12	179.64	8,037.97	79.14	8.44	68.73	1.10
8,077.00	2.03	180.79	8,068.95	78.02	8.43	67.82	0.32
8,107.00	2.04	177.56	8,098.93	76.95	8.45	66.98	0.38
8,137.00	2.49	178.53	8,128.91	75.77	8.49	66.05	1.51
8,168.00	2.32	174.57	8,159.88	74.47	8.57	65.05	0.77
8,200.00	2.49	172.39	8,191.86	73.14	8.72	64.06	0.60
8,232.00	2.62	171.98	8,223.82	71.72	8.91	63.04	0.41
8,262.00	2.80	171.37	8,253.79	70.32	9.12	62.03	0.61
8,294.00	2.34	181.08	8,285.76	68.89	9.22	60.95	1.97
8,324.00	2.19	180.94	8,315.73	67.71	9.20	59.98	0.50
8,356.00	2.24	192.34	8,347.71	66.49	9.06	58.91	1.38
8,386.00	1.93	190.60	8,377.69	65.42	8.84	57.92	1.05
8,416.00	2.01	183.64	8,407.67	64.39	8.71	57.02	0.84
8,447.00	1.93	185.98	8,438.66	63.33	8.63	56.11	0.37

## Design Report for Ron Lamb 31A-4-1 - Plan #1 - Gyrodata Gyro and Sperry MWD Survey

Measured Depth (ft)	Inclination (°)	Azimuth (°)	Vertical Depth (ft)	+N/-S (ft)	+E/-W (ft)	Vertical Section (ft)	Dogleg Rate (°/100ft)
8,477.00	1.88	179.28	8,468.64	62.34	8.58	55.29	0.76
8,509.00	1.83	179.39	8,500.62	61.30	8.59	54.46	0.16
8,539.00	2.18	181.10	8,530.60	60.25	8.58	53.61	1.18
8,570.00	2.29	176.07	8,561.58	59.05	8.62	52.66	0.73
8,601.00	2.27	181.50	8,592.56	57.81	8.64	51.68	0.70
8,632.00	2.31	181.85	8,623.53	56.58	8.61	50.66	0.14
8,663.00	1.95	186.19	8,654.51	55.43	8.53	49.69	1.27
8,695.00	1.95	187.44	8,686.49	54.35	8.40	48.74	0.13
8,725.00	1.91	182.31	8,716.47	53.34	8.31	47.88	0.59
8,757.00	1.90	183.17	8,748.46	52.28	8.26	47.00	0.09
8,789.00	1.81	174.30	8,780.44	51.25	8.28	46.18	0.94
8,819.00	1.92	179.45	8,810.42	50.27	8.34	45.42	0.67
8,851.00	2.06	176.97	8,842.40	49.16	8.37	44.55	0.51
8,882.00	2.17	176.15	8,873.38	48.02	8.44	43.67	0.37
8,913.00	2.31	177.35	8,904.36	46.81	8.51	42.74	0.48
8,943.00	2.16	173.58	8,934.34	45.64	8.60	41.85	0.70
8,973.00	2.37	175.09	8,964.31	44.46	8.72	40.97	0.73
9,004.00	2.26	175.33	8,995.29	43.22	8.82	40.03	0.36
9,034.00	2.16	179.10	9,025.27	42.06	8.88	39.13	0.59
9,065.00	1.85	186.01	9,056.25	40.98	8.83	38.24	1.27
9,095.00	1.72	186.98	9,086.23	40.05	8.73	37.43	0.44
9,125.00	1.67	188.55	9,116.22	39.17	8.61	36.65	0.23
9,157.00	1.72	191.85	9,148.20	38.24	8.44	35.80	0.34
9,187.00	1.81	191.33	9,178.19	37.34	8.26	34.96	0.30
9,218.00	1.86	189.05	9,209.17	36.36	8.08	34.07	0.29
9,248.00	1.94	186.64	9,239.16	35.37	7.95	33.20	0.38
9,280.00	2.06	184.19	9,271.14	34.26	7.84	32.24	0.46
9,310.00	2.17	182.07	9,301.12	33.16	7.78	31.31	0.45
9,342.00	2.18	182.39	9,333.10	31.94	7.73	30.31	0.05
9,372.00	2.11	185.18	9,363.07	30.82	7.66	29.36	0.42
9,403.00	2.01	185.62	9,394.05	29.71	7.55	28.41	0.33
9,434.00	1.97	184.68	9,425.04	28.64	7.46	27.49	0.17
9,466.00	1.82	188.28	9,457.02	27.59	7.34	26.57	0.60
9,498.00	1.88	189.19	9,489.00	26.57	7.18	25.65	0.21
9,528.00	1.84	193.02	9,518.99	25.61	7.00	24.77	0.44
9,558.00	1.96	193.30	9,548.97	24.65	6.77	23.86	0.40
9,590.00	2.10	199.39	9,580.95	23.56	6.45	22.80	0.80
9,620.00	2.17	198.34	9,610.93	22.50	6.09	21.73	0.27
9,651.00	2.17	193.53	9,641.91	21.37	5.77	20.63	0.59
9,682.00	1.89	194.20	9,672.89	20.31	5.50	19.62	0.91
9,713.00	1.96	192.35	9,703.87	19.30	5.26	18.66	0.30
9,743.00	1.87	191.29	9,733.85	18.31	5.06	17.75	0.32
9,774.00	1.85	189.89	9,764.84	17.33	4.87	16.84	0.16
9,805.00	1.92	186.17	9,795.82	16.32	4.73	15.94	0.45
9,836.00	1.72	182.30	9,826.80	15.33	4.66	15.11	0.76
9,867.00	1.73	177.62	9,857.79	14.40	4.66	14.36	0.46
9,898.00	1.56	171.32	9,888.78	13.52	4.74	13.70	0.80
9,928.00	1.64	160.78	9,918.76	12.71	4.94	13.17	1.01
9,960.00	1.56	156.17	9,950.75	11.88	5.27	12.69	0.47
9,990.00	1.73	147.99	9,980.74	11.12	5.68	12.32	0.96

## Design Report for Ron Lamb 31A-4-1 - Plan #1 - Gyrodata Gyro and Sperry MWD Survey

Measured Depth (ft)	Inclination (°)	Azimuth (°)	Vertical Depth (ft)	+N/-S (ft)	+E/-W (ft)	Vertical Section (ft)	Dogleg Rate (°/100ft)
10,021.00	1.68	138.14	10,011.73	10.38	6.23	12.05	0.96
10,052.00	1.85	132.32	10,042.71	9.71	6.90	11.91	0.80
10,083.00	1.81	123.65	10,073.70	9.10	7.68	11.88	0.90
10,113.00	2.03	121.02	10,103.68	8.57	8.53	11.95	0.79
10,145.00	2.20	115.77	10,135.66	8.01	9.57	12.12	0.80
10,168.00	2.53	116.00	10,158.64	7.59	10.42	12.29	1.44
10,199.00	2.23	101.59	10,189.61	7.17	11.63	12.67	2.15
10,230.00	2.84	101.15	10,220.58	6.90	12.97	13.25	1.97
10,261.00	2.68	98.77	10,251.54	6.64	14.44	13.91	0.63
10,291.00	1.72	128.13	10,281.52	6.26	15.49	14.22	4.84
10,322.00	1.87	120.28	10,312.51	5.71	16.29	14.26	0.93
10,353.00	0.92	154.89	10,343.50	5.23	16.83	14.20	3.97
10,385.00	0.41	187.17	10,375.50	4.89	16.93	13.97	1.92
10,416.00	0.98	168.08	10,406.49	4.52	16.97	13.70	1.96
10,447.00	0.68	168.83	10,437.49	4.08	17.06	13.40	0.97
10,508.00	1.11	145.65	10,498.48	3.24	17.46	12.96	0.91
10,569.00	1.11	134.80	10,559.47	2.33	18.21	12.68	0.34
10,599.00	1.29	137.71	10,589.47	1.88	18.65	12.57	0.63
10,629.00	1.01	128.41	10,619.46	1.46	19.08	12.49	1.12
10,690.00	0.15	71.69	10,680.46	1.15	19.58	12.54	1.53
10,751.00	0.42	111.37	10,741.46	1.10	19.86	12.66	0.52
10,813.00	0.33	150.35	10,803.45	0.86	20.16	12.65	0.43
10,874.00	0.50	134.80	10,864.45	0.52	20.44	12.54	0.33
10,936.00	0.91	70.85	10,926.45	0.49	21.10	12.90	1.33
10,997.00	1.68	55.17	10,987.43	1.16	22.29	14.15	1.38
11,028.00	1.38	64.32	11,018.42	1.58	23.00	14.91	1.25
11,059.00	2.05	48.76	11,049.41	2.11	23.75	15.78	2.61
11,090.00	1.59	60.61	11,080.39	2.68	24.54	16.71	1.91
11,120.00	1.31	82.25	11,110.38	2.94	25.25	17.33	2.03
11,152.00	2.07	61.31	11,142.37	3.26	26.11	18.11	3.02
11,182.00	2.19	68.27	11,172.35	3.73	27.12	19.09	0.95
11,213.00	2.43	67.47	11,203.32	4.21	28.28	20.15	0.78
11,244.00	2.34	75.88	11,234.30	4.61	29.50	21.21	1.16
11,275.00	2.01	74.93	11,265.27	4.91	30.64	22.12	1.07
11,305.00	2.01	80.74	11,295.26	5.13	31.67	22.91	0.68
11,337.00	1.59	82.11	11,327.24	5.28	32.66	23.62	1.32
11,368.00	1.29	69.48	11,358.23	5.46	33.41	24.21	1.40
11,398.00	1.65	60.59	11,388.22	5.79	34.11	24.89	1.42
11,429.00	1.86	65.83	11,419.21	6.22	34.95	25.73	0.85
11,459.00	1.68	61.20	11,449.19	6.63	35.78	26.55	0.77
11,489.00	1.98	50.59	11,479.18	7.17	36.57	27.46	1.50
11,520.00	1.98	64.40	11,510.16	7.74	37.47	28.45	1.54
11,550.00	1.66	78.12	11,540.14	8.05	38.36	29.23	1.79
11,581.00	1.36	68.41	11,571.13	8.28	39.14	29.88	1.27
11,613.00	1.53	79.11	11,603.12	8.50	39.91	30.51	0.99
11,643.00	1.57	79.40	11,633.11	8.65	40.71	31.11	0.14
11,673.00	1.97	80.43	11,663.10	8.81	41.62	31.78	1.34
11,705.00	1.97	82.13	11,695.08	8.98	42.71	32.56	0.18
11,737.00	1.58	85.87	11,727.06	9.09	43.69	33.23	1.27
11,769.00	1.50	78.07	11,759.05	9.21	44.54	33.82	0.70



## Design Report for Ron Lamb 31A-4-1 - Plan #1 - Gyrodata Gyro and Sperry MWD Survey

Measured Depth (ft)	Inclination (°)	Azimuth (°)	Vertical Depth (ft)	+N/-S (ft)	+E/-W (ft)	Vertical Section (ft)	Dogleg Rate (°/100ft)
11,800.00	0.88	87.55	11,790.04	9.30	45.18	34.28	2.09
11,819.00	0.16	83.93	11,809.04	9.31	45.35	34.39	3.79
11,831.00	0.39	246.43	11,821.04	9.30	45.33	34.36	4.54
11,847.00	1.05	251.79	11,837.04	9.23	45.14	34.20	4.14
11,863.00	1.88	248.64	11,853.04	9.09	44.76	33.85	5.21
11,895.00	1.38	260.22	11,885.02	8.83	43.89	33.13	1.86
11,927.00	2.14	278.77	11,917.01	8.86	42.92	32.58	2.94
11,959.00	2.43	272.49	11,948.98	8.98	41.65	31.92	1.20
11,989.00	2.55	268.48	11,978.95	8.99	40.35	31.16	0.70
12,022.00	2.37	272.90	12,011.92	9.00	38.93	30.33	0.79
12,054.00	2.41	273.42	12,043.90	9.07	37.60	29.60	0.14
12,086.00	2.13	275.26	12,075.87	9.17	36.34	28.93	0.90
12,118.00	1.73	271.17	12,107.85	9.23	35.26	28.34	1.32
12,150.00	1.87	267.22	12,139.84	9.22	34.26	27.73	0.58
12,182.00	1.99	282.15	12,171.82	9.31	33.19	27.18	1.61
12,214.00	2.31	279.31	12,203.80	9.53	32.01	26.66	1.05
12,246.00	2.37	281.55	12,235.77	9.77	30.73	26.08	0.34
12,277.00	1.80	293.36	12,266.75	10.09	29.65	25.71	2.29
12,309.00	2.55	286.08	12,298.73	10.49	28.51	25.35	2.49
12,341.00	2.50	283.18	12,330.69	10.84	27.14	24.82	0.43
12,373.00	2.46	289.58	12,362.66	11.23	25.82	24.35	0.87
12,405.00	3.01	284.26	12,394.63	11.67	24.36	23.84	1.89
12,437.00	2.73	282.44	12,426.59	12.04	22.80	23.21	0.92
12,469.00	2.88	284.79	12,458.55	12.41	21.28	22.61	0.59
12,488.00	3.06	284.19	12,477.52	12.66	20.32	22.24	0.96
12,520.00	2.98	284.62	12,509.48	13.07	18.69	21.61	0.26
12,551.00	3.00	286.89	12,540.44	13.51	17.13	21.04	0.39
12,583.00	2.98	285.93	12,572.39	13.99	15.53	20.47	0.17
12,604.00	2.97	285.51	12,593.37	14.28	14.48	20.09	0.11
<b>Final Sperry MWD Survey</b>							
12,670.00	2.97	285.51	12,659.28	15.19	11.19	18.87	0.00
<b>Survey Projection to TD of Sperry Directional Work</b>							

Design Annotations

Measured Depth (ft)	Vertical Depth (ft)	Local Coordinates +N/-S (ft)	+E/-W (ft)	Comment
200.00	200.00	0.63	-0.20	Surveys from 200.00ft to 2940.00ft are Gyrodata Gyro Surveys
2,940.00	2,938.99	59.75	1.90	Tie-On to Gyrodata Gyro Survey
3,025.00	3,023.85	63.96	-0.68	First Sperry MWD Survey
12,604.00	12,593.37	14.28	14.48	Final Sperry MWD Survey
12,670.00	12,659.28	15.19	11.19	Survey Projection to TD of Sperry Directional Work

Vertical Section Information

Angle Type	Target	Azimuth (°)	Origin Type	Origin +N/-S (ft)	Origin +E/-W (ft)	Start TVD (ft)
TD	No Target (Freehand)	36.36	Slot	0.00	0.00	0.00

---

**Design Report for Ron Lamb 31A-4-1 - Plan #1 - Gyrodata Gyro and Sperry MWD Survey**

---


**Survey tool program**

From (ft)	To (ft)	Survey/Plan	Survey Tool
200.00	2,940.00	Gyrodata Gyro Surveys	NS-GYRO-MS
3,025.00	12,670.00	Sperry MWD Surveys	MWD

Project: Sanpete County, UT  
Site: Sec. 31-T15S-R3E  
Well: Ron Lamb 31A-4-1  
Wellbore: Plan #1

# Petro-Hunt, LLC

**HALLIBURTON**




Project: Sanpete County, UT  
Site: Sec. 31-T15S-R3E  
Well: Ron Lamb 31A-4-1

# Petro-Hunt, LLC

HALLIBURTON

## LEGEND

- Ron Lamb 31A-4-1, Plan #1, Plan #1 Proposal V0
- Gyrodata Gyro and Sperry MWD Survey



# **Petro-Hunt, LLC**

Sanpete County, UT

Sec. 31-T15S-R3E

Ron Lamb 31A-4-1

Plan #1

Design: Gyrodata Gyro and Sperry MWD Survey

## **Sperry Drilling Services Standard Report**

06 April, 2009

Well Coordinates: 6,976,041.82 N, 1,605,521.44 E (39° 28' 15.34" N, 111° 37' 25.01" W)  
Ground Level: 5,543.40 ft

Local Coordinate Origin:	Centered on Well Ron Lamb 31A-4-1
Viewing Datum:	RKB 28' @ 5571.40ft (Original Well Elev)
TVDs to System:	N
North Reference:	True
Unit System:	API - US Survey Feet

Geodetic Scale Factor Applied  
Version: 2003.14 Build: 57

**RECEIVED**

**JUL 26 2010**

**DIV. OF OIL, GAS & MINING**

**HALLIBURTON**

## Design Report for Ron Lamb 31A-4-1 - Plan #1 - Gyrodata Gyro and Sperry MWD Survey

Measured Depth (ft)	Inclination (°)	Azimuth (°)	Vertical Depth (ft)	+N/-S (ft)	+E/-W (ft)	Vertical Section (ft)	Dogleg Rate (°/100ft)
0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
200.00	0.38	342.58	200.00	0.63	-0.20	0.39	0.19
<b>Surveys from 200.00ft to 2940.00ft are Gyrodata Gyro Surveys</b>							
400.00	0.67	3.33	399.99	2.43	-0.33	1.76	0.17
600.00	0.44	22.04	599.98	4.31	0.03	3.49	0.14
800.00	0.56	18.12	799.97	5.95	0.62	5.16	0.06
1,000.00	0.61	12.97	999.96	7.92	1.16	7.07	0.04
1,100.00	0.52	350.94	1,099.96	8.89	1.21	7.87	0.23
1,200.00	0.73	26.61	1,199.95	9.90	1.42	8.82	0.43
1,300.00	0.76	26.00	1,299.94	11.07	2.00	10.10	0.03
1,400.00	0.60	22.14	1,399.94	12.15	2.49	11.26	0.17
1,500.00	0.96	24.34	1,499.93	13.40	3.03	12.59	0.36
1,600.00	0.93	31.25	1,599.91	14.86	3.80	14.21	0.12
1,700.00	1.46	27.60	1,699.89	16.68	4.81	16.28	0.54
1,800.00	1.69	28.11	1,799.85	19.11	6.09	19.00	0.23
1,900.00	1.93	22.22	1,899.80	21.97	7.42	22.09	0.30
2,000.00	1.93	19.37	1,999.75	25.12	8.62	25.34	0.10
2,100.00	2.22	14.40	2,099.68	28.58	9.66	28.74	0.34
2,200.00	2.34	10.71	2,199.60	32.46	10.52	32.38	0.19
2,300.00	2.31	2.00	2,299.52	36.48	10.97	35.88	0.35
2,400.00	2.29	356.71	2,399.44	40.49	10.93	39.08	0.21
2,500.00	2.08	350.21	2,499.37	44.27	10.50	41.88	0.32
2,600.00	1.90	338.71	2,599.31	47.61	9.59	44.02	0.44
2,700.00	2.06	331.68	2,699.25	50.73	8.14	45.68	0.29
2,800.00	2.57	326.16	2,799.17	54.18	6.04	47.21	0.56
2,900.00	2.95	322.22	2,899.05	58.07	3.21	48.67	0.42
2,940.00	3.16	321.65	2,938.99	59.75	1.90	49.24	0.53
<b>Tie-On to Gyrodata Gyro Survey</b>							
3,025.00	3.54	334.54	3,023.85	63.96	-0.68	51.10	0.99
<b>First Sperry MWD Survey</b>							
3,117.00	4.07	321.71	3,115.65	69.09	-3.93	53.30	1.09
3,210.00	4.73	324.53	3,208.37	74.80	-8.20	55.37	0.75
3,302.00	5.27	329.01	3,300.02	81.51	-12.57	58.18	0.72
3,334.00	5.33	327.14	3,331.89	84.02	-14.14	59.27	0.57
3,364.00	4.71	323.90	3,361.77	86.18	-15.62	60.14	2.27
3,394.00	4.85	329.52	3,391.67	88.27	-16.99	61.01	1.63
3,426.00	3.92	327.45	3,423.57	90.36	-18.26	61.93	2.95
3,457.00	3.29	334.02	3,454.51	92.05	-19.22	62.73	2.43
3,488.00	2.40	332.41	3,485.47	93.43	-19.91	63.43	2.88
3,520.00	2.15	330.14	3,517.45	94.54	-20.52	63.96	0.83
3,552.00	1.84	335.50	3,549.43	95.53	-21.03	64.45	1.13
3,583.00	0.88	327.27	3,580.42	96.18	-21.37	64.78	3.15
3,614.00	1.12	329.66	3,611.41	96.65	-21.65	64.99	0.79
3,644.00	1.58	321.74	3,641.41	97.22	-22.06	65.21	1.65
3,676.00	2.52	314.62	3,673.39	98.06	-22.83	65.43	3.04
3,706.00	3.13	318.50	3,703.35	99.14	-23.84	65.70	2.13
3,736.00	3.91	324.85	3,733.29	100.59	-24.97	66.19	2.90
3,768.00	4.35	327.58	3,765.21	102.51	-26.25	66.98	1.51
3,798.00	5.76	342.19	3,795.09	104.90	-27.32	68.27	6.33

## Design Report for Ron Lamb 31A-4-1 - Plan #1 - Gyrodata Gyro and Sperry MWD Survey

Measured Depth (ft)	Inclination (°)	Azimuth (°)	Vertical Depth (ft)	+N/-S (ft)	+E/-W (ft)	Vertical Section (ft)	Dogleg Rate (°/100ft)
3,827.00	7.13	347.80	3,823.91	108.05	-28.15	70.31	5.19
3,857.00	8.40	352.06	3,853.63	112.04	-28.84	73.12	4.64
3,888.00	8.53	355.20	3,884.30	116.57	-29.35	76.47	1.55
3,918.00	8.28	355.87	3,913.97	120.94	-29.69	79.78	0.89
3,950.00	7.81	356.59	3,945.66	125.41	-29.99	83.21	1.50
3,980.00	7.56	357.45	3,975.39	129.42	-30.20	86.31	0.92
4,011.00	7.26	358.57	4,006.13	133.41	-30.34	89.44	1.07
4,041.00	7.11	0.93	4,035.89	137.16	-30.35	92.45	1.10
4,072.00	6.38	0.31	4,066.68	140.80	-30.31	95.41	2.37
4,103.00	5.93	2.89	4,097.50	144.12	-30.22	98.14	1.70
4,129.00	5.41	3.02	4,123.37	146.69	-30.09	100.28	2.00
4,161.00	4.87	9.63	4,155.25	149.54	-29.78	102.76	2.50
4,191.00	4.22	19.29	4,185.15	151.83	-29.21	104.95	3.34
4,223.00	3.66	31.13	4,217.08	153.82	-28.29	107.09	3.08
4,255.00	3.45	45.03	4,249.02	155.37	-27.08	109.06	2.76
4,290.00	3.64	63.87	4,283.95	156.61	-25.34	111.09	3.36
4,320.00	3.88	81.02	4,313.89	157.18	-23.48	112.65	3.82
4,351.00	4.05	89.01	4,344.81	157.37	-21.35	114.06	1.86
4,382.00	3.70	91.57	4,375.74	157.36	-19.25	115.30	1.26
4,413.00	2.20	97.59	4,406.70	157.25	-17.66	116.16	4.93
4,426.00	1.45	87.49	4,419.69	157.23	-17.25	116.38	6.26
4,507.00	0.34	313.85	4,500.68	157.44	-16.40	117.05	2.10
4,537.00	0.49	298.70	4,530.68	157.56	-16.58	117.05	0.62
4,567.00	0.75	306.18	4,560.68	157.74	-16.85	117.03	0.91
4,599.00	0.75	291.93	4,592.68	157.94	-17.21	116.98	0.58
4,629.00	0.77	249.59	4,622.68	157.94	-17.58	116.76	1.83
4,660.00	1.14	222.90	4,653.67	157.65	-17.99	116.28	1.84
4,690.00	1.59	227.48	4,683.66	157.15	-18.50	115.57	1.54
4,721.00	1.49	217.32	4,714.65	156.53	-19.06	114.75	0.94
4,752.00	1.28	222.56	4,745.64	155.96	-19.54	114.00	0.79
4,783.00	0.58	194.50	4,776.64	155.55	-19.81	113.51	2.63
4,814.00	0.53	164.43	4,807.64	155.26	-19.81	113.28	0.94
4,845.00	0.44	155.88	4,838.64	155.02	-19.73	113.13	0.37
4,876.00	0.73	126.28	4,869.64	154.79	-19.52	113.07	1.32
4,908.00	0.68	132.66	4,901.63	154.54	-19.21	113.05	0.29
4,939.00	0.76	145.75	4,932.63	154.25	-18.96	112.96	0.59
4,971.00	0.65	155.66	4,964.63	153.91	-18.77	112.81	0.51
5,001.00	0.81	152.76	4,994.63	153.56	-18.60	112.63	0.55
5,032.00	0.64	173.14	5,025.62	153.19	-18.48	112.40	0.99
5,062.00	0.90	180.40	5,055.62	152.79	-18.46	112.09	0.92
5,093.00	1.23	172.38	5,086.62	152.22	-18.42	111.65	1.17
5,123.00	1.92	170.55	5,116.60	151.40	-18.29	111.07	2.31
5,154.00	2.23	176.56	5,147.58	150.29	-18.17	110.25	1.22
5,184.00	2.48	174.28	5,177.56	149.06	-18.07	109.32	0.89
5,214.00	2.53	175.99	5,207.53	147.76	-17.96	108.33	0.30
5,245.00	2.71	179.39	5,238.50	146.34	-17.91	107.22	0.77
5,275.00	2.69	175.38	5,268.46	144.93	-17.84	106.13	0.63
5,306.00	2.81	180.78	5,299.43	143.44	-17.79	104.96	0.92
5,336.00	2.92	184.67	5,329.39	141.95	-17.87	103.71	0.74
5,368.00	2.90	181.50	5,361.35	140.33	-17.95	102.35	0.51

## Design Report for Ron Lamb 31A-4-1 - Plan #1 - Gyrodata Gyro and Sperry MWD Survey

Measured Depth (ft)	Inclination (°)	Azimuth (°)	Vertical Depth (ft)	+N/-S (ft)	+E/-W (ft)	Vertical Section (ft)	Dogleg Rate (°/100ft)
5,398.00	2.59	178.36	5,391.32	138.89	-17.95	101.20	1.15
5,428.00	2.83	178.19	5,421.28	137.47	-17.91	100.08	0.80
5,459.00	2.91	183.23	5,452.24	135.92	-17.93	98.82	0.85
5,489.00	3.15	178.68	5,482.20	134.34	-17.96	97.53	1.13
5,521.00	3.33	174.24	5,514.15	132.53	-17.84	96.14	0.96
5,551.00	3.39	171.46	5,544.10	130.79	-17.62	94.87	0.58
5,582.00	3.13	163.18	5,575.05	129.07	-17.24	93.71	1.73
5,612.00	3.06	156.81	5,605.00	127.55	-16.69	92.82	1.17
5,643.00	2.90	150.00	5,635.96	126.11	-15.97	92.08	1.25
5,674.00	2.70	144.54	5,666.93	124.84	-15.16	91.54	1.07
5,705.00	2.80	136.73	5,697.89	123.69	-14.21	91.18	1.25
5,737.00	2.65	122.90	5,729.85	122.72	-13.06	91.08	2.10
5,767.00	2.50	121.51	5,759.82	122.00	-11.92	91.18	0.54
5,798.00	1.91	116.91	5,790.80	121.42	-10.88	91.32	1.99
5,828.00	1.87	116.31	5,820.78	120.97	-10.00	91.49	0.15
5,859.00	1.94	114.88	5,851.77	120.53	-9.07	91.68	0.27
5,889.00	1.96	116.72	5,881.75	120.08	-8.15	91.87	0.22
5,921.00	1.95	113.13	5,913.73	119.62	-7.16	92.08	0.38
5,951.00	2.03	120.90	5,943.71	119.15	-6.23	92.25	0.94
5,983.00	2.20	119.66	5,975.69	118.56	-5.21	92.38	0.55
6,014.00	2.52	124.63	6,006.67	117.87	-4.13	92.47	1.22
6,045.00	2.33	138.17	6,037.64	117.02	-3.15	92.36	1.94
6,075.00	1.91	154.70	6,067.62	116.11	-2.53	92.00	2.46
6,107.00	1.91	162.89	6,099.60	115.12	-2.15	91.43	0.85
6,137.00	2.22	158.71	6,129.58	114.10	-1.79	90.82	1.15
6,169.00	2.44	163.27	6,161.55	112.87	-1.37	90.08	0.90
6,199.00	2.05	165.39	6,191.53	111.74	-1.05	89.36	1.33
6,229.00	1.05	151.56	6,221.52	110.98	-0.78	88.90	3.54
6,261.00	0.70	107.34	6,253.52	110.66	-0.46	88.84	2.29
6,291.00	0.81	50.25	6,283.51	110.74	-0.12	89.11	2.43
6,322.00	0.85	43.22	6,314.51	111.05	0.21	89.55	0.35
6,352.00	0.77	44.68	6,344.51	111.36	0.50	89.97	0.28
6,384.00	0.81	43.50	6,376.50	111.67	0.81	90.41	0.13
6,415.00	0.96	34.72	6,407.50	112.05	1.11	90.88	0.65
6,446.00	0.75	36.25	6,438.50	112.42	1.37	91.34	0.68
6,476.00	0.43	19.55	6,468.50	112.69	1.53	91.65	1.20
6,507.00	0.09	42.68	6,499.50	112.81	1.58	91.78	1.13
6,538.00	0.19	43.04	6,530.50	112.87	1.64	91.86	0.32
6,569.00	0.07	300.10	6,561.50	112.92	1.65	91.91	0.70
6,599.00	0.12	149.27	6,591.50	112.90	1.65	91.89	0.61
6,630.00	0.13	177.19	6,622.50	112.84	1.67	91.85	0.20
6,660.00	0.22	97.95	6,652.50	112.79	1.73	91.86	0.78
6,691.00	0.29	190.69	6,683.49	112.71	1.78	91.81	1.20
6,721.00	0.33	142.55	6,713.49	112.57	1.81	91.72	0.85
6,752.00	0.37	164.36	6,744.49	112.40	1.90	91.63	0.45
6,783.00	0.37	164.98	6,775.49	112.21	1.95	91.51	0.01
6,815.00	0.48	162.11	6,807.49	111.98	2.02	91.37	0.35
6,847.00	0.69	174.48	6,839.49	111.66	2.08	91.15	0.76
6,877.00	0.68	169.55	6,869.49	111.30	2.13	90.89	0.20
6,907.00	0.93	165.26	6,899.49	110.89	2.22	90.61	0.86



## Design Report for Ron Lamb 31A-4-1 - Plan #1 - Gyrodata Gyro and Sperry MWD Survey

Measured Depth (ft)	Inclination (°)	Azimuth (°)	Vertical Depth (ft)	+N/-S (ft)	+E/-W (ft)	Vertical Section (ft)	Dogleg Rate (°/100ft)
6,938.00	0.96	166.39	6,930.48	110.40	2.34	90.29	0.11
6,969.00	0.95	158.05	6,961.48	109.91	2.50	89.99	0.45
7,000.00	1.08	167.81	6,992.47	109.38	2.66	89.66	0.70
7,031.00	1.28	168.77	7,023.47	108.76	2.79	89.23	0.65
7,063.00	1.23	170.50	7,055.46	108.07	2.92	88.75	0.20
7,093.00	1.35	166.58	7,085.45	107.41	3.05	88.30	0.50
7,125.00	1.32	167.18	7,117.44	106.68	3.22	87.82	0.10
7,156.00	1.24	162.96	7,148.43	106.01	3.40	87.38	0.40
7,187.00	1.27	157.41	7,179.43	105.37	3.63	87.00	0.40
7,218.00	1.12	164.45	7,210.42	104.77	3.84	86.64	0.68
7,249.00	1.45	165.56	7,241.41	104.09	4.02	86.21	1.07
7,279.00	1.32	153.58	7,271.40	103.42	4.27	85.81	1.06
7,310.00	1.53	157.67	7,302.39	102.71	4.58	85.43	0.75
7,340.00	1.48	156.21	7,332.38	101.99	4.89	85.03	0.21
7,372.00	1.49	150.93	7,364.37	101.25	5.26	84.65	0.43
7,402.00	1.76	158.68	7,394.36	100.48	5.62	84.24	1.16
7,432.00	1.72	147.94	7,424.35	99.67	6.02	83.83	1.09
7,464.00	1.92	149.95	7,456.33	98.80	6.55	83.44	0.66
7,494.00	2.26	161.67	7,486.31	97.80	6.99	82.90	1.81
7,525.00	2.27	168.33	7,517.29	96.62	7.30	82.13	0.85
7,555.00	2.22	171.89	7,547.26	95.46	7.50	81.32	0.49
7,585.00	1.64	156.35	7,577.25	94.49	7.76	80.69	2.59
7,616.00	1.34	146.10	7,608.24	93.78	8.14	80.35	1.29
7,647.00	1.55	158.12	7,639.23	93.09	8.50	80.00	1.19
7,679.00	1.48	163.23	7,671.22	92.30	8.78	79.53	0.48
7,711.00	1.70	176.78	7,703.20	91.43	8.92	78.91	1.36
7,741.00	2.00	178.04	7,733.19	90.46	8.97	78.16	1.01
7,772.00	1.91	179.97	7,764.17	89.40	8.99	77.32	0.36
7,802.00	2.08	190.03	7,794.15	88.37	8.89	76.43	1.30
7,833.00	2.11	184.49	7,825.13	87.24	8.75	75.44	0.66
7,863.00	2.35	186.50	7,855.11	86.08	8.64	74.44	0.84
7,895.00	2.35	183.25	7,887.08	84.78	8.52	73.32	0.42
7,925.00	2.52	181.95	7,917.05	83.50	8.47	72.26	0.60
7,955.00	2.25	181.78	7,947.03	82.25	8.43	71.23	0.90
7,986.00	1.90	180.90	7,978.01	81.13	8.40	70.31	1.13
8,016.00	1.80	177.37	8,007.99	80.16	8.41	69.54	0.51
8,046.00	2.12	179.64	8,037.97	79.14	8.44	68.73	1.10
8,077.00	2.03	180.79	8,068.95	78.02	8.43	67.82	0.32
8,107.00	2.04	177.56	8,098.93	76.95	8.45	66.98	0.38
8,137.00	2.49	178.53	8,128.91	75.77	8.49	66.05	1.51
8,168.00	2.32	174.57	8,159.88	74.47	8.57	65.05	0.77
8,200.00	2.49	172.39	8,191.86	73.14	8.72	64.06	0.60
8,232.00	2.62	171.98	8,223.82	71.72	8.91	63.04	0.41
8,262.00	2.80	171.37	8,253.79	70.32	9.12	62.03	0.61
8,294.00	2.34	181.08	8,285.76	68.89	9.22	60.95	1.97
8,324.00	2.19	180.94	8,315.73	67.71	9.20	59.98	0.50
8,356.00	2.24	192.34	8,347.71	66.49	9.06	58.91	1.38
8,386.00	1.93	190.60	8,377.69	65.42	8.84	57.92	1.05
8,416.00	2.01	183.64	8,407.67	64.39	8.71	57.02	0.84
8,447.00	1.93	185.98	8,438.66	63.33	8.63	56.11	0.37

## Design Report for Ron Lamb 31A-4-1 - Plan #1 - Gyrodata Gyro and Sperry MWD Survey

Measured Depth (ft)	Inclination (°)	Azimuth (°)	Vertical Depth (ft)	+N/-S (ft)	+E/-W (ft)	Vertical Section (ft)	Dogleg Rate (°/100ft)
8,477.00	1.88	179.28	8,468.64	62.34	8.58	55.29	0.76
8,509.00	1.83	179.39	8,500.62	61.30	8.59	54.46	0.16
8,539.00	2.18	181.10	8,530.60	60.25	8.58	53.61	1.18
8,570.00	2.29	176.07	8,561.58	59.05	8.62	52.66	0.73
8,601.00	2.27	181.50	8,592.56	57.81	8.64	51.68	0.70
8,632.00	2.31	181.85	8,623.53	56.58	8.61	50.66	0.14
8,663.00	1.95	186.19	8,654.51	55.43	8.53	49.69	1.27
8,695.00	1.95	187.44	8,686.49	54.35	8.40	48.74	0.13
8,725.00	1.91	182.31	8,716.47	53.34	8.31	47.88	0.59
8,757.00	1.90	183.17	8,748.46	52.28	8.26	47.00	0.09
8,789.00	1.81	174.30	8,780.44	51.25	8.28	46.18	0.94
8,819.00	1.92	179.45	8,810.42	50.27	8.34	45.42	0.67
8,851.00	2.06	176.97	8,842.40	49.16	8.37	44.55	0.51
8,882.00	2.17	176.15	8,873.38	48.02	8.44	43.67	0.37
8,913.00	2.31	177.35	8,904.36	46.81	8.51	42.74	0.48
8,943.00	2.16	173.58	8,934.34	45.64	8.60	41.85	0.70
8,973.00	2.37	175.09	8,964.31	44.46	8.72	40.97	0.73
9,004.00	2.26	175.33	8,995.29	43.22	8.82	40.03	0.36
9,034.00	2.16	179.10	9,025.27	42.06	8.88	39.13	0.59
9,065.00	1.85	186.01	9,056.25	40.98	8.83	38.24	1.27
9,095.00	1.72	186.98	9,086.23	40.05	8.73	37.43	0.44
9,125.00	1.67	188.55	9,116.22	39.17	8.61	36.65	0.23
9,157.00	1.72	191.85	9,148.20	38.24	8.44	35.80	0.34
9,187.00	1.81	191.33	9,178.19	37.34	8.26	34.96	0.30
9,218.00	1.86	189.05	9,209.17	36.36	8.08	34.07	0.29
9,248.00	1.94	186.64	9,239.16	35.37	7.95	33.20	0.38
9,280.00	2.06	184.19	9,271.14	34.26	7.84	32.24	0.46
9,310.00	2.17	182.07	9,301.12	33.16	7.78	31.31	0.45
9,342.00	2.18	182.39	9,333.10	31.94	7.73	30.31	0.05
9,372.00	2.11	185.18	9,363.07	30.82	7.66	29.36	0.42
9,403.00	2.01	185.62	9,394.05	29.71	7.55	28.41	0.33
9,434.00	1.97	184.68	9,425.04	28.64	7.46	27.49	0.17
9,466.00	1.82	188.28	9,457.02	27.59	7.34	26.57	0.60
9,498.00	1.88	189.19	9,489.00	26.57	7.18	25.65	0.21
9,528.00	1.84	193.02	9,518.99	25.61	7.00	24.77	0.44
9,558.00	1.96	193.30	9,548.97	24.65	6.77	23.86	0.40
9,590.00	2.10	199.39	9,580.95	23.56	6.45	22.80	0.80
9,620.00	2.17	198.34	9,610.93	22.50	6.09	21.73	0.27
9,651.00	2.17	193.53	9,641.91	21.37	5.77	20.63	0.59
9,682.00	1.89	194.20	9,672.89	20.31	5.50	19.62	0.91
9,713.00	1.96	192.35	9,703.87	19.30	5.26	18.66	0.30
9,743.00	1.87	191.29	9,733.85	18.31	5.06	17.75	0.32
9,774.00	1.85	189.89	9,764.84	17.33	4.87	16.84	0.16
9,805.00	1.92	186.17	9,795.82	16.32	4.73	15.94	0.45
9,836.00	1.72	182.30	9,826.80	15.33	4.66	15.11	0.76
9,867.00	1.73	177.62	9,857.79	14.40	4.66	14.36	0.46
9,898.00	1.56	171.32	9,888.78	13.52	4.74	13.70	0.80
9,928.00	1.64	160.78	9,918.76	12.71	4.94	13.17	1.01
9,960.00	1.56	156.17	9,950.75	11.88	5.27	12.69	0.47
9,990.00	1.73	147.99	9,980.74	11.12	5.68	12.32	0.96

## Design Report for Ron Lamb 31A-4-1 - Plan #1 - Gyrodata Gyro and Sperry MWD Survey

Measured Depth (ft)	Inclination (°)	Azimuth (°)	Vertical Depth (ft)	+N/-S (ft)	+E/-W (ft)	Vertical Section (ft)	Dogleg Rate (°/100ft)
10,021.00	1.68	138.14	10,011.73	10.38	6.23	12.05	0.96
10,052.00	1.85	132.32	10,042.71	9.71	6.90	11.91	0.80
10,083.00	1.81	123.65	10,073.70	9.10	7.68	11.88	0.90
10,113.00	2.03	121.02	10,103.68	8.57	8.53	11.95	0.79
10,145.00	2.20	115.77	10,135.66	8.01	9.57	12.12	0.80
10,168.00	2.53	116.00	10,158.64	7.59	10.42	12.29	1.44
10,199.00	2.23	101.59	10,189.61	7.17	11.63	12.67	2.15
10,230.00	2.84	101.15	10,220.58	6.90	12.97	13.25	1.97
10,261.00	2.68	98.77	10,251.54	6.64	14.44	13.91	0.63
10,291.00	1.72	128.13	10,281.52	6.26	15.49	14.22	4.84
10,322.00	1.87	120.28	10,312.51	5.71	16.29	14.26	0.93
10,353.00	0.92	154.89	10,343.50	5.23	16.83	14.20	3.97
10,385.00	0.41	187.17	10,375.50	4.89	16.93	13.97	1.92
10,416.00	0.98	168.08	10,406.49	4.52	16.97	13.70	1.96
10,447.00	0.68	168.83	10,437.49	4.08	17.06	13.40	0.97
10,508.00	1.11	145.65	10,498.48	3.24	17.46	12.96	0.91
10,569.00	1.11	134.80	10,559.47	2.33	18.21	12.68	0.34
10,599.00	1.29	137.71	10,589.47	1.88	18.65	12.57	0.63
10,629.00	1.01	128.41	10,619.46	1.46	19.08	12.49	1.12
10,690.00	0.15	71.69	10,680.46	1.15	19.58	12.54	1.53
10,751.00	0.42	111.37	10,741.46	1.10	19.86	12.66	0.52
10,813.00	0.33	150.35	10,803.45	0.86	20.16	12.65	0.43
10,874.00	0.50	134.80	10,864.45	0.52	20.44	12.54	0.33
10,936.00	0.91	70.85	10,926.45	0.49	21.10	12.90	1.33
10,997.00	1.68	55.17	10,987.43	1.16	22.29	14.15	1.38
11,028.00	1.38	64.32	11,018.42	1.58	23.00	14.91	1.25
11,059.00	2.05	48.76	11,049.41	2.11	23.75	15.78	2.61
11,090.00	1.59	60.61	11,080.39	2.68	24.54	16.71	1.91
11,120.00	1.31	82.25	11,110.38	2.94	25.25	17.33	2.03
11,152.00	2.07	61.31	11,142.37	3.26	26.11	18.11	3.02
11,182.00	2.19	68.27	11,172.35	3.73	27.12	19.09	0.95
11,213.00	2.43	67.47	11,203.32	4.21	28.28	20.15	0.78
11,244.00	2.34	75.88	11,234.30	4.61	29.50	21.21	1.16
11,275.00	2.01	74.93	11,265.27	4.91	30.64	22.12	1.07
11,305.00	2.01	80.74	11,295.26	5.13	31.67	22.91	0.68
11,337.00	1.59	82.11	11,327.24	5.28	32.66	23.62	1.32
11,368.00	1.29	69.48	11,358.23	5.46	33.41	24.21	1.40
11,398.00	1.65	60.59	11,388.22	5.79	34.11	24.89	1.42
11,429.00	1.86	65.83	11,419.21	6.22	34.95	25.73	0.85
11,459.00	1.68	61.20	11,449.19	6.63	35.78	26.55	0.77
11,489.00	1.98	50.59	11,479.18	7.17	36.57	27.46	1.50
11,520.00	1.98	64.40	11,510.16	7.74	37.47	28.45	1.54
11,550.00	1.66	78.12	11,540.14	8.05	38.36	29.23	1.79
11,581.00	1.36	68.41	11,571.13	8.28	39.14	29.88	1.27
11,613.00	1.53	79.11	11,603.12	8.50	39.91	30.51	0.99
11,643.00	1.57	79.40	11,633.11	8.65	40.71	31.11	0.14
11,673.00	1.97	80.43	11,663.10	8.81	41.62	31.78	1.34
11,705.00	1.97	82.13	11,695.08	8.98	42.71	32.56	0.18
11,737.00	1.58	85.87	11,727.06	9.09	43.69	33.23	1.27
11,769.00	1.50	78.07	11,759.05	9.21	44.54	33.82	0.70

## Design Report for Ron Lamb 31A-4-1 - Plan #1 - Gyrodata Gyro and Sperry MWD Survey

Measured Depth (ft)	Inclination (°)	Azimuth (°)	Vertical Depth (ft)	+N/-S (ft)	+E/-W (ft)	Vertical Section (ft)	Dogleg Rate (°/100ft)
11,800.00	0.88	87.55	11,790.04	9.30	45.18	34.28	2.09
11,819.00	0.16	83.93	11,809.04	9.31	45.35	34.39	3.79
11,831.00	0.39	246.43	11,821.04	9.30	45.33	34.36	4.54
11,847.00	1.05	251.79	11,837.04	9.23	45.14	34.20	4.14
11,863.00	1.88	248.64	11,853.04	9.09	44.76	33.85	5.21
11,895.00	1.38	260.22	11,885.02	8.83	43.89	33.13	1.86
11,927.00	2.14	278.77	11,917.01	8.86	42.92	32.58	2.94
11,959.00	2.43	272.49	11,948.98	8.98	41.65	31.92	1.20
11,989.00	2.55	268.48	11,978.95	8.99	40.35	31.16	0.70
12,022.00	2.37	272.90	12,011.92	9.00	38.93	30.33	0.79
12,054.00	2.41	273.42	12,043.90	9.07	37.60	29.60	0.14
12,086.00	2.13	275.26	12,075.87	9.17	36.34	28.93	0.90
12,118.00	1.73	271.17	12,107.85	9.23	35.26	28.34	1.32
12,150.00	1.87	267.22	12,139.84	9.22	34.26	27.73	0.58
12,182.00	1.99	282.15	12,171.82	9.31	33.19	27.18	1.61
12,214.00	2.31	279.31	12,203.80	9.53	32.01	26.66	1.05
12,246.00	2.37	281.55	12,235.77	9.77	30.73	26.08	0.34
12,277.00	1.80	293.36	12,266.75	10.09	29.65	25.71	2.29
12,309.00	2.55	286.08	12,298.73	10.49	28.51	25.35	2.49
12,341.00	2.50	283.18	12,330.69	10.84	27.14	24.82	0.43
12,373.00	2.46	289.58	12,362.66	11.23	25.82	24.35	0.87
12,405.00	3.01	284.26	12,394.63	11.67	24.36	23.84	1.89
12,437.00	2.73	282.44	12,426.59	12.04	22.80	23.21	0.92
12,469.00	2.88	284.79	12,458.55	12.41	21.28	22.61	0.59
12,488.00	3.06	284.19	12,477.52	12.66	20.32	22.24	0.96
12,520.00	2.98	284.62	12,509.48	13.07	18.69	21.61	0.26
12,551.00	3.00	286.89	12,540.44	13.51	17.13	21.04	0.39
12,583.00	2.98	285.93	12,572.39	13.99	15.53	20.47	0.17
12,604.00	2.97	285.51	12,593.37	14.28	14.48	20.09	0.11
<b>Final Sperry MWD Survey</b>							
12,670.00	2.97	285.51	12,659.28	15.19	11.19	18.87	0.00
<b>Survey Projection to TD of Sperry Directional Work</b>							

### Design Annotations

Measured Depth (ft)	Vertical Depth (ft)	Local Coordinates +N/-S (ft)	+E/-W (ft)	Comment
200.00	200.00	0.63	-0.20	Surveys from 200.00ft to 2940.00ft are Gyrodata Gyro Surveys
2,940.00	2,938.99	59.75	1.90	Tie-On to Gyrodata Gyro Survey
3,025.00	3,023.85	63.96	-0.68	First Sperry MWD Survey
12,604.00	12,593.37	14.28	14.48	Final Sperry MWD Survey
12,670.00	12,659.28	15.19	11.19	Survey Projection to TD of Sperry Directional Work

### Vertical Section Information

Angle Type	Target	Azimuth (°)	Origin Type	Origin +N/-S (ft)	+E/-W (ft)	Start TVD (ft)
TD	No Target (Freehand)	36.36	Slot	0.00	0.00	0.00

---

**Design Report for Ron Lamb 31A-4-1 - Plan #1 - Gyrodata Gyro and Sperry MWD Survey**

---


**Survey tool program**

<b>From (ft)</b>	<b>To (ft)</b>	<b>Survey/Plan</b>	<b>Survey Tool</b>
200.00	2,940.00	Gyrodata Gyro Surveys	NS-GYRO-MS
3,025.00	12,670.00	Sperry MWD Surveys	MWD

Project: Sanpete County, UT  
Site: Sec. 31-T15S-R3E  
Well: Ron Lamb 31A-4-1  
Wellbore: Plan #1

# Petro-Hunt, LLC

HALLIBURTON




Project: Sanpete County, UT  
Site: Sec. 31-T15S-R3E  
Well: Ron Lamb 31A-4-1

# Petro-Hunt, LLC

HALLIBURTON

## LEGEND

- Ron Lamb 31A-4-1, Plan #1, Plan #1 Proposal V0
- Gyrodata Gyro and Sperry MWD Survey





**SURVEY REPORT**

**Petro Hunt, LLC.**

**Ron Lamb #31A-4-1**

**Unit #109**

**Sanpete County, Utah**

**RM1208GW957**

**December 31, 2008**





**Gyrodata Incorporated**

301 Thelma Dr. #433  
Casper, Wyoming 82609

307/234-7241

Fax: 307/234-6309

**SURVEY REPORT**

**Petro Hunt, LLC.**

**Ron Lamb #31A-4-1**

**Unit #109**

**Sanpete County, Utah**

**RM1208GW957**

**December 31, 2008**

**RECEIVED**

**JUL 26 2010**

**DIV. OF OIL, GAS & MINING**



**Gyrodata Incorporated**

301 Thelma Dr. #433  
Casper, Wyoming 82609

307/234-7241  
Fax: 307/234-6309

December 31, 2008

Petro Hunt, LLC.  
258 119<sup>th</sup> Ave. SW  
Killdeer, ND 85640

Re: **Ron Lamb #31A-4-1**  
**Sanpete County, Utah**

Enclosed, please find one (1) original and one (1) disk of the completed survey for the above referenced well.

We would like to take this opportunity to thank you for using Gyrodata, and we look forward to serving you in the future.

Sincerely,

A handwritten signature in black ink, appearing to read "JS", written over a horizontal line.

Joel Sulzen  
Operations Manager

JS:mg

A Gyrodata Directional Survey

for

PETRO HUNT, LLC.

Lease: Ron Lamb Well: 31A-4-1, 4" Drillpipe

Location: Unit #109, Sanpete County, Utah

Job Number: RM1208GW957

Run Date: 12/30/2008 8:28:37 AM

Surveyor: Matt Le Bas

Calculation Method: MINIMUM CURVATURE

Survey Latitude: 39.470900 deg. N Longitude: 111.623050 deg. W

Azimuth Correction:

Gyro: Bearings are Relative to True North

Vertical Section Calculated from Well Head Location

Closure Calculated from Well Head Location

Horizontal Coordinates Calculated from Well Head Location

# A Gyrodata Directional Survey

Petro Hunt, LLC.

Lease: Ron Lamb Well: 31A-4-1, 4" Drillpipe

Location: Unit #109, Sanpete County, Utah

Job Number: RM1208GW957

MEASURED DEPTH feet	I N C L deg.	AZIMUTH deg.	BORE HOLE BEARING deg. min.	DOGLEG SEVERITY deg./ 100 ft.	VERTICAL DEPTH feet	CLOSURE DIST. feet	AZIMUTH deg.	HORIZONTAL COORDINATES feet	
0.00	0.00	0.00	N 0 0 E	0.00	0.00	0.0	0.0	0.00 N	0.00 E
-----									
0 - 2940 FT RATE GYROSCOPIC MULTISHOT SURVEY RUN INSIDE 3-1/2" DRILLPIPE									
ALL MEASURED DEPTHS AND COORDINATES REFERENCED TO UNIT #109 R.K.B. 30 FT									
DEPTHS AS PER COMPANY MAN									
-----									
200.00	0.38	342.58	N 17 25 W	0.19	200.00	0.7	342.6	0.64 N	0.20 W
400.00	0.67	3.33	N 3 20 E	0.17	399.99	2.5	352.3	2.45 N	0.33 W
600.00	0.44	22.04	N 22 3 E	0.15	599.98	4.3	0.3	4.33 N	0.02 E
800.00	0.56	18.12	N 18 7 E	0.06	799.97	6.0	5.9	5.96 N	0.61 E
1000.00	0.61	12.97	N 12 58 E	0.04	999.96	8.0	8.3	7.92 N	1.15 E
1100.00	0.52	350.94	N 9 4 W	0.24	1099.96	9.0	7.7	8.89 N	1.20 E
1200.00	0.73	26.61	N 26 37 E	0.43	1199.95	10.0	8.1	9.91 N	1.42 E
1300.00	0.76	26.00	N 26 0 E	0.03	1299.94	11.3	10.2	11.08 N	1.99 E
1400.00	0.60	22.14	N 22 9 E	0.17	1399.94	12.4	11.5	12.16 N	2.48 E
1500.00	0.96	24.34	N 24 21 E	0.36	1499.93	13.7	12.7	13.41 N	3.02 E
1600.00	0.93	31.25	N 31 15 E	0.12	1599.91	15.3	14.3	14.86 N	3.79 E
1700.00	1.46	27.60	N 27 36 E	0.54	1699.89	17.4	16.0	16.68 N	4.80 E
1800.00	1.69	28.11	N 28 6 E	0.23	1799.85	20.0	17.7	19.10 N	6.08 E
1900.00	1.93	22.22	N 22 13 E	0.31	1899.80	23.2	18.6	21.96 N	7.41 E
2000.00	1.93	19.37	N 19 22 E	0.10	1999.75	26.5	18.9	25.11 N	8.61 E
2100.00	2.22	14.40	N 14 24 E	0.34	2099.68	30.2	18.7	28.58 N	9.65 E
2200.00	2.34	10.71	N 10 42 E	0.19	2199.60	34.1	17.9	32.46 N	10.51 E
2300.00	2.31	2.00	N 2 0 E	0.35	2299.52	38.1	16.7	36.48 N	10.96 E
2400.00	2.29	356.71	N 3 17 W	0.21	2399.44	41.9	15.1	40.49 N	10.91 E

# A Gyrodata Directional Survey

Petro Hunt, LLC.

Lease: Ron Lamb Well: 31A-4-1, 4" Drillpipe

Location: Unit #109, Sanpete County, Utah

Job Number: RM1208GW957

MEASURED DEPTH feet	I N C L deg.	AZIMUTH deg.	BORE HOLE BEARING deg. min.	DOGLEG SEVERITY deg./ 100 ft.	VERTICAL DEPTH feet	CLOSURE DIST. AZIMUTH feet deg.	HORIZONTAL COORDINATES feet
2500.00	2.08	350.21	N 9 47 W	0.32	2499.37	45.5 13.3	44.26 N 10.49 E
2600.00	1.90	338.71	N 21 18 W	0.44	2599.31	48.5 11.4	47.59 N 9.58 E
2700.00	2.06	331.68	N 28 19 W	0.29	2699.25	51.4 9.1	50.72 N 8.13 E
2800.00	2.57	326.16	N 33 50 W	0.55	2799.17	54.5 6.3	54.16 N 6.03 E
2900.00	2.95	322.22	N 37 47 W	0.43	2899.05	58.1 3.2	58.06 N 3.20 E
2940.00	3.16	321.65	N 38 21 W	0.52	2938.99	59.8 1.8	59.74 N 1.89 E

Final Station Closure: Distance: 59.77 ft Az: 1.81 deg.

As Measured From: 31A-4-1, 4" Drillpipe



GARY R. HERBERT  
Governor

GREGORY S. BELL  
Lieutenant Governor

# State of Utah

## DEPARTMENT OF NATURAL RESOURCES

MICHAEL R. STYLER  
Executive Director

### Division of Oil, Gas and Mining

JOHN R. BAZA  
Division Director

March 16, 2011

CERTIFIED MAIL NO.: 7005 1820 0001 5562 7883

Mr. Cary Vice  
Petro-Hunt, LLC  
1601 Elm Street, Suite 3400  
Dallas, TX 75201

43 039 30034  
Ron Lamb 31A-4-1  
15S 3E 31

Subject: Extended Shut-in and Temporary Abandoned Well Requirements for Fee or State Leases

Dear Mr. Vice:

As of January 2011, Petro-Hunt, LLC (Petro) has two (2) Fee Lease Wells (see Attachment A) that are currently in non-compliance with the requirements for extended shut-in or temporarily abandoned (SI/TA) status. One of the above listed wells (Attachment A) is past due on approved SI/TA extension, which ended September 1, 2009. Petro has not submitted necessary data with good reason for further extension on said well. Please submit the necessary data as outlined below to bring wells into compliance.

Wells SI/TA beyond twelve (12) consecutive months requires filing a Sundry Notice (R649-3-36-1). Wells with five (5) years non-activity or non-productivity shall be plugged, unless the Division grants approval for extended shut-in time upon a showing of good cause by the operator (649-3-36-1.3.3). For extended SI/TA consideration the operator shall provide the Utah Division of Oil, Gas & Mining with the following:

1. Reasons for SI/TA of the well (R649-3-36-1.1).
2. The length of time the well is expected to be SI/TA (R649-3-36-1.2), and
3. An explanation and supporting data if necessary, for showing the well has integrity, meaning that the casing, cement, equipment condition, static fluid level, pressure, existence or absence of Underground Sources of Drinking Water and other factors do not make the well a risk to public health and safety or the environment (R649-3-36-1.3).

Please note that the Divisions preferred method for showing well integrity is by MIT

Page 2  
Petro-Hunt, LLC  
March 16, 2011

Submitting the information suggested below may help show well integrity and may help qualify your well for extended SI/TA. **Note: As of July 1, 2003, wells in violation of the SI/TA rule R649-3-36 may be subject to full cost bonding (R649-3-1-4.2, 4.3).**

1. Wellbore diagram, and
2. Copy of recent casing pressure test, and
3. Current pressures on the wellbore (tubing pressure, casing pressure, and casing/casing annuli pressure) showing wellbore has integrity, and
4. Fluid level in the wellbore, and
5. An explanation of how the submitted information proves integrity.

If the required information is not received within 30 days of the date of this notice, further actions may be initiated. If you have any questions concerning this matter, please contact me at (801) 538-5281.

Sincerely,



Dustin K. Doucet  
Petroleum Engineer

DKD/JP/js  
Enclosure  
cc: Compliance File  
Well File

N:\O&G Reviewed Docs\ChronFile\PetroleumEngineer\SITA

# ATTACHMENT A

	Well Name	API	LEASE	Years Inactive
<b>1<sup>ST</sup> NOTICE</b>				
→ 1	RON LAMB 31A-4-1	43-039-30034	FEE	1 Year 11 Months
<b>PAST DUE SI/TA EXTENSION as of 9/1/2009</b>				
2	VHCF 35A-3-1	43-039-30033	FEE	3 Years 10 Months



**STATE OF UTAH**  
DEPARTMENT OF NATURAL RESOURCES  
DIVISION OF OIL, GAS AND MINING

FORM 9

**SUNDRY NOTICES AND REPORTS ON WELLS**

Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.

1. TYPE OF WELL OIL WELL <input checked="" type="checkbox"/> GAS WELL <input type="checkbox"/> OTHER <u>SI / TA WELL</u>		5. LEASE DESIGNATION AND SERIAL NUMBER: <b>PATENTED</b>
2. NAME OF OPERATOR: <b>PETRO-HUNT, L. L. C.</b>		6. IF INDIAN, ALLOTTEE OR TRIBE NAME: <b>N/A</b>
3. ADDRESS OF OPERATOR: <b>258 119TH AVENUE SW</b> CITY: <b>KILLDEER</b> STATE: <b>ND</b> ZIP: <b>58640</b>		7. UNIT or CA AGREEMENT NAME: <b>N/A</b>
4. LOCATION OF WELL FOOTAGES AT SURFACE: <b>1569' FNL &amp; 1154' FEL</b>		8. WELL NAME and NUMBER: <b>RON LAMB 31A-4-1</b>
PHONE NUMBER: <b>(701) 863-6622</b>		9. API NUMBER: <b>4303930034</b>
QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: <b>SENE 31 15S 03E S</b>		10. FIELD AND POOL, OR WILDCAT: <b>WILDCAT</b>
COUNTY: <b>SANPETE</b>		STATE: <b>UTAH</b>

11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION		
<input checked="" type="checkbox"/> NOTICE OF INTENT (Submit in Duplicate) Approximate date work will start: <u>5/15/2011</u>	<input type="checkbox"/> ACIDIZE	<input type="checkbox"/> DEEPEN	<input type="checkbox"/> REPERFORATE CURRENT FORMATION
<input type="checkbox"/> SUBSEQUENT REPORT (Submit Original Form Only) Date of work completion: _____	<input type="checkbox"/> ALTER CASING	<input type="checkbox"/> FRACTURE TREAT	<input type="checkbox"/> SIDETRACK TO REPAIR WELL
	<input type="checkbox"/> CASING REPAIR	<input type="checkbox"/> NEW CONSTRUCTION	<input type="checkbox"/> TEMPORARILY ABANDON
	<input type="checkbox"/> CHANGE TO PREVIOUS PLANS	<input type="checkbox"/> OPERATOR CHANGE	<input type="checkbox"/> TUBING REPAIR
	<input type="checkbox"/> CHANGE TUBING	<input checked="" type="checkbox"/> PLUG AND ABANDON	<input type="checkbox"/> VENT OR FLARE
	<input type="checkbox"/> CHANGE WELL NAME	<input type="checkbox"/> PLUG BACK	<input type="checkbox"/> WATER DISPOSAL
	<input type="checkbox"/> CHANGE WELL STATUS	<input type="checkbox"/> PRODUCTION (START/RESUME)	<input type="checkbox"/> WATER SHUT-OFF
	<input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS	<input type="checkbox"/> RECLAMATION OF WELL SITE	<input type="checkbox"/> OTHER: _____
	<input type="checkbox"/> CONVERT WELL TYPE	<input type="checkbox"/> RECOMPLETE - DIFFERENT FORMATION	

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.

THE SUBJECT WELL WAS TEMPORARILY ABANDONED ACCORDING TO APPROVED PROCEDURES ON 02/25/2009. OUR TEMPORARY ABANDONMENT PROCEDURE HAS INSURED THAT THERE IS NO RISK TO PUBLIC HEALTH AND SAFETY OR THE ENVIRONMENT. PETRO-HUNT, L. L. C. HAS PLANS TO FINALIZE THE PLUG AND ABANDONMENT OPERATION IN MAY 2011, WHEN THE WEATHER PERMITS. AT THAT TIME, THE WELLHEADS WILL BE REMOVED AND THE CASING STRINGS WILL BE CUT BELOW GROUND LEVEL AND A STEEL PLATE WILL BE WELDED ACROSS THE CASING STUBS.

I HAVE ATTACHED THE "ACTUAL TA SCHEMATIC" OF SUBJECT WELL.

**COPY SENT TO OPERATOR**

Date: 3.31.2011

Initials: KS

NAME (PLEASE PRINT) Cary J. Vice

TITLE Sr. Drilling Engineer

SIGNATURE Cary J. Vice

DATE 3/29/2011

(This space for State use only)

**APPROVED BY THE STATE  
OF UTAH DIVISION OF  
OIL, GAS, AND MINING**

**RECEIVED**

**MAR 29 2011**

DIV. OF OIL, GAS & MINING

(5/2000)


DATE: 3/29/2011 (See Instructions on Reverse Side)

BY: [Signature]

\* Valid through July 1, 2011

## DRILLING PROGRAM

COMPANY NAME	PETRO HUNT L. L. C.	DATE	6/28/2010	cjv
WELL NAME	RON LAMB 31A-4-1	TD:	12670 RKB	
FIELD	WILDCAT	PROSPECT:	WALES	
LOCATION	SECTION 31, T 15S, R 3E	STATE:	UTAH	
OBJECTIVE ZONE(S)	JURASSIC LOWER TWIN CREEK AND JURASSIC NAVAJO	COUNTY:	SANPETE	
		WATER DEPTH:	N/A	



STATE OF UTAH  
DEPARTMENT OF NATURAL RESOURCES  
DIVISION OF OIL, GAS AND MINING

FORM 9

**SUNDRY NOTICES AND REPORTS ON WELLS**

Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.

1. TYPE OF WELL OIL WELL <input type="checkbox"/> GAS WELL <input type="checkbox"/> OTHER <u>P&amp;A'd WELL</u>		5. LEASE DESIGNATION AND SERIAL NUMBER: <b>PATENTED</b>
2. NAME OF OPERATOR: <b>PETRO-HUNT, L. L. C.</b>		6. IF INDIAN, ALLOTTEE OR TRIBE NAME:
3. ADDRESS OF OPERATOR: <b>1601 ELM ST, SUITE 3400</b> CITY <b>DALLAS</b> STATE <b>TX</b> ZIP <b>75201</b>		7. UNIT or CA AGREEMENT NAME:
4. LOCATION OF WELL FOOTAGES AT SURFACE: <b>1569' FNL &amp; 1154' FEL</b>		8. WELL NAME and NUMBER: <b>RON LAMB 31A-4-1</b>
PHONE NUMBER: <b>(214) 880-8400</b>		9. API NUMBER: <b>4303930034</b>
QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: <b>SENE 31 15S 03E</b>		10. FIELD AND POOL, OR WILDCAT: <b>WILDCAT</b>

COUNTY: **SANPETE**

STATE: **UTAH**

11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION		
<input type="checkbox"/> NOTICE OF INTENT (Submit in Duplicate) Approximate date work will start: _____	<input type="checkbox"/> ACIDIZE	<input type="checkbox"/> DEEPEN	<input type="checkbox"/> REPERFORATE CURRENT FORMATION
	<input type="checkbox"/> ALTER CASING	<input type="checkbox"/> FRACTURE TREAT	<input type="checkbox"/> SIDETRACK TO REPAIR WELL
	<input type="checkbox"/> CASING REPAIR	<input type="checkbox"/> NEW CONSTRUCTION	<input type="checkbox"/> TEMPORARILY ABANDON
	<input type="checkbox"/> CHANGE TO PREVIOUS PLANS	<input type="checkbox"/> OPERATOR CHANGE	<input type="checkbox"/> TUBING REPAIR
	<input type="checkbox"/> CHANGE TUBING	<input checked="" type="checkbox"/> PLUG AND ABANDON	<input type="checkbox"/> VENT OR FLARE
<input type="checkbox"/> SUBSEQUENT REPORT (Submit Original Form Only) Date of work completion: <b>5/20/2011</b>	<input type="checkbox"/> CHANGE WELL NAME	<input type="checkbox"/> PLUG BACK	<input type="checkbox"/> WATER DISPOSAL
	<input type="checkbox"/> CHANGE WELL STATUS	<input type="checkbox"/> PRODUCTION (START/RESUME)	<input type="checkbox"/> WATER SHUT-OFF
	<input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS	<input type="checkbox"/> RECLAMATION OF WELL SITE	<input type="checkbox"/> OTHER: _____
	<input type="checkbox"/> CONVERT WELL TYPE	<input type="checkbox"/> RECOMPLETE - DIFFERENT FORMATION	


12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.

ALL CASING STRINGS WERE CUT 5' BELOW GROUND LEVEL. A STEEL PLATE WAS WELDED ACROSS THE STUB WITH THE API NUMBER ON IT.

**RECEIVED**

**JAN 26 2012**

**DIV. OF OIL, GAS & MINING**

NAME (PLEASE PRINT) <b>CARY J. VICE</b>	TITLE <b>SR. DRILLING ENGINEER</b>
SIGNATURE 	DATE <b>1/25/2012</b>

(This space for State use only)